SOLICITATION, OFFER, AND AWARD (Construction, Alteration, or Repair)	1. SOLICITATION NO. W91236-05-B-0003	2. TYPE OF SOLICITATION [X] SEALED BID (IFB) [ ] NEGOTIATED (RFP)	3. DATE ISSUED 03-Feb-2005	PAGE OF PAGES 1 OF 116

IMPORTANT - The "offer" section on the reverse must be fully completed by offeror.

4. CONTRACT NO.	5. REQUISITION/PURCHASE REQUEST NO. W26GLG-5012-8674	6. PROJECT NO.

7. ISSUED BY CODE W91236	8. ADDRESS OFFER TO (If Other Than Item 7) CODE
USA ENGINEER DISTRICT, NORFOLK CONTRACTING OFFICE 803 FRONT STREET NORFOLK VA 23510-1096 TEL: FAX: 757-441-7183	**See Item 7** TEL: FAX:

9. FOR INFORMATION CALL:	A. NAME	B. TELEPHONE NO. (Include area code) (NO COLLECT CALLS)
	CHERYL B JONES	757-441-7242

SOLICITATION

NOTE: In sealed bid solicitations "offer" and "offeror" mean "bid" and "bidder".

10. THE GOVERNMENT REQUIRES PERFORMANCE OF THE WORK DESCRIBED IN THESE DOCUMENTS (Title, identifying no., date):

MAINTENANCE DREDGING AND REALIGNMENT LYNNHAVEN INLET, BAY AND CONNECTING WATERS, VIRGINIA BEACH, VIRGINIA

The project consists of dredging by hydraulic dredge and pipeline the Entrance Channel and Turning Basin to a required depth of 11 feet, the Channel to Broad Bay to a required depth of 10 feet, Narrows Channel to a required depth of 7 feet, and the Long Creek Side Channel to a required depth of 9 feet, each with 1-foot of allowable overdepth. The work, including allowable overdepth and estimated accretion to 1 April 2005, involves dredging approximately 245,000 cubic yards of material to be transported and deposited in the Government-furnished upland and shoreline placement areas as designated for each respective dredging area.

THIS ACQUISITION IS 100% SET ASIDE FOR SMALL BUSINESS.

NAICS CODE: 237990
SIC CODE: 1629

11. The Contractor shall begin performance within 14 calendar days and complete it within 90 calendar days after receiving [ ] award, [X] notice to proceed. This performance period is [X] mandatory, [ ] negotiable. (See _____ .)

12 A. THE CONTRACTOR MUST FURNISH ANY REQUIRED PERFORMANCE AND PAYMENT BONDS? (If "YES," indicate within how many calendar days after award in Item 12B.) [X] YES [ ] NO	12B. CALENDAR DAYS 10

13. ADDITIONAL SOLICITATION REQUIREMENTS:

A. Sealed offers in original and 1 copies to perform the work required are due at the place specified in Item 8 by 02:09 PM (hour) local time 08 Mar 2005 (date). If this is a sealed bid solicitation, offers must be publicly opened at that time. Sealed envelopes containing offers shall be marked to show the offeror's name and address, the solicitation number, and the date and time offers are due.

B. An offer guarantee [X] is, [ ] is not required.

C. All offers are subject to the (1) work requirements, and (2) other provisions and clauses incorporated in the solicitation in full text or by reference.

D. Offers providing less than 30 calendar days for Government acceptance after the date offers are due will not be considered and will be rejected.

SOLICITATION, OFFER, AND AWARD (Continued)

(Construction, Alteration, or Repair)

OFFER ***(Must be fully completed by offeror)***

14. NAME AND ADDRESS OF OFFEROR *(Include ZIP Code)*		15. TELEPHONE NO. *(Include area code)*
		16. REMITTANCE ADDRESS *(Include only if different than Item 14)* **See Item 14**
CODE	FACILITY CODE	

17. The offeror agrees to perform the work required at the prices specified below in strict accordance with the terms of this solicitation, if this offer is accepted by the Government in writing within _____ calendar days after the date offers are due. *(Insert any number equal to or greater than the minimum requirements stated in Item 13D. Failure to insert any number means the offeror accepts the minimum in Item 13D.)*

AMOUNTS	SEE SCHEDULE OF PRICES

18. The offeror agrees to furnish any required performance and payment bonds.

19. ACKNOWLEDGMENT OF AMENDMENTS

(The offeror acknowledges receipt of amendments to the solicitation -- give number and date of each)

AMENDMENT NO.										
DATE										

20A. NAME AND TITLE OF PERSON AUTHORIZED TO SIGN OFFER *(Type or print)*	20B. SIGNATURE	20C. OFFER DATE

AWARD ***(To be completed by Government)***

21. ITEMS ACCEPTED:

22. AMOUNT	23. ACCOUNTING AND APPROPRIATION DATA

24. SUBMIT INVOICES TO ADDRESS SHOWN IN *(4 copies unless otherwise specified)*	**ITEM**	25. OTHER THAN FULL AND OPEN COMPETITION PURSUANT TO ☐ 10 U.S.C. 2304(c) ☐ 41 U.S.C. 253(c)
26. ADMINISTERED BY CODE		27. PAYMENT WILL BE MADE BY: CODE

CONTRACTING OFFICER WILL COMPLETE ITEM 28 OR 29 AS APPLICABLE

☐ 28. NEGOTIATED AGREEMENT *(Contractor is required to sign this document and return _ _ copies to issuing office.)* Contractor agrees to furnish and deliver all items or perform all work, requisitions identified on this form and any continuation sheets for the consideration stated in this contract. The rights and obligations of the parties to this contract shall be governed by (a) this contract award, (b) the solicitation, and (c) the clauses, representations, certifications, and specifications or incorporated by reference in or attached to this contract.

☐ 29. AWARD *(Contractor is not required to sign this document.)* Your offer on this solicitation, is hereby accepted as to the items listed. This award consummates the contract, which consists of (a) the Government solicitation and your offer, and (b) this contract award. No further contractual document is necessary.

30A. NAME AND TITLE OF CONTRACTOR OR PERSON AUTHORIZED TO SIGN *(Type or print)*		31A. NAME OF CONTRACTING OFFICER *(Type or print)* TEL: EMAIL:
30B. SIGNATURE	30C. DATE	31B. UNITED STATES OF AMERICA BY
		31C. AWARD DATE

Section 00010 - Solicitation Contract Form

TEM NO	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
001		1	Lump Sum		

FFP
MOBILIZATION AND DEMOBILIZATION
PURCHASE REQUEST NUMBER: W26GLG-5012-8674

_____

NET AMT

FOB: Destination

TEM NO	SUPPLIES/SERVICES	QUANTITY	UNIT	UNIT PRICE	AMOUNT
002		245,000	Cubic Yard		

FFP
DREDGING THE ENTRANCE CHANNEL AND TURNING BASIN TO A REQUIRED DEPTH OF 11 FEET, THE CHANNEL TO BROAD BAY TO A REQUIRED DEPTH OF 10 FEET, NARROWS CHANNEL TO A REQUIRED DEPTH OF 7 FEET, AND THE LONG CREEK SIDE CHANNEL TO A REQUIRED DEPTH OF 9 FEET, EACH WITH 1-FOOT OF ALLOWABLE OVERDEPTH, AND PLACING THE DREDGED MATERIAL WITHIN THE GOVERNMENT FURNISHED DESIGNATED PLACEMENT SITE FOR EACH RESPECTIVE DREDGING AREA, COMPLETE, INCLUDING ALL ASSOCIATED WORK AS INDICATED AND SPECIFIED. **THIS IS AN ESTIMATED QUANTITY.**

_____

NET AMT

TOTAL ESTIMATED AMOUNT BID (CLINS 0001 & 0002)……. $_____

FOB: Destination

Section 00100 - Bidding Schedule/Instructions to Bidders

CLAUSES INCORPORATED BY FULL TEXT

52.214-3 AMENDMENTS TO INVITATIONS FOR BIDS (DEC 1989)

(a) If this solicitation is amended, then all terms and conditions which are not modified remain unchanged.

(b) Bidders shall acknowledge receipt of any amendment to this solicitation (1) by signing and returning the amendment, (2) by identifying the amendment number and date in the space provided for this purpose on the form for submitting a bid, (3) by letter or telegram, or (4) by facsimile, if facsimile bids are authorized in the solicitation. The Government must receive the acknowledgment by the time and at the place specified for receipt of bids.

(End of provision)

52.214-5 SUBMISSION OF BIDS (MAR 1997)

(a) Bids and bid modifications shall be submitted in sealed envelopes or packages (unless submitted by electronic means) (1) addressed to the office specified in the solicitation, and (2) showing the time and date specified for receipt, the solicitation number, and the name and address of the bidder.

(b) Bidders using commercial carrier services shall ensure that the bid is addressed and marked on the outermost envelope or wrapper as prescribed in subparagraphs (a)(1) and (2) of this provision when delivered to the office specified in the solicitation.

(c) Telegraphic bids will not be considered unless authorized by the solicitation; however, bids may be modified or withdrawn by written or telegraphic notice.

(d) Facsimile bids, modifications, or withdrawals, will not be considered unless authorized by the solicitation.

(e) Bids submitted by electronic commerce shall be considered only if the electronic commerce method was specifically stipulated or permitted by the solicitation.

(End of provision)

52.214-6 EXPLANATION TO PROSPECTIVE BIDDERS (APR 1984)

Any prospective bidder desiring an explanation or interpretation of the solicitation, drawings, specifications, etc., must request it in writing soon enough to allow a reply to reach all prospective bidders before the submission of their bids. Oral explanations or instructions given before the award of a contract will not be binding. Any information given a prospective bidder concerning a solicitation will be furnished promptly to all other prospective bidders as an amendment to the solicitation, if that information is necessary in submitting bids or if the lack of it would be prejudicial to other prospective bidders.

(End of provision)

52.214-7 LATE SUBMISSIONS, MODIFICATIONS, AND WITHDRAWALS OF BIDS (NOV 1999)

(a) Bidders are responsible for submitting bids, and any modifications or withdrawals, so as to reach the Government office designated in the invitation for bids (IFB) by the time specified in the IFB. If no time is specified in the IFB, the time for receipt is 4:30 p.m., local time, for the designated Government office on the date that bids are due.

(b)(1) Any bid, modification, or withdrawal received at the Government office designated in the IFB after the exact time specified for receipt of bids is “late” and will not be considered unless it is received before award is made, the Contracting Officer determines that accepting the late bid would not unduly delay the acquisition; and--

(i) If it was transmitted through an electronic commerce method authorized by the IFB, it was received at the initial point of entry to the Government infrastructure not later than 5:00 p.m. one working day prior to the date specified for receipt of bids; or

(ii) There is acceptable evidence to establish that it was received at the Government installation designated for receipt of bids and was under the Government's control prior to the time set for receipt of bids.

(2) However, a late modification of an otherwise successful bid that makes its terms more favorable to the Government, will be considered at any time it is received and may be accepted.

(c) Acceptable evidence to establish the time of receipt at the Government installation includes the time/date stamp of that installation on the bid wrapper, other documentary evidence of receipt maintained by the installation, or oral testimony or statements of Government personnel.

(d) If an emergency or unanticipated event interrupts normal Government processes so that bids cannot be received at the Government office designated for receipt of bids by the exact time specified in the IFB and urgent Government requirements preclude amendment of the IFB, the time specified for receipt of bids will be deemed to be extended to the same time of day specified in the solicitation on the first work day on which normal Government processes resume.

(e) Bids may be withdrawn by written notice received at any time before the exact time set for receipt of bids. If the IFB authorizes facsimile bids, bids may be withdrawn via facsimile received at any time before the exact time set for receipt of bids, subject to the conditions specified in the provision at 52.214-31, Facsimile Bids. A bid may be withdrawn in person by a bidder or its authorized representative if, before the exact time set for receipt of bids, the identity of the person requesting withdrawal is established and the person signs a receipt for the bid.

(End of provision)

52.214-18 PREPARATION OF BIDS--CONSTRUCTION (APR 1984)

(a) Bids must be (1) submitted on the forms furnished by the Government or on copies of those forms, and (2) manually signed. The person signing a bid must initial each erasure or change appearing on any bid form.

(b) The bid form may require bidders to submit bid prices for one or more items on various bases, including--

(1) Lump sum bidding;

(2) Alternate prices;

(3) Units of construction; or

(4) Any combination of subparagraphs (1) through (3) above.

(c) If the solicitation requires bidding on all items, failure to do so will disqualify the bid. If bidding on all items is not required, bidders should insert the words "no bid" in the space provided for any item on which no price is submitted.

(d) Alternate bids will not be considered unless this solicitation authorizes their submission.

(End of provision)

52.214-19 CONTRACT AWARD--SEALED BIDDING--CONSTRUCTION (AUG 1996)

(a) The Government will evaluate bids in response to this solicitation without discussions and will award a contract to the responsible bidder whose bid, conforming to the solicitation, will be most advantageous to the Government, considering only price and the price-related factors specified elsewhere in the solicitation.

(b) The Government may reject any or all bids, and waive informalities or minor irregularities in bids received.

(c) The Government may accept any item or combination of items, unless doing so is precluded by a restrictive limitation in the solicitation or the bid.

(d) The Government may reject a bid as nonresponsive if the prices bid are materially unbalanced between line items or subline items. A bid is materially unbalanced when it is based on prices significantly less than cost for some work and prices which are significantly overstated in relation to cost for other work, and if there is a reasonable doubt that the bid will result in the lowest overall cost to the Government even though it may be the low evaluated bid, or if it is so unbalanced as to be tantamount to allowing an advance payment.

(End of provison)

52.214-5000 APPARENT CLERICAL MISTAKES (MAR 1995)--EFARS

(a) For the purpose of initial evaluations of bids, the following will be utilized in the resolving arithmetic discrepancies found on the face of bidding schedule as submitted by the bidder:

(1) Obviously misplaced decimal points will be corrected;

(2) Discrepancy between unit price and extended price, the unit price will govern;

(3) Apparent errors in extension of unit prices will be corrected;

(4) Apparent errors in addition of lump-sum and extended prices will be corrected.

(b) For the purpose of bid evaluation, the government will proceed on the assumption that the bidder intends his bid to be evaluated on basis of the unit prices, the totals arrived at by resolution of arithmetic discrepancies as provided above and the bid will be so reflected on the abstract of bids.

(c) These correction procedures shall not be used to resolve any ambiguity concerning which bid is low.

(End of statement)

52.233-2 SERVICE OF PROTEST (AUG 1996)

(a) Protests, as defined in section 33.101 of the Federal Acquisition Regulation, that are filed directly with an agency, and copies of any protests that are filed with the General Accounting Office (GAO), shall be served on the Contracting Officer (addressed as follows) by obtaining written and dated acknowledgment of receipt from

Chief, Contracting Office
USAED, Norfolk
803 Front Street
Norfolk, VA 23510-1096

(b) The copy of any protest shall be received in the office designated above within one day of filing a protest with the GAO.

(End of provision)

52.236-27 SITE VISIT (CONSTRUCTION) (FEB 1995)

(a) The clauses at 52.236-2, Differing Site Conditions, and 52.236-3, Site Investigations and Conditions Affecting the Work, will be included in any contract awarded as a result of this solicitation. Accordingly, offerors or quoters are urged and expected to inspect the site where the work will be performed.

(b) Site visits may be arranged during normal duty hours by contacting:
Name: Gregg Williams
Address: 803 Front Street, Norfolk, VA 23510-1096
Telephone: (757) 201-7616

(End of provision)

252.236-7008 CONTRACT PRICES - BIDDING SCHEDULES. (DEC 1991)

(a) The Government's payment for the items listed in the Bidding Schedule shall constitute full compensation to the Contractor for --

(1) Furnishing all plant, labor, equipment, appliances, and materials; and

(2) Performing all operations required to complete the work in conformity with the drawings and specifications.

(b) The Contractor shall include in the prices for the items listed in the Bidding Schedule all costs for work in the specifications, whether or not specifically listed in the Bidding Schedule.

E4LC02 AWARD TO RESPONSIBLE OFFEROR

Responsibility will be determined, prior to award, by the Contracting Officer, either by performing a pre-award survey or conclusions based on a previous pre-award survey and/or any performance data available. A pre-award survey will be performed and the offeror will be required to show that he has the necessary capital, experience, and owns or can procure the necessary plant or other resources to commence the work at the time prescribed in the specifications and thereafter to prosecute and complete the work safely and satisfactorily within the time specified.

E4LC04 EVIDENCE OF AUTHORITY TO SIGN OFFERS

Evidence of the authority of individuals signing offers to submit firm offers on behalf of the offeror is required except where the offer is signed, and shows that it is so signed, by: the President, Vice-President, or Secretary of an incorporated offeror; a partner in the case of a partnership; or the owner in the case of a sole proprietorship. Failure to submit with the offer satisfactory evidence of the authority of all other persons may be cause for
rejection of the offer as invalid or nonresponsive.

E4LC05 PREAWARD SAFETY CONFERENCE

a. Where an apparent low bidder, in performance of contracts during the previous three-year period, incurred one or more accidents, or where, in the opinion of the Contracting Officer, there is any question regarding this compliance with any safety or accident prevention requirement, such bidder, on request of the Contracting Officer prior to any award under this solicitation, shall attend a conference with representatives of the Contracting Officer to discuss any such accidents or non-compliance, the reason for their occurrence, and measures which will be taken to preclude any recurrence thereof.

b. Information elicited at this conference will be used by the Contracting Officer, in conjunction with other information obtained in a preaward survey, in determining the bidder's responsibility.

c. The items discussed, the preventive measures considered, and any conclusions reached in this conference shall be recorded in minutes of the meeting, which shall be authenticated by the signatures of representatives of the bidder and the Contracting Officer, and any procedures noted therein as agreed upon shall become an obligation of the bidder, along with all other safety and accident prevention requirements of the contract, if award is made to him.

E4LC06 INSPECTION OF THE SITE

Prospective bidders are invited to visit the site of the work in order to acquaint themselves as to site conditions and other problems incident to the prosecution of the work. Arrangements for inspection of the site shall be made through the Office the Area Engineer identified in the clause 52.236-27, entitled "SITE VISIT (CONSTRUCTION)."

E4LC08 MAGNITUDE OF CONSTRUCTION PROJECT

The estimated contract price of the work for this project is between $1,000,000.00 and $5,000,000.00.

E4LC09 BASIS OF AWARD

All blanks must be filled in by the bidder. A single award will be made to the lowest responsible, responsive bidder on the basis of the total price bid. Prior to making an award, a pre-award survey will be made and the low bidder will be required to show that he has the necessary capital, experience, and owns or can procure the necessary plant to commence the work at the time prescribed in the specifications and thereafter to prosecute and complete the work safely and satisfactorily within the time specified.

E4LC10 UNBALANCED OFFERS

Any offer which is materially unbalanced as to prices for the Base Items and the Optional Items may be rejected as non-responsive or otherwise not considered for award. An unbalanced offer is one which is based on prices significantly less than cost for some work and prices which are significantly overstated for other work.

E4LC23 INCURRING COSTS

The Government is not liable for any costs incurred by the offeror submitting an offer in response to this solicitation.

E4LC29 AGENTS

Offers signed by an Agent must be made in the name of the Principal and must be accompanied by evidence of said Agent’s authority to act on behalf of its Principal.

E4LC58 BID GUARANTEE (SEP 1996)

(a) Failure to furnish a bid guarantee in the proper form and amount, by the time set for opening of bids, may be cause for rejection of the bid.
(b) The bidder shall furnish a bid guarantee in the form of a firm commitment, e.g., bid bond supported by good and sufficient surety or sureties acceptable to the Government, postal money order, certified check, cashier's check, irrevocable letter of credit, or, under Treasury Department regulations, certain bonds or notes of the United States. The Contracting Officer will return bid guarantees, other than bid bonds, (1) to unsuccessful bidders as soon as practicable after the opening of bids, and (2) to the successful bidder upon execution of contractual documents and bonds (including any necessary coinsurance or reinsurance agreements), as required by the bid as accepted.
(c) The amount of the bid guarantee shall be 20 percent of the bid price or $3,000,000, whichever is less.
(d) If the successful bidder, upon acceptance of its bid by the Government within the period specified for acceptance, fails to execute all contractual documents or furnish executed bond(s) within 10 days after receipt of the forms by the bidder, the Contracting Officer may terminate the contract for default.
(e) In the event the contract is terminated for default, the bidder is liable for any cost of acquiring the work that exceeds the amount of its bid, and the bid guarantee is available to offset the difference.
(End of provision)

Section 00600 - Representations & Certifications

CLAUSES INCORPORATED BY FULL TEXT

52.203-2 CERTIFICATE OF INDEPENDENT PRICE DETERMINATION (APR 1985)

(a) The offeror certifies that --

(1) The prices in this offer have been arrived at independently, without, for the purpose of restricting competition, any consultation, communication, or agreement with any other offeror or competitor relating to –

(i) Those prices,

(ii) The intention to submit an offer, or

(iii) The methods of factors used to calculate the prices offered:

(2) The prices in this offer have not been and will not be knowingly disclosed by the offeror, directly or indirectly, to any other offeror or competitor before bid opening (in the case of a sealed bid solicitation) or contract award (in the case of a negotiated solicitation) unless otherwise required by law; and

(3) No attempt has been made or will be made by the offeror to induce any other concern to submit or not to submit an offer for the purpose of restricting competition.

(b) Each signature on the offer is considered to be a certification by the signatory that the signatory --

(1) Is the person in the offeror's organization responsible for determining the prices offered in this bid or proposal, and that the signatory has not participated and will not participate in any action contrary to subparagraphs (a)(1) through (a)(3) of this provision; or

(2) (i) Has been authorized, in writing, to act as agent for the following principals in certifying that those principals have not participated, and will not participate in any action contrary to subparagraphs (a)(1) through (a)(3) of this provison _____ (insert full name of person(s) in the offeror's organization responsible for determining the prices offered in this bid or proposal, and the title of his or her position in the offeror's organization);

(ii) As an authorized agent, does certify that the principals named in subdivision (b)(2)(i) above have not participated, and will not participate, in any action contrary to subparagraphs (a)(1) through (a)(3) above; and

(iii) As an agent, has not personally participated, and will not participate, in any action contrary to subparagraphs (a)(1) through (a)(3) of this provision.

(c) If the offeror deletes or modifies subparagraph (a)(2) of this provision, the offeror must furnish with its offer a signed statement setting forth in detail the circumstances of the disclosure.

(End of clause)

52.203-11 CERTIFICATION AND DISCLOSURE REGARDING PAYMENTS TO INFLUENCE CERTAIN FEDERAL TRANSACTIONS (APR 1991)

(a) The definitions and prohibitions contained in the clause, at FAR 52.203-12, Limitation on Payments to Influence Certain Federal

Transactions, included in this solicitation, are hereby incorporated by reference in paragraph (b) of this Certification.

(b) The offeror, by signing its offer, hereby certifies to the best of his or her knowledge and belief that on or after December 23, 1989,--

(1) No Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress on his or her behalf in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment or modification of any Federal contract, grant, loan, or cooperative agreement;

(2) If any funds other than Federal appropriated funds (including profit or fee received under a covered Federal transaction) have been paid, or will be paid to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress or an employee of a Member of Congress on his or her behalf in connection with this solicitation, the offeror shall complete and submit, with its offer, OMB standard form LLL, Disclosure of Lobbying Activities, to the Contracting Officer; and

(3) He or she will include the language of this certification in all subcontract awards at any tier and require that all recipients of subcontract awards in excess of $100,000 shall certify and disclose accordingly.

(c) Submission of this certification and disclosure is a prerequisite for making or entering into this contract imposed by section 1352, title 31, United States Code. Any person who makes an expenditure prohibited under this provision, shall be subject to a civil penalty of not less than $10,000, and not more than $100,000, for each such failure.

(End of provision)

52.204-3 TAXPAYER IDENTIFICATION (OCT 1998)

(a) Definitions.

“Common parent,” as used in this provision, means that corporate entity that owns or controls an affiliated group of corporations that files its Federal income tax returns on a consolidated basis, and of which the offeror is a member.

“Taxpayer Identification Number (TIN),” as used in this provision, means the number required by the Internal Revenue Service (IRS) to be used by the offeror in reporting income tax and other returns. The TIN may be either a Social Security Number or an Employer Identification Number.

(b) All offerors must submit the information required in paragraphs (d) through (f) of this provision to comply with debt collection requirements of 31 U.S.C. 7701(c) and 3325(d), reporting requirements of 26 U.S.C. 6041, 6041A, and 6050M, and implementing regulations issued by the IRS. If the resulting contract is subject to the payment reporting requirements described in Federal Acquisition Regulation (FAR) 4.904, the failure or refusal by the offeror to furnish the information may result in a 31 percent reduction of payments otherwise due under the contract.

(c) The TIN may be used by the Government to collect and report on any delinquent amounts arising out of the offeror's relationship with the Government (31 U.S.C. 7701(c)(3)). If the resulting contract is subject to the payment reporting requirements described in FAR 4.904, the TIN provided hereunder may be matched with IRS records to verify the accuracy of the offeror's TIN.

(d) Taxpayer Identification Number (TIN).

___ TIN:._____

___ TIN has been applied for.

___ TIN is not required because:

___ Offeror is a nonresident alien, foreign corporation, or foreign partnership that does not have income effectively connected with the conduct of a trade or business in the United States and does not have an office or place of business or a fiscal paying agent in the United States;

___ Offeror is an agency or instrumentality of a foreign government;

___ Offeror is an agency or instrumentality of the Federal Government.

(e) Type of organization.

___ Sole proprietorship;

___ Partnership;

___ Corporate entity (not tax-exempt);

___ Corporate entity (tax-exempt);

___ Government entity (Federal, State, or local);

___ Foreign government;

___ International organization per 26 CFR 1.6049-4;

___ Other _____

(f) Common parent.

___ Offeror is not owned or controlled by a common parent as defined in paragraph (a) of this provision.

___ Name and TIN of common parent:

Name _____

TIN _____

(End of provision)

52.204-5 WOMEN-OWNED BUSINESS (OTHER THAN SMALL BUSINESS) (MAY 1999)

(a) Definition. Women-owned business concern, as used in this provision, means a concern that is at least 51 percent owned by one or more women; or in the case of any publicly owned business, at least 51 percent of its stock is owned by one or more women; and whose management and daily business operations are controlled by one or more women.

(b) Representation. [Complete only if the offeror is a women-owned business concern and has not represented itself as a small business concern in paragraph (b)(1) of FAR 52.219-1, Small Business Program Representations, of this solicitation.] The offeror represents that it ( ) is a women-owned business concern.

(End of provision)

52.204-6 DATA UNIVERSAL NUMBERING SYSTEM (DUNS) NUMBER (OCT 2003)

(a) The offeror shall enter, in the block with its name and address on the cover page of its offer, the annotation “DUNS” or “DUNS+4” followed by the DUNS number or “DUNS+4” that identifies the offeror's name and address exactly as stated in the offer. The DUNS number is a nine-digit number assigned by Dun and Bradstreet, Inc. The DUNS+4 is the DUNS number plus a 4-character suffix that may be assigned at the discretion of the offeror to establish additional CCR records for identifying alternative Electronic Funds Transfer (EFT) accounts (see Subpart 32.11) for the same parent concern.

(b) If the offeror does not have a DUNS number, it should contact Dun and Bradstreet directly to obtain one.

(1) An offeror may obtain a DUNS number--

(i) If located within the United States, by calling Dun and Bradstreet at 1-866-705-5711 or via the Internet at http://www.dnb.com; or

(ii) If located outside the United States, by contacting the local Dun and Bradstreet office.

(2) The offeror should be prepared to provide the following information:

(i) Company legal business name.

(ii) Tradestyle, doing business, or other name by which your entity is commonly recognized.

(iii) Company physical street address, city, state and Zip Code.

(iv) Company mailing address, city, state and Zip Code (if separate from physical).

(v) Company telephone number.

(vi) Date the company was started.

(vii) Number of employees at your location.

(viii) Chief executive officer/key manager.

(ix) Line of business (industry).

(x) Company Headquarters name and address (reporting relationship within your entity).
(End of provision)

52.209-5 CERTIFICATION REGARDING DEBARMENT, SUSPENSION, PROPOSED DEBARMENT, AND OTHER RESPONSIBILITY MATTERS (DEC 2001)

(a)(1) The Offeror certifies, to the best of its knowledge and belief, that-

(i) The Offeror and/or any of its Principals-

(A) Are ( ) are not ( ) presently debarred, suspended, proposed for debarment, or declared ineligible for the award of contracts by any Federal agency;

(B) Have ( ) have not ( ), within a three-year period preceding this offer, been convicted of or had a civil judgment rendered against them for: commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, state, or local) contract or subcontract; violation of Federal or state antitrust statutes relating to the submission of offers; or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, tax evasion, or receiving stolen property; and

(C) Are ( ) are not ( ) presently indicted for, or otherwise criminally or civilly charged by a governmental entity with, commission of any of the offenses enumerated in paragraph (a)(1)(i)(B) of this provision.

(ii) The Offeror has ( ) has not ( ), within a three-year period preceding this offer, had one or more contracts terminated for default by any Federal agency.

(2) "Principals," for the purposes of this certification, means officers; directors; owners; partners; and, persons having primary management or supervisory responsibilities within a business entity (e.g., general manager; plant manager; head of a subsidiary, division, or business segment, and similar positions).

This Certification Concerns a Matter Within the Jurisdiction of an Agency of the United States and the Making of a False, Fictitious, or Fraudulent Certification May Render the Maker Subject to Prosecution Under Section 1001, Title 18, United States Code.

(b) The Offeror shall provide immediate written notice to the Contracting Officer if, at any time prior to contract award, the Offeror learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.

(c) A certification that any of the items in paragraph (a) of this provision exists will not necessarily result in withholding of an award under this solicitation. However, the certification will be considered in connection with a determination of the Offeror's responsibility. Failure of the Offeror to furnish a certification or provide such additional information as requested by the Contracting Officer may render the Offeror nonresponsible.

(d) Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render, in good faith, the certification required by paragraph (a) of this provision. The knowledge and information of an Offeror is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

(e) The certification in paragraph (a) of this provision is a material representation of fact upon which reliance was placed when making award. If it is later determined that the Offeror knowingly rendered an erroneous certification, in addition to other remedies available to the Government, the Contracting Officer may terminate the contract resulting from this solicitation for default.

(End of provision)

52.219-1 SMALL BUSINESS PROGRAM REPRESENTATIONS (MAY 2004)

(a)(1) The North American Industry Classification System (NAICS) code for this acquisition is 237990.

(2) The small business size standard is $17.2 Million.

(3) The small business size standard for a concern which submits an offer in its own name, other than on a construction or service contract, but which proposes to furnish a product which it did not itself manufacture, is 500 employees.

(b) Representations. (1) The offeror represents as part of its offer that it ( ) is, ( ) is not a small business concern.

(2) (Complete only if the offeror represented itself as a small business concern in paragraph (b)(1) of this provision.) The offeror represents, for general statistical purposes, that it ( ) is, ( ) is not a small disadvantaged business concern as defined in 13 CFR 124.1002.

(3) (Complete only if the offeror represented itself as a small business concern in paragraph (b)(1) of this provision.) The offeror represents as part of its offer that it ( ) is, ( ) is not a women-owned small business concern.

(4) (Complete only if the offeror represented itself as a small business concern in paragraph (b)(1) of this provision.) The offeror represents as part of its offer that it ( ) is, ( ) is not a veteran-owned small business concern.

(5) (Complete only if the offeror represented itself as a veteran-owned small business concern in paragraph (b)(4) of this provision.) The offeror represents as part of its offer that it ( ) is, ( ) is not a service-disabled veteran-owned small business concern.

(6) (Complete only if the offeror represented itself as a small business concern in paragraph (b)(1) of this provision.) The offeror represents, as part of its offer, that--

(i) It ( ) is, ( ) is not a HUBZone small business concern listed, on the date of this representation, on the List of Qualified HUBZone Small Business Concerns maintained by the Small Business Administration, and no material change in ownership and control, principal office, or HUBZone employee percentage has occurred since it was certified by the Small Business Administration in accordance with 13 CFR part 126; and

(ii) It ( ) is, ( ) is not a joint venture that complies with the requirements of 13 CFR part 126, and the representation in paragraph (b)(6)(i) of this provision is accurate for the HUBZone small business concern or concerns that are participating in the joint venture. (The offeror shall enter the name or names of the HUBZone small business concern or concerns that are participating in the joint venture:_____.) Each HUBZone small business concern participating in the joint venture shall submit a separate signed copy of the HUBZone representation.

(c) Definitions. As used in this provision--

Service-disabled veteran-owned small business concern--

(1) Means a small business concern--

(i) Not less than 51 percent of which is owned by one or more service-disabled veterans or, in the case of any publicly owned business, not less than 51 percent of the stock of which is owned by one or more service-disabled veterans; and

(ii) The management and daily business operations of which are controlled by one or more service-disabled veterans or, in the case of a service-disabled veteran with permanent and severe disability, the spouse or permanent caregiver of such veteran.

(2) Service-disabled veteran means a veteran, as defined in 38 U.S.C. 101(2), with a disability that is service-connected, as defined in 38 U.S.C. 101(16).

"Small business concern," means a concern, including its affiliates, that is independently owned and operated, not dominant in the field of operation in which it is bidding on Government contracts, and qualified as a small business under the criteria in 13 CFR Part 121 and the size standard in paragraph (a) of this provision.

Veteran-owned small business concern means a small business concern--

(1) Not less than 51 percent of which is owned by one or more veterans (as defined at 38 U.S.C. 101(2)) or, in the case of any publicly owned business, not less than 51 percent of the stock of which is owned by one or more veterans; and

(2) The management and daily business operations of which are controlled by one or more veterans.

"Women-owned small business concern," means a small business concern --

(1) That is at least 51 percent owned by one or more women; in the case of any publicly owned business, at least 51 percent of the stock of which is owned by one or more women; and

(2) Whose management and daily business operations are controlled by one or more women.

(d) Notice.

(1) If this solicitation is for supplies and has been set aside, in whole or in part, for small business concerns, then the clause in this solicitation providing notice of the set-aside contains restrictions on the source of the end items to be furnished.

(2) Under 15 U.S.C. 645(d), any person who misrepresents a firm's status as a small, HUBZone small, small disadvantaged, or women-owned small business concern in order to obtain a contract to be awarded under the preference programs established pursuant to section 8(a), 8(d), 9, or 15 of the Small Business Act or any other provision of Federal law that specifically references section 8(d) for a definition of program eligibility, shall--

(i) Be punished by imposition of fine, imprisonment, or both;

(ii) Be subject to administrative remedies, including suspension and debarment; and

(iii) Be ineligible for participation in programs conducted under the authority of the Act.

(End of provision)

52.219-2 EQUAL LOW BIDS. (OCT 1995)

(a) This provision applies to small business concerns only.

(b) The bidder's status as a labor surplus area (LSA) concern may affect entitlement to award in case of tie bids. If the bidder wishes to be considered for this priority, the bidder must identify, in the following space, the LSA in which the costs to be incurred on account of manufacturing or production (by the bidder or the first-tier subcontractors) amount to more than 50 percent of the contract price.

_____

_____

(c) Failure to identify the labor surplus area as specified in paragraph (b) of this provision will preclude the bidder from receiving priority consideration. If the bidder is awarded a contract as a result of receiving priority consideration under this provision and would not have otherwise received award, the bidder shall perform the contract or cause the contract to be performed in accordance with the obligations of an LSA concern.

52.219-19 SMALL BUSINESS CONCERN REPRESENTATION FOR THE SMALL BUSINESS COMPETITIVENESS DEMONSTRATION PROGRAM (OCT 2000)

(a) Definition.

"Emerging small business" as used in this solicitation, means a small business concern whose size is no greater than 50 percent of the numerical size standard applicable to the North American Industry Classification System (NAICS) code assigned to a contracting opportunity.

(b) [Complete only if the Offeror has represented itself under the provision at 52.219-1 as a small business concern under the size standards of this solicitation.] The Offeror [ ] is, [ ] is not an emerging small business.

(c) (Complete only if the Offeror is a small business or an emerging small business, indicating its size range.)

Offeror's number of employees for the past 12 months (check this column if size standard stated in solicitation is expressed in terms of number of employees) or Offeror's average annual gross revenue for the last 3 fiscal years (check this column if size standard stated in solicitation is expressed in terms of annual receipts). (Check one of the following.)

No. of Employees	Avg. Annual Gross Revenues
____ 50 or fewer	____ $1 million or less
____ 51 - 100	____ $1,000,001 - $2 million
____ 101 - 250	____ $2,000,001 - $3.5 million
____ 251 - 500	____ $3,500,001 - $5 million

____ 501 - 750 ____ $5,000,001 - $10 million

____ 751 - 1,000 ____ $10,000,001 - $17 million

____ Over 1,000 ____ Over $17 million

(End of provision)

52.222-21 PROHIBITION OF SEGREGATED FACILITIES (FEB 1999)

(a) Segregated facilities, as used in this clause, means any waiting rooms, work areas, rest rooms and wash rooms, restaurants and other eating areas, time clocks, locker rooms and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees, that are segregated by explicit directive or are in fact segregated on the basis of race, color, religion, sex, or national origin because of written or oral policies or employee custom. The term does not include separate or single-user rest rooms or necessary dressing or sleeping areas provided to assure privacy between the sexes.

(b) The Contractor agrees that it does not and will not maintain or provide for its employees any segregated facilities at any of its establishments, and that it does not and will not permit its employees to perform their services at any location under its control where segregated facilities are maintained. The Contractor agrees that a breach of this clause is a violation of the Equal Opportunity clause in this contract.

(c) The Contractor shall include this clause in every subcontract and purchase order that is subject to the Equal Opportunity clause of this contract.

(End of clause)

52.222-22 PREVIOUS CONTRACTS AND COMPLIANCE REPORTS (FEB 1999)

The offeror represents that --

(a) ( ) It has, ( ) has not participated in a previous contract or subcontract subject to the Equal Opportunity clause of this solicitation;

(b) ( ) It has, ( ) has not, filed all required compliance reports; and

(c) Representations indicating submission of required compliance reports, signed by proposed subcontractors, will be obtained before subcontract awards.

(End of provision)

52.223-13 CERTIFICATION OF TOXIC CHEMICAL RELEASE REPORTING (AUG 2003)

(a) Executive Order 13148, of April 21, 2000, Greening the Government through Leadership in Environmental Management, requires submission of this certification as a prerequisite for contract award.

(b) By signing this offer, the offeror certifies that--

(1) As the owner or operator of facilities that will be used in the performance of this contract that are subject to the filing and reporting requirements described in section 313 of the Emergency Planning and Community Right-to-Know Act of 1986 (EPCRA) (42 U.S.C. 11023) and section 6607 of the Pollution Prevention Act of 1990 (PPA) (42 U.S.C. 13106), the offeror will file and continue to file for such facilities for the life of the contract the Toxic Chemical Release Inventory Form (Form R) as described in sections 313(a) and (g) of EPCRA and section 6607 of PPA; or

(2) None of its owned or operated facilities to be used in the performance of this contract is subject to the Form R filing and reporting requirements because each such facility is exempt for at least one of the following reasons: (Check each block that is applicable.)

( ) (i) The facility does not manufacture, process, or otherwise use any toxic chemicals listed in 40 CFR 372.65;

( ) (ii) The facility does not have 10 or more full-time employees as specified in section 313.(b)(1)(A) of EPCRA 42 U.S.C. 11023(b)(1)(A);

( ) (iii) The facility does not meet the reporting thresholds of toxic chemicals established under section 313(f) of EPCRA, 42 U.S.C. 11023(f) (including the alternate thresholds at 40 CFR 372.27, provided an appropriate certification form has been filed with EPA);

( ) (iv) The facility does not fall within the following Standard Industrial Classification (SIC) codes or their corresponding North American Industry Classification System sectors:

(A) Major group code 10 (except 1011, 1081, and 1094.

(B) Major group code 12 (except 1241).

(C) Major group codes 20 through 39.

(D) Industry code 4911, 4931, or 4939 (limited to facilities that combust coal and/or oil for the purpose of generating power for distribution in commerce).

(E) Industry code 4953 (limited to facilities regulated under the Resource Conservation and Recovery Act, Subtitle C (42 U.S.C. 6921, et seq.), 5169, 5171, or 7389 (limited to facilities primarily engaged in solvent recovery services on a contract or fee basis); or

( ) (v) The facility is not located within the United States or its outlying areas.

(End of clause)

252.209-7001 DISCLOSURE OF OWNERSHIP OR CONTROL BY THE GOVERNMENT OF A TERRORIST COUNTRY (SEP 2004)

(a) "Definitions."

As used in this provision --

(a) "Government of a terrorist country" includes the state and the government of a terrorist country, as well as any political subdivision, agency, or instrumentality thereof.

(2) "Terrorist country" means a country determined by the Secretary of State, under section 6(j)(1)(A) of the Export Administration Act of 1979 (50 U.S.C. App. 2405(j)(i)(A)), to be a country the government of which has repeatedly provided support for such acts of international terrorism. As of the date of this provision, terrorist countries subject to this provision include: Cuba, Iran, Libya, North Korea, Sudan, and Syria.

(3) "Significant interest" means --

(i) Ownership of or beneficial interest in 5 percent or more of the firm's or subsidiary's securities. Beneficial interest includes holding 5 percent or more of any class of the firm's securities in "nominee shares," "street names," or some other method of holding securities that does not disclose the beneficial owner;

(ii) Holding a management position in the firm, such as a director or officer;

(iii) Ability to control or influence the election, appointment, or tenure of directors or officers in the firm;

(iv) Ownership of 10 percent or more of the assets of a firm such as equipment, buildings, real estate, or other tangible assets of the firm; or

(v) Holding 50 percent or more of the indebtness of a firm.

(b) "Prohibition on award."

In accordance with 10 U.S.C. 2327, no contract may be awarded to a firm or a subsidiary of a firm if the government of a terrorist country has a significant interest in the firm or subsidiary or, in the case of a subsidiary, the firm that owns the subsidiary, unless a waiver is granted by the Secretary of Defense.

(c) "Disclosure."

If the government of a terrorist country has a significant interest in the Offeror or a subsidiary of the Offeror, the Offeror shall disclosure such interest in an attachment to its offer. If the Offeror is a subsidiary, it shall also disclose any significant interest the government of a terrorist country has in any firm that owns or controls the subsidiary. The disclosure shall include --

(1) Identification of each government holding a significant interest; and

(2) A description of the significant interest held by each government.

(End of provision)

252.225-7031 SECONDARY ARAB BOYCOTT OF ISRAEL (APR 2003)

(a) Definitions. As used in this provision--

(1) Foreign person means any person (including any individual, partnership, corporation, or other form of association) other than a United States person.

(2) United States person is defined in 50 U.S.C. App. 2415(2) and means--

(i) Any United States resident or national (other than an individual resident outside the United States who is employed by other than a United States person);

(ii) Any domestic concern (including any permanent domestic establishment of any foreign concern); and

(iii) Any foreign subsidiary or affiliate (including any permanent foreign establishment) of any domestic concern that is controlled in fact by such domestic concern.

(b) Certification. If the offeror is a foreign person, the offeror certifies, by submission of an offer, that it--

(1) Does not comply with the Secondary Arab Boycott of Israel; and

(2) Is not taking or knowingly agreeing to take any action, with respect to the Secondary Boycott of Israel by Arab countries, which 50 U.S.C. App. 2407(a) prohibits a United States person from taking.

(End of provision)

252.226-7001 UTILIZATION OF INDIAN ORGANIZATIONS AND INDIAN-OWNED ECONOMIC ENTERPRISES, AND NATIVE HAWAIIAN SMALL BUSINESS CONCERNS (SEP 2004)

(a) Definitions. As used in this clause--

Indian means--

(1) Any person who is a member of any Indian tribe, band, group, pueblo, or community that is recognized by the Federal Government as eligible for services from the Bureau of Indian Affairs (BIA) in accordance with 25 U.S.C. 1452(c); and

(2) Any ``Native'' as defined in the Alaska Native Claims Settlement Act (43 U.S.C. 1601 et seq.).

Indian organization means the governing body of any Indian tribe or entity established or recognized by the governing body of an Indian tribe for the purposes of 25 U.S.C. chapter 17.

Indian-owned economic enterprise means any Indian-owned (as determined by the Secretary of the Interior) commercial, industrial, or business activity established or organized for the purpose of profit, provided that Indian ownership constitutes not less than 51 percent of the enterprise.

Indian tribe means any Indian tribe, band, group, pueblo, or community, including native villages and native groups (including corporations organized by Kenai, Juneau, Sitka, and Kodiak) as defined in the Alaska Native Claims Settlement Act, that is recognized by the Federal Government as eligible for services from BIA in accordance with 25 U.S.C. 1452(c).

Interested party means a contractor or an actual or prospective offeror whose direct economic interest would be affected by the award of a subcontract or by the failure to award a subcontract.

Native Hawaiian small business concern means an entity that is--

(1) A small business concern as defined in section 3 of the Small Business Act (15 U.S.C. 632) and relevant implementing regulations; and

(2) Owned and controlled by a Native Hawaiian as defined in 25 U.S.C. 4221(9).

(b) The Contractor shall use its best efforts to give Indian organizations, Indian-owned economic enterprises, and Native Hawaiian small business concerns the maximum practicable opportunity to participate in the subcontracts it awards, to the fullest extent consistent with efficient performance of the contract.

(c) The Contracting Officer and the Contractor, acting in good faith, may rely on the representation of an Indian organization, Indian-owned economic enterprise, or Native Hawaiian small business concern as to its eligibility, unless an interested party challenges its status or the Contracting Officer has independent reason to question that status.

(d) In the event of a challenge to the representation of a subcontractor, the Contracting Officer will refer the matter to--

(1) For matters relating to Indian organizations or Indian-owned economic enterprises: U.S. Department of the Interior, Bureau of Indian Affairs, Attn: Chief, Division of Contracting and Grants Administration, 1849 C Street NW, MS-2626-MIB, Washington, DC 20240-4000. The BIA will determine the eligibility and will notify the Contracting Officer.

(2) For matters relating to Native Hawaiian small business concerns: Department of Hawaiian Home Lands, PO Box 1879, Honolulu, HI 96805. The Department of Hawaiian Home Lands will determine the eligibility and will notify the Contracting Officer.

(e) No incentive payment will be made--

(1) While a challenge is pending; or

(2) If a subcontractor is determined to be an ineligible participant.

(f)(1) The Contractor, on its own behalf or on behalf of a subcontractor at any tier, may request an incentive payment in accordance with this clause.

(2) The incentive amount that may be requested is 5 percent of the estimated cost, target cost, or fixed price included in the subcontract at the time of award to the Indian organization, Indian-owned economic enterprise, or Native Hawaiian small business concern.

(3) In the case of a subcontract for commercial items, the Contractor may receive an incentive payment only if the subcontracted items are produced or manufactured in whole or in part by an Indian organization, Indian-owned economic enterprise, or Native Hawaiian small business concern.

(4) The Contractor has the burden of proving the amount claimed and shall assert its request for an incentive payment prior to completion of contract performance.

(5) The Contracting Officer, subject to the terms and conditions of the contract and the availability of funds, will authorize an incentive payment of 5 percent of the estimated cost, target cost, or fixed price included in the subcontract awarded to the Indian organization, Indian-owned economic enterprise, or Native Hawaiian small business concern.

(6) If the Contractor requests and receives an incentive payment on behalf of a subcontractor, the Contractor is obligated to pay the subcontractor the incentive amount.

(g) The Contractor shall insert the substance of this clause, including this paragraph (g), in all subcontracts exceeding $500,000.
(End of clause)

E4LC01 CORPORATE CERTIFICATE

Note: Contractor, if a corporation, should cause the following certificate to be executed under its corporate seal, provided that the same officer shall not execute both the contract and the certificate.

CERTIFICATE

I, _____, certify that I am

_____ of the corporation named as Contractor herein, that

_____, was then the _____ of said

corporation; that said contract was duly signed for and in behalf of said corporation of authority

of its governing body, and is within the scope of its corporate powers.

_____
(Name of Corporation)

_____
(Signature)

(Corporate Seal)

NOTE: A CORPORATE OFFICER OTHER THAN THE OFFICER SIGNING THE SOLICITATION MUST FILL OUT AND SIGN THIS FORM.

E4LC17 COMMERCIAL AND GOVERNMENT ENTITY (CAGE) CODE REPORTING

(a) The Offeror is requested to enter its CAGE code in the space provided below. The CAGE code entered must be for that name and address.

(b) If the Offeror does not have a CAGE code, it may ask the Contracting Officer to request one in accordance with the provisions of DFARS 52.204-7001 in the section of this solicitation entitled "Instructions to Bidders."

(c) Do not delay submission of the offer pending receipt of a CAGE code.

CAGE Code: __ __ __ __ __

( ) UNKNOWN

Section 00700 - Contract Clauses

CLAUSES INCORPORATED BY FULL TEXT

52.202-1 DEFINITIONS (JUL 2004)

(a) When a solicitation provision or contract clause uses a word or term that is defined in the Federal Acquisition Regulation (FAR), the word or term has the same meaning as the definition in FAR 2.101 in effect at the time the solicitation was issued, unless--

(1) The solicitation, or amended solicitation, provides a different definition;

(2) The contracting parties agree to a different definition;

(3) The part, subpart, or section of the FAR where the provision or clause is prescribed provides a different meaning; or

(4) The word or term is defined in FAR Part 31, for use in the cost principles and procedures.

(b) The FAR Index is a guide to words and terms the FAR defines and shows where each definition is located. The FAR Index is available via the Internet at http://www.acqnet.gov at the end of the FAR, after the FAR Appendix.

(End of clause)

52.203-3 GRATUITIES (APR 1984)

(a) The right of the Contractor to proceed may be terminated by written notice if, after notice and hearing, the agency head or a designee determines that the Contractor, its agent, or another representative--

(1) Offered or gave a gratuity (e.g., an entertainment or gift) to an officer, official, or employee of the Government; and

(2) Intended, by the gratuity, to obtain a contract or favorable treatment under a contract.

(b) The facts supporting this determination may be reviewed by any court having lawful jurisdiction.

(c) If this contract is terminated under paragraph (a) of this clause, the Government is entitled--

(1) To pursue the same remedies as in a breach of the contract; and

(2) In addition to any other damages provided by law, to exemplary damages of not less than 3 nor more than 10 times the cost incurred by the Contractor in giving gratuities to the person concerned, as determined by the agency head or a designee. (This subparagraph (c)(2) is applicable only if this contract uses money appropriated to the Department of Defense.)

(d) The rights and remedies of the Government provided in this clause shall not be exclusive and are in addition to any other rights and remedies provided by law or under this contract.

(End of clause)

52.203-5 COVENANT AGAINST CONTINGENT FEES (APR 1984)

(a) The Contractor warrants that no person or agency has been employed or retained to solicit or obtain this contract upon an agreement or understanding for a contingent fee, except a bona fide employee or agency. For breach or violation of this warranty, the Government shall have the right to annul this contract without liability or, in its discretion, to deduct from the contract price or consideration, or otherwise

recover, the full amount of the contingent fee.

(b) "Bona fide agency," as used in this clause, means an established commercial or selling agency, maintained by a contractor for the purpose of securing business, that neither exerts nor proposes to exert improper influence to solicit or obtain Government contracts nor holds itself out as being able to obtain any Government contract or contracts through improper influence.

"Bona fide employee," as used in this clause, means a person, employed by a contractor and subject to the contractor's supervision and control as to time, place, and manner of performance, who neither exerts nor proposes to exert improper influence to solicit or obtain Government contracts nor holds out as being able to obtain any Government contract or contracts through improper influence.

"Contingent fee," as used in this clause, means any commission, percentage, brokerage, or other fee that is contingent upon the success that a person or concern has in securing a Government contract.

"Improper influence," as used in this clause, means any influence that induces or tends to induce a Government employee or officer to give consideration or to act regarding a Government contract on any basis other than the merits of the matter.

(End of clause)

52.203-7 ANTI-KICKBACK PROCEDURES. (JUL 1995)

(a) Definitions.

"Kickback," as used in this clause, means any money, fee, commission, credit, gift, gratuity, thing of value, or compensation of any kind which is provided, directly or indirectly, to any prime Contractor, prime Contractor employee, subcontractor, or subcontractor employee for the purpose of improperly obtaining or rewarding favorable treatment in connection with a prime contract or in connection with a subcontract relating to a prime contract.

"Person," as used in this clause, means a corporation, partnership, business association of any kind, trust, joint-stock company, or individual.

"Prime contract," as used in this clause, means a contract or contractual action entered into by the United States for the purpose of obtaining supplies, materials, equipment, or services of any kind.

"Prime Contractor," as used in this clause, means a person who has entered into a prime contract with the United States.

"Prime Contractor employee," as used in this clause, means any officer, partner, employee, or agent of a prime Contractor.

"Subcontract," as used in this clause, means a contract or contractual action entered into by a prime Contractor or subcontractor for the purpose of obtaining supplies, materials, equipment, or services of any kind under a prime contract.

"Subcontractor," as used in this clause, (1) means any person, other than the prime Contractor, who offers to furnish or furnishes any supplies, materials, equipment, or services of any kind under a prime contract or a subcontract entered into in connection with such prime contract, and (2) includes any person who offers to furnish or furnishes general supplies to the prime Contractor or a higher tier subcontractor.

"Subcontractor employee," as used in this clause, means any officer, partner, employee, or agent of a subcontractor.

(b) The Anti-Kickback Act of 1986 (41 U.S.C. 51-58) (the Act), prohibits any person from -

(1) Providing or attempting to provide or offering to provide any kickback;

(2) Soliciting, accepting, or attempting to accept any kickback; or

(3) Including, directly or indirectly, the amount of any kickback in the contract price charged by a prime Contractor to the United States or in the contract price charged by a subcontractor to a prime Contractor or higher tier subcontractor.

(c)(1) The Contractor shall have in place and follow reasonable procedures designed to prevent and detect possible violations described in paragraph (b) of this clause in its own operations and direct business relationships.

(2) When the Contractor has reasonable grounds to believe that a violation described in paragraph (b) of this clause may have occurred, the Contractor shall promptly report in writing the possible violation. Such reports shall be made to the inspector general of the contracting agency, the head of the contracting agency if the agency does not have an inspector general, or the Department of Justice.

(3) The Contractor shall cooperate fully with any Federal agency investigating a possible violation described in paragraph (b) of this clause.

(4) The Contracting Officer may (i) offset the amount of the kickback against any monies owed by the United States under the prime contract and/or (ii) direct that the Prime Contractor withhold, from sums owed a subcontractor under the prime contract, the amount of any kickback. The Contracting Officer may order the monies withheld under subdivision (c)(4)(ii) of this clause be paid over to the Government unless the Government has already offset those monies under subdivision (c)(4)(i) of this clause. In either case, the Prime Contractor shall notify the Contracting Officer when the monies are withheld.

(5) The Contractor agrees to incorporate the substance of this clause, including this subparagraph (c)(5) but excepting subparagraph (c)(1), in all subcontracts under this contract which exceed $100,000.

52.203-8 CANCELLATION, RESCISSION, AND RECOVERY OF FUNDS FOR ILLEGAL OR IMPROPER ACTIVITY (JAN 1997)

(a) If the Government receives information that a contractor or a person has engaged in conduct constituting a violation of subsection (a), (b), (c), or (d) of Section 27 of the Office of Federal Procurement Policy Act (41 U.S.C. 423) (the Act), as amended by section 4304 of the 1996 National Defense Authorization Act for Fiscal Year 1996 (Pub. L. 104-106), the Government may--

(1) Cancel the solicitation, if the contract has not yet been awarded or issued; or

(2) Rescind the contract with respect to which--

(i) The Contractor or someone acting for the Contractor has been convicted for an offense where the conduct constitutes a violation of subsection 27(a) or (b) of the Act for the purpose of either--

(A) Exchanging the information covered by such subsections for anything of value; or

(B) Obtaining or giving anyone a competitive advantage in the award of a Federal agency procurement contract; or

(ii) The head of the contracting activity has determined, based upon a preponderance of the evidence, that the Contractor or someone acting for the Contractor has engaged in conduct constituting an offense punishable under subsections 27(e)(1) of the Act.

(b) If the Government rescinds the contract under paragraph (a) of this clause, the Government is entitled to recover, in addition to any penalty prescribed by law, the amount expended under the contract.

(c) The rights and remedies of the Government specified herein are not exclusive, and are in addition to any other rights and remedies provided by law, regulation, or under this contract.

(End of clause)

52.203-10 PRICE OR FEE ADJUSTMENT FOR ILLEGAL OR IMPROPER ACTIVITY (JAN 1997)

(a) The Government, at its election, may reduce the price of a fixed-price type contract and the total cost and fee under a cost-type contract

by the amount of profit or fee determined as set forth in paragraph (b) of this clause if the head of the contracting activity or designee determines that there was a violation of subsection 27 (a), (b), or (c) of the Office of Federal Procurement Policy Act, as amended (41 U.S.C. 423), as implemented in section 3.104 of the Federal Acquisition Regulation.

(b) The price or fee reduction referred to in paragraph (a) of this clause shall be--

(1) For cost-plus-fixed-fee contracts, the amount of the fee specified in the contract at the time of award;

(2) For cost-plus-incentive-fee contracts, the target fee specified in the contract at the time of award, notwithstanding any minimum fee or "fee floor" specified in the contract;

(3) For cost-plus-award-fee contracts--

(i) The base fee established in the contract at the time of contract award;

(ii) If no base fee is specified in the contract, 30 percent of the amount of each award fee otherwise payable to the Contractor for each award fee evaluation period or at each award fee determination point.

(4) For fixed-price-incentive contracts, the Government may--

(i) Reduce the contract target price and contract target profit both by an amount equal to the initial target profit specified in the contract at the time of contract award; or

(ii) If an immediate adjustment to the contract target price and contract target profit would have a significant adverse impact on the incentive price revision relationship under the contract, or adversely affect the contract financing provisions, the Contracting Officer may defer such adjustment until establishment of the total final price of the contract. The total final price established in accordance with the incentive price revision provisions of the contract shall be reduced by an amount equal to the initial target profit specified in the contract at the time of contract award and such reduced price shall be the total final contract price.

(5) For firm-fixed-price contracts, by 10 percent of the initial contract price or a profit amount determined by the Contracting Officer from records or documents in existence prior to the date of the contract award.

(c) The Government may, at its election, reduce a prime contractor's price or fee in accordance with the procedures of paragraph (b) of this clause for violations of the Act by its subcontractors by an amount not to exceed the amount of profit or fee reflected in the subcontract at the time the subcontract was first definitively priced.

(d) In addition to the remedies in paragraphs (a) and (c) of this clause, the Government may terminate this contract for default. The rights and remedies of the Government specified herein are not exclusive, and are in addition to any other rights and remedies provided by law or under this contract.

(End of clause)

52.203-12 LIMITATION ON PAYMENTS TO INFLUENCE CERTAIN FEDERAL TRANSACTIONS (JUN 2003)

(a) Definitions.

"Agency," as used in this clause, means executive agency as defined in 2.101.

"Covered Federal action," as used in this clause, means any of the following Federal actions:

(1) The awarding of any Federal contract.

(2) The making of any Federal grant.

(3) The making of any Federal loan.

(4) The entering into of any cooperative agreement.

(5) The extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.

"Indian tribe" and "tribal organization," as used in this clause, have the meaning provided in section 4 of the Indian Self-Determination and Education Assistance Act (25 U.S.C. 450B) and include Alaskan Natives.

"Influencing or attempting to influence," as used in this clause, means making, with the intent to influence, any communication to or appearance before an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with any covered Federal action.

"Local government," as used in this clause, means a unit of government in a State and, if chartered, established, or otherwise recognized by a State for the performance of a governmental duty, including a local public authority, a special district, an intrastate district, a council of governments, a sponsor group representative organization, and any other instrumentality of a local government.

"Officer or employee of an agency," as used in this clause, includes the following individuals who are employed by an agency:

(1) An individual who is appointed to a position in the Government under Title 5, United States Code, including a position under a temporary appointment.

(2) A member of the uniformed services, as defined in subsection 101(3),Title 37, United States Code.

(3) A special Government employee, as defined in section 202, Title 18, United States Code.

(4) An individual who is a member of a Federal advisory committee, as defined by the Federal Advisory Committee Act, Title 5, United States Code, appendix 2.

"Person," as used in this clause, means an individual, corporation, company, association, authority, firm, partnership, society, State, and local government, regardless of whether such entity is operated for profit, or not for profit. This term excludes an Indian tribe, tribal organization, or any other Indian organization with respect to expenditures specifically permitted by other Federal law.

"Reasonable compensation," as used in this clause, means, with respect to a regularly employed officer or employee of any person, compensation that is consistent with the normal compensation for such officer or employee for work that is not furnished to, not funded by, or not furnished in cooperation with the Federal Government.

"Reasonable payment," as used in this clause, means, with respect to professional and other technical services, a payment in an amount that is consistent with the amount normally paid for such services in the private sector.

"Recipient," as used in this clause, includes the Contractor and all subcontractors. This term excludes an Indian tribe, tribal organization, or any other Indian organization with respect to expenditures specifically permitted by other Federal law.

"Regularly employed," as used in this clause, means, with respect to an officer or employee of a person requesting or receiving a Federal contract, an officer or employee who is employed by such person for at least 130 working days within 1 year immediately preceding the date of the submission that initiates agency consideration of such person for receipt of such contract. An officer or employee who is employed by such person for less than 130 working days within 1 year immediately preceding the date of the submission that initiates agency consideration of such person shall be considered to be regularly employed as soon as he or she is employed by such person for 130 working days.

State, as used in this clause, means a State of the United States, the District of Columbia, or an outlying area of the United States, an agency or instrumentality of a State, and multi-State, regional, or interstate entity having governmental duties and powers.

(b) Prohibitions.

(1) Section 1352 of Title 31, United States Code, among other things, prohibits a recipient of a Federal contract, grant, loan, or cooperative agreement from using appropriated funds to pay any person for influencing or attempting to influence an officer or employee of any agency,

a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with any of the following covered Federal actions: the awarding of any Federal contract; the making of any Federal grant; the making of any Federal loan; the entering into of any cooperative agreement; or the modification of any Federal contract, grant, loan, or cooperative agreement.

(2) The Act also requires Contractors to furnish a disclosure if any funds other than Federal appropriated funds (including profit or fee received under a covered Federal transaction) have been paid, or will be paid, to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with a Federal contract, grant, loan, or cooperative agreement.

(3) The prohibitions of the Act do not apply under the following conditions:

(i) Agency and legislative liaison by own employees.

(A) The prohibition on the use of appropriated funds, in subparagraph (b)(1) of this clause, does not apply in the case of a payment of reasonable compensation made to an officer or employee of a person requesting or receiving a covered Federal action if the payment is for agency and legislative liaison activities not directly related to a covered Federal action.

(B) For purposes of subdivision (b)(3)(i)(A) of this clause, providing any information specifically requested by an agency or Congress is permitted at any time.

(C) The following agency and legislative liaison activities are permitted at any time where they are not related to a specific solicitation for any covered Federal action:

(1) Discussing with an agency the qualities and characteristics (including individual demonstrations) of the person's products or services, conditions or terms of sale, and service capabilities.

(2) Technical discussions and other activities regarding the application or adaptation of the person's products or services for an agency's use.

(D) The following agency and legislative liaison activities are permitted where they are prior to formal solicitation of any covered Federal action--

(1) Providing any information not specifically requested but necessary for an agency to make an informed decision about initiation of a covered Federal action;

(2) Technical discussions regarding the preparation of an unsolicited proposal prior to its official submission; and

(3) Capability presentations by persons seeking awards from an agency pursuant to the provisions of the Small Business Act, as amended by Pub. L. 95-507, and subsequent amendments.

(E) Only those services expressly authorized by subdivision (b)(3)(i)(A) of this clause are permitted under this clause.

(ii) Professional and technical services.

(A) The prohibition on the use of appropriated funds, in subparagraph (b)(1) of this clause, does not apply in the case of--

(1) A payment of reasonable compensation made to an officer or employee of a person requesting or receiving a covered Federal action or an extension, continuation, renewal, amendment, or modification of a covered Federal action, if payment is for professional or technical services rendered directly in the preparation, submission, or negotiation of any bid, proposal, or application for that Federal action or for meeting requirements imposed by or pursuant to law as a condition for receiving that Federal action.

(2) Any reasonable payment to a person, other than an officer or employee of a person requesting or receiving a covered Federal action or an extension, continuation, renewal, amendment, or modification of a covered Federal action if the payment is for professional or technical services rendered directly in the preparation, submission, or negotiation of any bid, proposal, or application for that Federal action or for meeting requirements imposed by or pursuant to law as a condition for receiving that Federal action. Persons other than officers or employees of a person requesting or receiving a covered Federal action include consultants and trade associations.

(B) For purposes of subdivision (b)(3)(ii)(A) of this clause, "professional and technical services" shall be limited to advice and analysis directly applying any professional or technical discipline. For example, drafting of a legal document accompanying a bid or proposal by a lawyer is allowable. Similarly, technical advice provided by an engineer on the performance or operational capability of a piece of equipment rendered directly in the negotiation of a contract is allowable. However, communications with the intent to influence made by a professional (such as a licensed lawyer) or a technical person (such as a licensed accountant) are not allowable under this section unless they provide advice and analysis directly applying their professional or technical expertise and unless the advice or analysis is rendered directly and solely in the preparation, submission or negotiation of a covered Federal action. Thus, for example, communications with the intent to influence made by a lawyer that do not provide legal advice or analysis directly and solely related to the legal aspects of his or her client's proposal, but generally advocate one proposal over another are not allowable under this section because the lawyer is not providing professional legal services. Similarly, communications with the intent to influence made by an engineer providing an engineering analysis prior to the preparation or submission of a bid or proposal are not allowable under this section since the engineer is providing technical services but not directly in the preparation, submission or negotiation of a covered Federal action.

(C) Requirements imposed by or pursuant to law as a condition for receiving a covered Federal award include those required by law or regulation and any other requirements in the actual award documents.

(D) Only those services expressly authorized by subdivisions (b)(3)(ii)(A)(1) and (2) of this clause are permitted under this clause.

(E) The reporting requirements of FAR 3.803(a) shall not apply with respect to payments of reasonable compensation made to regularly employed officers or employees of a person.

(c) Disclosure.

(1) The Contractor who requests or receives from an agency a Federal contract shall file with that agency a disclosure form, OMB standard form LLL, Disclosure of Lobbying Activities, if such person has made or has agreed to make any payment using nonappropriated funds (to include profits from any covered Federal action), which would be prohibited under subparagraph (b)(1) of this clause, if paid for with appropriated funds.

(2) The Contractor shall file a disclosure form at the end of each calendar quarter in which there occurs any event that materially affects the accuracy of the information contained in any disclosure form previously filed by such person under subparagraph (c)(1) of this clause. An event that materially affects the accuracy of the information reported includes--

(i) A cumulative increase of $25,000 or more in the amount paid or expected to be paid for influencing or attempting to influence a covered Federal action; or

(ii) A change in the person(s) or individual(s) influencing or attempting to influence a covered Federal action; or

(iii) A change in the officer(s), employee(s), or Member(s) contacted to influence or attempt to influence a covered Federal action.

(3) The Contractor shall require the submittal of a certification, and if required, a disclosure form by any person who requests or receives any subcontract exceeding $100,000 under the Federal contract.

(4) All subcontractor disclosure forms (but not certifications) shall be forwarded from tier to tier until received by the prime Contractor. The prime Contractor shall submit all disclosures to the Contracting Officer at the end of the calendar quarter in which the disclosure form is submitted by the subcontractor. Each subcontractor certification shall be retained in the subcontract file of the awarding Contractor.

(d) Agreement. The Contractor agrees not to make any payment prohibited by this clause.

(e) Penalties.

(1) Any person who makes an expenditure prohibited under paragraph (a) of this clause or who fails to file or amend the disclosure form to be filed or amended by paragraph (b) of this clause shall be subject to civil penalties as provided for by 31 U.S.C. 1352. An imposition of a civil penalty does not prevent the Government from seeking any other remedy that may be applicable.

(2) Contractors may rely without liability on the representation made by their subcontractors in the certification and disclosure form.

(f) Cost allowability. Nothing in this clause makes allowable or reasonable any costs which would otherwise be unallowable or unreasonable. Conversely, costs made specifically unallowable by the requirements in this clause will not be made allowable under any other provision.

(End of clause)

52.204-4 PRINTED OR COPIED DOUBLE-SIDED ON RECYCLED PAPER (AUG 2000)

(a) Definitions. As used in this clause--

“Postconsumer material” means a material or finished product that has served its intended use and has been discarded for disposal or recovery, having completed its life as a consumer item. Postconsumer material is a part of the broader category of “recovered material.” For paper and paper products, postconsumer material means “postconsumer fiber” defined by the U.S. Environmental Protection Agency (EPA) as--

(1) Paper, paperboard, and fibrous materials from retail stores, office buildings, homes, and so forth, after they have passed through their end-usage as a consumer item, including: used corrugated boxes; old newspapers; old magazines; mixed waste paper; tabulating cards; and used cordage; or

(2) All paper, paperboard, and fibrous materials that enter and are collected from municipal solid waste; but not

(3) Fiber derived from printers' over-runs, converters' scrap, and over-issue publications.

“Printed or copied double-sided” means printing or reproducing a document so that information is on both sides of a sheet of paper.

“Recovered material,” for paper and paper products, is defined by EPA in its Comprehensive Procurement Guideline as “recovered fiber” and means the following materials:

(1) Postconsumer fiber; and

(2) Manufacturing wastes such as--

(i) Dry paper and paperboard waste generated after completion of the papermaking process (that is, those manufacturing operations up to and including the cutting and trimming of the paper machine reel into smaller rolls or rough sheets) including: envelope cuttings, bindery trimmings, and other paper and paperboard waste resulting from printing, cutting, forming, and other converting operations; bag, box, and carton manufacturing wastes; and butt rolls, mill wrappers, and rejected unused stock; and

(ii) Repulped finished paper and paperboard from obsolete inventories of paper and paperboard manufacturers, merchants, wholesalers, dealers, printers, converters, or others.

(b) In accordance with Section 101 of Executive Order 13101 of September 14, 1998, Greening the Government through Waste Prevention, Recycling, and Federal Acquisition, the Contractor is encouraged to submit paper documents, such as offers, letters, or reports, that are printed or copied double-sided on recycled paper that meet minimum content standards specified in Section 505 of Executive Order 13101, when not using electronic commerce methods to submit information or data to the Government.

(c) If the Contractor cannot purchase high-speed copier paper, offset paper, forms bond, computer printout paper, carbonless paper, file folders, white wove envelopes, writing and office paper, book paper, cotton fiber paper, and cover stock meeting the 30 percent postconsumer material standard for use in submitting paper documents to the Government, it should use paper containing no less than 20 percent postconsumer material. This lesser standard should be used only when paper meeting the 30 percent postconsumer material standard is not obtainable at a reasonable price or does not meet reasonable performance standards.

(End of clause)

52.209-6 PROTECTING THE GOVERNMENT'S INTEREST WHEN SUBCONTRACTING WITH CONTRACTORS DEBARRED, SUSPENDED, OR PROPOSED FOR DEBARMENT (JAN 2005)

(a) The Government suspends or debars Contractors to protect the Government's interests. The Contractor shall not enter into any subcontract in excess of the $25,000 with a Contractor that is debarred, suspended, or proposed for debarment unless there is a compelling reason to do so.

(b) The Contractor shall require each proposed first-tier subcontractor, whose subcontract will exceed $25,000, to disclose to the Contractor, in writing, whether as of the time of award of the subcontract, the subcontractor, or its principles, is or is not debarred, suspended, or proposed for debarment by the Federal Government.

(c) A corporate officer or a designee of the Contractor shall notify the Contracting Officer, in writing, before entering into a subcontract with a party that is debarred, suspended, or proposed for debarment (see FAR 9.404 for information on the in the Excluded Parties List System). The notice must include the following:

(1) The name of the subcontractor.

(2) The Contractor's knowledge of the reasons for the subcontractor being in the Excluded Parties List System.

(3) The compelling reason(s) for doing business with the subcontractor notwithstanding its inclusion in the Excluded Parties List System.

(4) The systems and procedures the Contractor has established to ensure that it is fully protecting the Government's interests when dealing with such subcontractor in view of the specific basis for the party's debarment, suspension, or proposed debarment.

(End of clause)

52.211-18 VARIATION IN ESTIMATED QUANTITY (APR 1984)

If the quantity of a unit-priced item in this contract is an estimated quantity and the actual quantity of the unit-priced item varies more than 15 percent above or below the estimated quantity, an equitable adjustment in the contract price shall be made upon demand of either party. The equitable adjustment shall be based upon any increase or decrease in costs due solely to the variation above 115 percent or below 85 percent of the estimated quantity. If the quantity variation is such as to cause an increase in the time necessary for completion, the Contractor may request, in writing, an extension of time, to be received by the Contracting Officer within 10 days from the beginning of the delay, or within such further period as may be granted by the Contracting Officer before the date of final settlement of the contract. Upon the receipt of a written request for an extension, the Contracting Officer shall ascertain the facts and make an adjustment for extending the completion date as, in the judgement of the Contracting Officer, is justified.

52.214-26 AUDIT AND RECORDS--SEALED BIDDING. (OCT 1997)

(a) As used in this clause, records includes books, documents, accounting procedures and practices, and other data, regardless of type and regardless of whether such items are in written form, in the form of computer data, or in any other form.

(b) Cost or pricing data. If the Contractor has been required to submit cost or pricing data in connection with the pricing of any modification to this contract, the Contracting Officer, or an authorized representative of the Contracting Officer, in order to evaluate the accuracy, completeness, and currency of the cost or pricing data, shall have the right to examine and audit all of the Contractor's records, including computations and projections, related to--

(1) The proposal for the modification;

(2) The discussions conducted on the proposal(s), including those related to negotiating;

(3) Pricing of the modification; or

(4) Performance of the modification.

(c) Comptroller General. In the case of pricing any modification, the Comptroller General of the United States, or an authorized representative, shall have the same rights as specified in paragraph (b) of this clause.

(d) Availability. The Contractor shall make available at its office at all reasonable times the materials described in reproduction, until 3 years after final payment under this contract, or for any other period specified in Subpart 4.7 of the Federal Acquisition Regulation (FAR). FAR Subpart 4.7, Contractor Records Retention, in effect on the data of this contract, is incorporated by reference in its entirety and made a part of this contract.

(1) If this contract is completely or partially terminated, the records relating to the work terminated shall be made available for 3 years after any resulting final termination settlement.

(2) Records pertaining to appeals under the Disputes clause or to litigation or the settlement of claims arising under or relating to the performance of this contract shall be made available until disposition of such appeals, litigation, or claims.

(e) The Contractor shall insert a clause containing all the provisions of this clause, including this paragraph (e), in all subcontracts expected to exceed the threshold in FAR 15.403-4(a)(1) for submission of cost or pricing data.

(End of clause)

52.214-27 PRICE REDUCTION FOR DEFECTIVE COST OR PRICING DATA - MODIFICATIONS - SEALED BIDDING. (OCT 1997)

(a) This clause shall become operative only for any modification to this contract involving aggregate increases and/or decreases in costs, plus applicable profits, expected to exceed the threshold for the submission of cost or pricing data at FAR 15.403-4(a)(1), except that this clause does not apply to a modification if an exception under FAR 15.403-1(b) applies.

(1) Based on adequate price competition;

(2) Based on established catalog or market prices of commercial items sold in substantial quantities to the general public; or

(3) Set by law or regulation.

(b) If any price, including profit, negotiated in connection with any modification under this clause, was increased by any significant amount because

(1) the Contractor or a subcontractor furnished cost or pricing data that were not complete, accurate, and current as certified in its Certificate of Current Cost or Pricing Data;

(2) a subcontractor or prospective subcontractor furnished the Contractor cost or pricing data that were not complete, accurate, and current as certified in the Contractor's Certificate of Current Cost or Pricing Data; or

(3) any of these parties furnished data of any description that were not accurate, the price shall be reduced accordingly and the contract shall be modified to reflect the reduction. This right to a price reduction is limited to that resulting from defects in data relating to modifications for which this clause becomes operative under paragraph (a) above.

(c) Any reduction in the contract price under paragraph (b) above due to defective data from a prospective subcontractor that was not subsequently awarded the subcontract shall be limited to the amount, plus applicable overhead and profit markup, by which:

(1) the actual subcontract; or

(2) the actual cost to the Contractor, if there was no subcontract, was less than the prospective subcontract cost estimate submitted by the Contractor; provided, that the actual subcontract price was not itself affected by defective cost or pricing data.

(d) If the Contracting Officer determines under paragraph (b) of this clause that a price or cost reduction should be made:

(1) the Contractor agrees not to raise the following matters as a defense:

(i) The Contractor or subcontractor was a sole source supplier or otherwise was in a superior bargaining position and thus the price of the contract would not have been modified even if accurate, complete, and current cost or pricing data had been submitted;

(ii) The Contracting Officer should have known that the cost or pricing data in issue were defective even though the Contractor or subcontractor took no affirmative action to bring the character of the data to the attention of the Contracting Officer;

(iii) The contract was based on an agreement about the total cost of the contract and there was no agreement about the cost of each item procured under the contract; or

(iv) The Contractor or subcontractor did not submit a Certificate of Current Cost or Pricing Data.

(2) Except as prohibited by subdivision (d)(2)(ii) of this clause:

(i) an offset in an amount determined appropriate by the Contracting Officer based upon the facts shall be allowed against the amount of a contract price reduction if:

(A) The Contractor certifies to the Contracting Officer that, to the best of the Contractor's knowledge and belief, the Contractor is entitled to the offset in the amount requested; and

(B) The Contractor proves that the cost or pricing data were available before the date of agreement on the price of the contract (or price of the modification) and that the data were not submitted before such date.

(ii) An offset shall not be allowed if:

(A) The understated data was known by the Contractor to be understated when the Certificate of Current Cost or Pricing Data was signed; or
(B) The Government proves that the facts demonstrate that the contract price would not have increased in the amount to be offset even if the available data had been submitted before the date of agreement on price.

(e) If any reduction in the contract price under this clause reduces the price of items for which payment was made prior to the date of the modification reflecting the price reduction, the Contractor shall be liable to and shall pay the United States at the time such overpayment is repaid:

(1) Simple interest on the amount of such overpayment to be computed from the date(s) of overpayment to the Contractor to the date the Government is repaid by the Contractor at the applicable underpayment rate effective for each quarter prescribed by the Secretary of the Treasury under 26 U.S.C. 6621(a)(2); and

(2) A penalty equal to the amount of the overpayment, if the Contractor or subcontractor knowingly submitted cost or pricing data which were incomplete, inaccurate, or noncurrent.

(End of clause)

52.214-28 SUBCONTRACTOR COST OR PRICING DATA - MODIFICATIONS - SEALED BIDDING. (OCT 1997)

(a) The requirements of paragraphs (b) and (c) of this clause shall:

(1) become operative only for any modification to this contract involving aggregate increases and/or decreases in costs, plus applicable profits, expected to exceed the threshold for submission of cost or pricing data at (FAR) 48 CFR 15.403-4(a)(1); and

(2) be limited to such modifications.

(b) Before awarding any subcontract expected to exceed the threshold for submission of cost or pricing data at FAR 15.403-4(a)(1), on the date of agreement on price or the date of award, whichever is later; or before pricing any subcontract modifications involving aggregate increases and/or decreases in costs, plus applicable profits, expected to exceed the threshold for submission of cost or pricing data at FAR 15.403-4(a)(1), the Contractor shall require the subcontractor to submit cost or pricing data (actually or by specific identification in writing), unless an exception under FAR 15.403-1(b) applies.

(1) Based on adequate price competition;

(2) Based on established catalog or market prices of commercial items sold in substantial quantities to the general public; or

(3) Set by law or regulation.

(c) The Contractor shall require the subcontractor to certify in substantially the form prescribed in subsection 15.406-2 of the Federal Acquisition Regulation that, to the best of its knowledge and belief, the data submitted under paragraph (b) above were accurate, complete, and current as of the date of agreement on the negotiated price of the subcontract or subcontract modification.

(d) The Contractor shall insert the substance of this clause, including this paragraph (d), in each subcontract that, when entered into, exceeds the threshold for submission of cost or pricing data at FAR 15.403-4(a)(1).

(End of clause)

52.219-6 NOTICE OF TOTAL SMALL BUSINESS SET-ASIDE (JUN 2003)

(a) Definition.

"Small business concern," as used in this clause, means a concern, including its affiliates, that is independently owned and operated, not dominant in the field of operation in which it is bidding on Government contracts, and qualified as a small business under the size standards in this solicitation.

(b) General. (1) Offers are solicited only from small business concerns. Offers received from concerns that are not small business concerns shall be considered nonresponsive and will be rejected.

(2) Any award resulting from this solicitation will be made to a small business concern.

(c) Agreement. A small business concern submitting an offer in its own name shall furnish, in performing the contract, only end items manufactured or produced by small business concerns in the United States or its outlying areas. If this procurement is processed under simplified **acquisition** procedures and the total amount of this contract does not exceed $25,000, a small business concern may furnish the product of any domestic firm. This paragraph does not apply to construction or service contracts.
(End of clause)

52.219-8 UTILIZATION OF SMALL BUSINESS CONCERNS (MAY 2004)

(a) It is the policy of the United States that small business concerns, veteran-owned small business concerns, service-disabled veteran-owned small business concerns, HUBZone small business concerns, small disadvantaged business concerns, and women-owned small business concerns shall have the maximum practicable opportunity to participate in performing contracts let by any Federal agency, including contracts and subcontracts for subsystems, assemblies, components, and related services for major systems. It is further the policy of the United States that its prime contractors establish procedures to ensure the timely payment of amounts due pursuant to the terms of their subcontracts with small business concerns, veteran-owned small business concerns, service-disabled veteran-owned small business concerns, HUBZone small business concerns, small disadvantaged business concerns, and women-owned small business concerns.

(b) The Contractor hereby agrees to carry out this policy in the awarding of subcontracts to the fullest extent consistent with efficient contract performance. The Contractor further agrees to cooperate in any studies or surveys as may be conducted by the United States Small Business

Administration or the awarding agency of the United States as may be necessary to determine the extent of the Contractor's compliance with this clause.

Definitions. As used in this contract--

HUBZone small business concern means a small business concern that appears on the List of Qualified HUBZone Small Business Concerns maintained by the Small Business Administration.
Service-disabled veteran-owned small business concern--

(1) Means a small business concern--

(i) Not less than 51 percent of which is owned by one or more service-disabled veterans or, in the case of any publicly owned business, not less than 51 percent of the stock of which is owned by one or more service-disabled veterans; and

(ii) The management and daily business operations of which are controlled by one or more service-disabled veterans or, in the case of a service-disabled veteran with permanent and severe disability, the spouse or permanent caregiver of such veteran.

(2) Service-disabled veteran means a veteran, as defined in 38 U.S.C. 101(2), with a disability that is service-connected, as defined in 38 U.S.C. 101(16).

Small business concern means a small business as defined pursuant to Section 3 of the Small Business Act and relevant regulations promulgated pursuant thereto.

Small disadvantaged business concern means a small business concern that represents, as part of its offer that--

(1) It has received certification as a small disadvantaged business concern consistent with 13 CFR part 124, subpart B;

(2) No material change in disadvantaged ownership and control has occurred since its certification;

(3) Where the concern is owned by one or more individuals, the net worth of each individual upon whom the certification is based does not exceed $750,000 after taking into account the applicable exclusions set forth at 13 CFR 124.104(c)(2); and

(4) It is identified, on the date of its representation, as a certified small disadvantaged business in the database maintained by the Small Business Administration (PRO-Net).

Veteran-owned small business concern means a small business concern--

(1) Not less than 51 percent of which is owned by one or more veterans (as defined at 38 U.S.C. 101(2)) or, in the case of any publicly owned business, not less than 51 percent of the stock of which is owned by one or more veterans; and

(2) The management and daily business operations of which are controlled by one or more veterans.

Women-owned small business concern means a small business concern--

(1) That is at least 51 percent owned by one or more women, or, in the case of any publicly owned business, at least 51 percent of the stock of which is owned by one or more women; and

(2) Whose management and daily business operations are controlled by one or more women.

(d) Contractors acting in good faith may rely on written representations by their subcontractors regarding their status as a small business concern, a veteran-owned small business concern, a service-disabled veteran-owned small business concern, a HUBZone small business concern, a small disadvantaged business concern, or a women-owned small business concern.

(End of clause)

52.219-14 LIMITATIONS ON SUBCONTRACTING (DEC 1996)

(a) This clause does not apply to the unrestricted portion of a partial set-aside.

(b) By submission of an offer and execution of a contract, the Offeror/Contractor agrees that in performance of the contract in the case of a contract for--

(1) Services (except construction). At least 50 percent of the cost of contract performance incurred for personnel shall be expended for employees of the concern.

(2) Supplies (other than procurement from a nonmanufacturer of such supplies). The concern shall perform work for at least 50 percent of the cost of manufacturing the supplies, not including the cost of materials.

(3) General construction. The concern will perform at least 15 percent of the cost of the contract, not including the cost of materials, with its own employees.

(4) Construction by special trade contractors. The concern will perform at least 25 percent of the cost of the contract, not including the cost of materials, with its own employees.

52.222-3 CONVICT LABOR (JUN 2003)

(a) Except as provided in paragraph (b) of this clause, the Contractor shall not employ in the performance of this contract any person undergoing a sentence of imprisonment imposed by any court of a State, the District of Columbia, Puerto Rico, the Northern Mariana Islands, American Samoa, Guam, or the U.S. Virgin Islands.

(b) The Contractor is not prohibited from employing persons--

(1) On parole or probation to work at paid employment during the term of their sentence;

(2) Who have been pardoned or who have served their terms; or

(3) Confined for violation of the laws of any of the States, the District of Columbia, Puerto Rico, the Northern Mariana Islands, American Samoa, Guam, or the U.S. Virgin Islands who are authorized to work at paid employment in the community under the laws of such jurisdiction, if--

(i) The worker is paid or is in an approved work training program on a voluntary basis;

(ii) Representatives of local union central bodies or similar labor union organizations have been consulted;

(iii) Such paid employment will not result in the displacement of employed workers, or be applied in skills, crafts, or trades in which there is a surplus of available gainful labor in the locality, or impair existing contracts for services;

(iv) The rates of pay and other conditions of employment will not be less than those paid or provided for work of a similar nature in the locality in which the work is being performed; and

(v) The Attorney General of the United States has certified that the work-release laws or **regulations** of the jurisdiction involved are in conformity with the requirements of Executive Order 11755, as amended by Executive Orders 12608 and 12943.

(End of clause)

52.222-4 CONTRACT WORK HOURS AND SAFETY STANDARDS ACT - OVERTIME COMPENSATION. (SEP 2000)

(a) Overtime requirements. No Contractor or subcontractor employing laborers or mechanics (see Federal Acquisition Regulation 22.300) shall require or permit them to work over 40 hours in any workweek unless they are paid at least 1 and 1/2 times the basic rate of pay for each hour worked over 40 hours.

(b) Violation; liability for unpaid wages; liquidated damages. The responsible Contractor and subcontractor are liable for unpaid wages if they violate the terms in paragraph (a) of this clause. In addition, the Contractor and subcontractor are liable for liquidated damages payable to the Government. The Contracting Officer will assess liquidated damages at the rate of $10 per affected employee for each calendar day on which the employer required or permitted the employee to work in excess of the standard workweek of 40 hours without paying overtime wages required by the Contract Work Hours and Safety Standards Act.

(c) Withholding for unpaid wages and liquidated damages. The Contracting Officer will withhold from payments due under the contract sufficient funds required to satisfy any Contractor or subcontractor liabilities for unpaid wages and liquidated damages. If amounts withheld under the contract are insufficient to satisfy Contractor or subcontractor liabilities, the Contracting Officer will withhold payments from other Federal or Federally assisted contracts held by the same Contractor that are subject to the Contract Work Hours and Safety Standards Act.

(d) Payrolls and basic records.

(1) The Contractor and its subcontractors shall maintain payrolls and basic payroll records for all laborers and mechanics working on the contract during the contract and shall make them available to the Government until 3 years after contract completion. The records shall contain the name and address of each employee, social security number, labor classifications, hourly rates of wages paid, daily and weekly number of hours worked, deductions made, and actual wages paid. The records need not duplicate those required for construction work by Department of Labor regulations at 29 CFR 5.5(a)(3) implementing the Davis-Bacon Act.

(2) The Contractor and its subcontractors shall allow authorized representatives of the Contracting Officer or the Department of Labor to inspect, copy, or transcribe records maintained under paragraph (d)(1) of this clause. The Contractor or subcontractor also shall allow authorized representatives of the Contracting Officer or Department of Labor to interview employees in the workplace during working hours.

(e) Subcontracts. The Contractor shall insert the provisions set forth in paragraphs (a) through (d) of this clause in subcontracts exceeding $100,000 and require subcontractors to include these provisions in any lower tier subcontracts. The Contractor shall be responsible for compliance by any subcontractor or lower-tier subcontractor with the provisions set forth in paragraphs (a) through (d) of this clause.

(End of clause)

52.222-6 DAVIS-BACON ACT (FEB 1995)

(a) All laborers and mechanics employed or working upon the site of the work will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR Part 3), the full amount of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the Contractor and such laborers and mechanics. Contributions made or costs reasonably anticipated for bona fide fringe benefits under section 1(b)(2) of the Davis-Bacon Act on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of paragraph (d) of this clause; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such period. Such laborers and mechanics shall be paid not less than the appropriate wage rate and fringe benefits in the wage determination for the classification of work actually performed, without regard to skill, except as provided in the clause entitled Apprentices and Trainees. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein; provided, That the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classifications and wage rates conformed under paragraph (b) of this clause) and the Davis-Bacon poster (WH-1321) shall be posted at all times by the Contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers.

(b)(1) The Contracting Officer shall require that any class of laborers or mechanics which is not listed in the wage determination and which is to be employed under the contract shall be classified in conformance with the wage determination. The Contracting Officer shall approve

an additional classification and wage rate and fringe benefits therefor only when all the following criteria have been met:

(i) The work to be performed by the classification requested is not performed by a classification in the wage determination.

(ii) The classification is utilized in the area by the construction industry.

(iii) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.

(2) If the Contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the Contracting Officer agree on the classification and wage rate (including the amount designated for fringe benefits, where appropriate), a report of the action taken shall be sent by the Contracting Officer to the Administrator of the Wage and Hour Division, Employment Standards Administration, U.S. Department of Labor, Washington, DC 20210. The Administrator or an authorized representative will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the Contracting Officer or will notify the Contracting Officer within the 30-day period that additional time is necessary.

(3) In the event the Contractor, the laborers or mechanics to be employed in the classification, or their representatives, and the Contracting Officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the Contracting Officer shall refer the questions, including the views of all interested parties and the recommendation of the Contracting Officer, to the Administrator of the Wage and Hour Division for determination. The Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the Contracting Officer or will notify the Contracting Officer within the 30-day period that additional time is necessary.

(4) The wage rate (including fringe benefits, where appropriate) determined pursuant to subparagraphs (b)(2) and (b)(3) of this clause shall be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.

(c) Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the Contractor shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly cash equivalent thereof.

(c) If the Contractor does not make payments to a trustee or other third person, the Contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program; provided, That the Secretary of Labor has found, upon the written request of the Contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the Contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

(End of clause)

52.222-7 WITHHOLDING OF FUNDS (FEB 1988)

The Contracting Officer shall, upon his or her own action or upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the Contractor under this contract or any other Federal contract with the same Prime Contractor, or any other Federally assisted contract subject to Davis-Bacon prevailing wage requirements, which is held by the same Prime Contractor, so much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the Contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the Contracting Officer may, after written notice to the Contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

(End of clause)

52.222-8 PAYROLLS AND BASIC RECORDS (FEB 1988)

(a) Payrolls and basic records relating thereto shall be maintained by the Contractor during the course of the work and preserved for a period of 3 years thereafter for all laborers and mechanics working at the site of the work. Such records shall contain the name, address, and social security number of each such worker, his or her correct classification, hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in section 1(b)(2)(B) of the Davis-Bacon Act), daily and weekly number of hours worked, deductions made, and actual wages paid. Whenever the Secretary of Labor has found, under paragraph (d) of the clause entitled Davis-Bacon Act, that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in section 1(b)(2)(B) of the Davis-Bacon Act, the Contractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits. Contractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprenticeship programs and certification of trainee programs, the registration of the apprentices and trainees, and the ratios and wage rates prescribed in the applicable programs.

(b)(1) The Contractor shall submit weekly for each week in which any contract work is performed a copy of all payrolls to the Contracting Officer. The payrolls submitted shall set out accurately and completely all of the information required to be maintained under paragraph (a) of this clause. This information may be submitted in any form desired. Optional Form WH-347 (Federal Stock Number 029-005-00014-1) is available for this purpose and may be purchased from the Superintendent of Documents, U.S. Government Printing Office, Washington, DC 20402. The Prime Contractor is responsible for the submission of copies of payrolls by all subcontractors.

(2) Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the Contractor or subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract and shall certify--

(i) That the payroll for the payroll period contains the information required to be maintained under paragraph (a) of this clause and that such information is correct and complete;

(ii) That each laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in the Regulations, 29 CFR Part 3; and

(iii) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.

(3) The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by subparagraph (b)(2) of this clause.

(4) The falsification of any of the certifications in this clause may subject the Contractor or subcontractor to civil or criminal prosecution under Section 1001 of Title 18 and Section 3729 of Title 31 of the United States Code.

(c) The Contractor or subcontractor shall make the records required under paragraph (a) of this clause available for inspection, copying, or transcription by the Contracting Officer or authorized representatives of the Contracting Officer or the Department of Labor. The Contractor or subcontractor shall permit the Contracting Officer or representatives of the Contracting Officer or the Department of Labor to interview employees during working hours on the job. If the Contractor or subcontractor fails to submit required records or to make them available, the Contracting Officer may, after written notice to the Contractor, take such action as may be necessary to cause the suspension of any further payment. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

(End of clause)

52.222-9 APPRENTICES AND TRAINEES (FEB 1988)

(a) Apprentices. Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor,

Employment and Training Administration, Bureau of Apprenticeship and Training, or with a State Apprenticeship Agency recognized by the Bureau, or if a person is employed in his or her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Bureau of Apprenticeship and Training or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice. The allowable ratio of apprentices to journeymen on the job site in any craft classification shall not be greater than the ratio permitted to the Contractor as to the entire work force under the registered program. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated in this paragraph, shall be paid not less than the applicable wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman's hourly rate) specified in the Contractor's or subcontractor's registered program shall be observed. Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination. In the event the Bureau of Apprenticeship and Training, or a State Apprenticeship Agency recognized by the Bureau, withdraws approval of an apprenticeship program, the Contractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

(b) Trainees. Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the U.S. Department of Labor, Employment and Training Administration. The ratio of trainees to journeymen on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration. Every trainee must be paid at not less than the rate specified in the approved program for the trainee's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed in the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman wage rate in the wage determination which provides for less than full fringe benefits for apprentices. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate in the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate in the wage determination for the work actually performed. In the event the Employment and Training Administration withdraws approval of a training program, the Contractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

(c) Equal employment opportunity. The utilization of apprentices, trainees, and journeymen under this clause shall be in conformity with the equal employment opportunity requirements of Executive Order 11246, as amended, and 29 CFR Part 30.

(End of clause)

52.222-10 COMPLIANCE WITH COPELAND ACT REQUIREMENTS (FEB 1988)

The Contractor shall comply with the requirements of 29 CFR Part 3, which are hereby incorporated by reference in this contract.

(End of clause)

52.222-11 SUBCONTRACTS (LABOR STANDARDS (FEB 1988)

(a) The Contractor or subcontractor shall insert in any subcontracts the clauses entitled Davis-Bacon Act, Contract Work Hours and Safety Standards Act-Overtime Compensation, Apprentices and Trainees, Payrolls and Basic Records, Compliance with Copeland Act Requirements, Withholding of Funds, Subcontracts (Labor Standards), Contract Termination-Debarment, Disputes Concerning Labor

Standards, Compliance with Davis-Bacon and Related Act Regulations, and Certification of Eligibility, and such other clauses as the Contracting Officer may, by appropriate instructions, require, and also a clause requiring subcontractors to include these clauses in any lower tier subcontracts. The Prime Contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with all the contract clauses cited in this paragraph.

(b)(1) Within 14 days after award of the contract, the Contractor shall deliver to the Contracting Officer a completed Statement and Acknowledgment Form (SF 1413) for each subcontract, including the subcontractor's signed and dated acknowledgment that the clauses set forth in paragraph (a) of this clause have been included in the subcontract.

(2) Within 14 days after the award of any subsequently awarded subcontract the Contractor shall deliver to the Contracting Officer an updated completed SF 1413 for such additional subcontract.

(End of clause)

52.222-12 CONTRACT TERMINATION--DEBARMENT (FEB 1988)

A breach of the contract clauses entitled Davis-Bacon Act, Contract Work Hours and Safety Standards Act--Overtime Compensation, Apprentices and Trainees, Payrolls and Basic Records, Compliance with Copeland Act Requirements, Subcontracts (Labor Standards), Compliance with Davis-Bacon and Related Act Regulations, or Certification of Eligibility may be grounds for termination of the contract, and for debarment as a Contractor and subcontractor as provided in 29 CFR 5.12.

(End of clause)

52.222-13 COMPLIANCE WITH DAVIS-BACON AND RELATED ACT REGULATIONS (FEB 1988)

All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR Parts 1, 3, and 5 are hereby incorporated by reference in this contract.

(End of clause)

52.222-35 EQUAL OPPORTUNITY FOR SPECIAL DISABLED VETERANS, VETERANS OF THE VIETNAM ERA, AND OTHER ELIGIBLE VETERANS (DEC 2001)

(a) Definitions. As used in this clause--

All employment openings means all positions except executive and top management, those positions that will be filled from within the Contractor's organization, and positions lasting 3 days or less. This term includes full-time employment, temporary employment of more than 3 days duration, and part-time employment.

Executive and top management means any employee--

(1) Whose primary duty consists of the management of the enterprise in which the individual is employed or of a customarily recognized department or subdivision thereof;

(2) Who customarily and regularly directs the work of two or more other employees;

(3) Who has the authority to hire or fire other employees or whose suggestions and recommendations as to the hiring or firing and as to the advancement and promotion or any other change of status of other employees will be given particular weight;

(4) Who customarily and regularly exercises discretionary powers; and

(5) Who does not devote more than 20 percent or, in the case of an employee of a retail or service establishment, who does not devote more than 40 percent of total hours of work in the work week to activities that are not directly and closely related to the performance of the work described in paragraphs (1) through (4) of this definition. This paragraph (5) does not apply in the case of an employee who is in sole charge of an establishment or a physically separated branch establishment, or who owns at least a 20 percent interest in the enterprise in which the individual is employed.

Other eligible veteran means any other veteran who served on active duty during a war or in a campaign or expedition for which a campaign badge has been authorized.

Positions that will be filled from within the Contractor's organization means employment openings for which the Contractor will give no consideration to persons outside the Contractor's organization (including any affiliates, subsidiaries, and parent companies) and includes any openings the Contractor proposes to fill from regularly established “recall” lists. The exception does not apply to a particular opening once an employer decides to consider applicants outside of its organization.

Qualified special disabled veteran means a special disabled veteran who satisfies the requisite skill, experience, education, and other job-related requirements of the employment position such veteran holds or desires, and who, with or without reasonable accommodation, can perform the essential functions of such position.

Special disabled veteran means--

(1) A veteran who is entitled to compensation (or who but for the receipt of military retired pay would be entitled to compensation) under laws administered by the Department of Veterans Affairs for a disability--

(i) Rated at 30 percent or more; or

(ii) Rated at 10 or 20 percent in the case of a veteran who has been determined under 38 U.S.C. 3106 to have a serious employment handicap (i.e., a significant impairment of the veteran's ability to prepare for, obtain, or retain employment consistent with the veteran's abilities, aptitudes, and interests); or

(2) A person who was discharged or released from active duty because of a service-connected disability.

Veteran of the Vietnam era means a person who--

(1) Served on active duty for a period of more than 180 days and was discharged or released from active duty with other than a dishonorable discharge, if any part of such active duty occurred--

(i) In the Republic of Vietnam between February 28, 1961, and May 7, 1975; or

(ii) Between August 5, 1964, and May 7, 1975, in all other cases; or

(2) Was discharged or released from active duty for a service-connected disability if any part of the active duty was performed--

(i) In the Republic of Vietnam between February 28, 1961, and May 7, 1975; or

(ii) Between August 5, 1964, and May 7, 1975, in all other cases.
(b) General. (1) The Contractor shall not discriminate against the individual because the individual is a special disabled veteran, a veteran of the Vietnam era, or other eligible veteran, regarding any position for which the employee or applicant for employment is qualified. The Contractor shall take affirmative action to employ, advance in employment, and otherwise treat qualified special disabled veterans, veterans of the Vietnam era, and other eligible veterans without discrimination based upon their disability or veterans' status in all employment practices such as--

(i) Recruitment, advertising, and job application procedures;

(ii) Hiring, upgrading, promotion, award of tenure, demotion, transfer, layoff, termination, right of return from layoff and rehiring;

(iii) Rate of pay or any other form of compensation and changes in compensation;

(iv) Job assignments, job classifications, organizational structures, position descriptions, lines of progression, and seniority lists;

(v) Leaves of absence, sick leave, or any other leave;

(vi) Fringe benefits available by virtue of employment, whether or not administered by the Contractor;

(vii) Selection and financial support for training, including apprenticeship, and on-the-job training under 38 U.S.C. 3687, professional meetings, conferences, and other related activities, and selection for leaves of absence to pursue training;

(viii) Activities sponsored by the Contractor including social or recreational programs; and

(ix) Any other term, condition, or privilege of employment.

(2) The Contractor shall comply with the rules, regulations, and relevant orders of the Secretary of Labor issued under the Vietnam Era Veterans' Readjustment Assistance Act of 1972 (the Act), as amended (38 U.S.C. 4211 and 4212).

(c) Listing openings. (1) The Contractor shall immediately list all employment openings that exist at the time of the execution of this contract and those which occur during the performance of this contract, including those not generated by this contract, and including those occurring at an establishment of the Contractor other than the one where the contract is being performed, but excluding those of independently operated corporate affiliates, at an appropriate local public employment service office of the State wherein the opening occurs. Listing employment openings with the U.S. Department of Labor's America's Job Bank shall satisfy the requirement to list jobs with the local employment service office.

(2) The Contractor shall make the listing of employment openings with the local employment service office at least concurrently with using any other recruitment source or effort and shall involve the normal obligations of placing a bona fide job order, including accepting referrals of veterans and nonveterans. This listing of employment openings does not require hiring any particular job applicant or hiring from any particular group of job applicants and is not intended to relieve the Contractor from any requirements of Executive orders or regulations concerning nondiscrimination in employment.

(3) Whenever the Contractor becomes contractually bound to the listing terms of this clause, it shall advise the State public employment agency in each State where it has establishments of the name and location of each hiring location in the State. As long as the Contractor is contractually bound to these terms and has so advised the State agency, it need not advise the State agency of subsequent contracts. The Contractor may advise the State agency when it is no longer bound by this contract clause.

(d) Applicability. This clause does not apply to the listing of employment openings that occur and are filled outside the 50 States, the District of Columbia, the Commonwealth of Puerto Rico, the Commonwealth of the Northern Mariana Islands, American Samoa, Guam, the Virgin Islands of the United States, and Wake Island.

(e) Postings. (1) The Contractor shall post employment notices in conspicuous places that are available to employees and applicants for employment.

(2) The employment notices shall--

(i) State the rights of applicants and employees as well as the Contractor's obligation under the law to take affirmative action to employ and advance in employment qualified employees and applicants who are special disabled veterans, veterans of the Vietnam era, and other eligible veterans; and

(ii) Be in a form prescribed by the Deputy Assistant Secretary for Federal Contract Compliance Programs, Department of Labor (Deputy Assistant Secretary of Labor), and provided by or through the Contracting Officer.

(3) The Contractor shall ensure that applicants or employees who are special disabled veterans are informed of the contents of the notice (e.g., the Contractor may have the notice read to a visually disabled veteran, or may lower the posted notice so that it can be read by a person in a wheelchair).

(4) The Contractor shall notify each labor union or representative of workers with which it has a collective bargaining agreement, or other contract understanding, that the Contractor is bound by the terms of the Act and is committed to take affirmative action to employ, and advance in employment, qualified special disabled veterans, veterans of the Vietnam era, and other eligible veterans.

(f) Noncompliance. If the Contractor does not comply with the requirements of this clause, the Government may take appropriate actions under the rules, regulations, and relevant orders of the Secretary of Labor issued pursuant to the Act.

(g) Subcontracts. The Contractor shall insert the terms of this clause in all subcontracts or purchase orders of $25,000 or more unless exempted by rules, regulations, or orders of the Secretary of Labor. The Contractor shall act as specified by the Deputy Assistant Secretary of Labor to enforce the terms, including action for noncompliance.

(End of clause)

52.222-36 AFFIRMATIVE ACTION FOR WORKERS WITH DISABILITIES (JUN 1998)

(a) General. (1) Regarding any position for which the employee or applicant for employment is qualified, the Contractor shall not discriminate against any employee or applicant because of physical or mental disability. The Contractor agrees to take affirmative action to employ, advance in employment, and otherwise treat qualified individuals with disabilities without discrimination based upon their physical or mental disability in all employment practices such as--

(i) Recruitment, advertising, and job application procedures;

(ii) Hiring, upgrading, promotion, award of tenure, demotion, transfer, layoff, termination, right of return from layoff, and rehiring;

(iii) Rates of pay or any other form of compensation and changes in compensation;

(iv) Job assignments, job classifications, organizational structures, position descriptions, lines of progression, and seniority lists;

(v) Leaves of absence, sick leave, or any other leave;

(vi) Fringe benefits available by virtue of employment, whether or not administered by the Contractor;

(vii) Selection and financial support for training, including apprenticeships, professional meetings, conferences, and other related activities, and selection for leaves of absence to pursue training;

(viii) Activities sponsored by the Contractor, including social or recreational programs; and

(ix) Any other term, condition, or privilege of employment.

(2) The Contractor agrees to comply with the rules, regulations, and relevant orders of the Secretary of Labor (Secretary) issued under the Rehabilitation Act of 1973 (29 U.S.C. 793) (the Act), as amended.

(b) Postings. (1) The Contractor agrees to post employment notices stating--

(i) The Contractor's obligation under the law to take affirmative action to employ and advance in employment qualified individuals with disabilities; and

(ii) The rights of applicants and employees.

(2) These notices shall be posted in conspicuous places that are available to employees and applicants for employment. The Contractor shall ensure that applicants and employees with disabilities are informed of the contents of the notice (e.g., the Contractor may have the notice read to a visually disabled individual, or may lower the posted notice so that it might be read by a person in a wheelchair). The notices shall be in a form prescribed by the Deputy Assistant Secretary for Federal Contract Compliance of the U.S. Department of Labor (Deputy Assistant Secretary) and shall be provided by or through the Contracting Officer.

(3) The Contractor shall notify each labor union or representative of workers with which it has a collective bargaining agreement or other contract understanding, that the Contractor is bound by the terms of Section 503 of the Act and is committed to take affirmative action to employ, and advance in employment, qualified individuals with physical or mental disabilities.

(c) Noncompliance. If the Contractor does not comply with the requirements of this clause, appropriate actions may be taken under the rules, regulations, and relevant orders of the Secretary issued pursuant to the Act.

(d) Subcontracts. The Contractor shall include the terms of this clause in every subcontract or purchase order in excess of $10,000 unless exempted by rules, regulations, or orders of the Secretary. The Contractor shall act as specified by the Deputy Assistant Secretary to enforce the terms, including action for noncompliance.

(End of clause)

52.222-37 EMPLOYMENT REPORTS ON SPECIAL DISABLED VETERANS, VETERANS OF THE VIETNAM ERA, AND OTHER ELIGIBLE VETERANS (DEC 2001)

(a) Unless the Contractor is a State or local government agency, the Contractor shall report at least annually, as required by the Secretary of Labor, on--

(1) The number of disabled veterans and the number of veterans of the Vietnam era in the workforce of the contractor by job category and hiring location; and

(2) The total number of new employees hired during the period covered by the report, and of that total, the number of disabled veterans, and the number of veterans of the Vietnam era.

(b) The above items shall be reported by completing the form entitled "Federal Contractor Veterans' Employment Report VETS-100."

(c) Reports shall be submitted no later than September 30 of each year beginning September 30, 1988.

(d) The employment activity report required by paragraph (a)(2) of this clause shall reflect total hires during the most recent 12-month period as of the ending date selected for the employment profile report required by paragraph (a)(1) of this clause. Contractors may select an ending date: (1) As of the end of any pay period during the period January through March 1st of the year the report is due, or (2) as of December 31, if the contractor has previous written approval from the Equal Employment Opportunity Commission to do so for purposes of submitting the Employer Information Report EEO-1 (Standard Form 100).

(e) The count of veterans reported according to paragraph (a) of this clause shall be based on voluntary disclosure. Each Contractor subject to the reporting requirements at 38 U.S.C. 4212 shall invite all disabled veterans and veterans of the Vietnam era who wish to benefit under the affirmative action program at 38 U.S.C. 4212 to identify themselves to the Contractor. The invitation shall state that the information is voluntarily provided; that the information will be kept confidential; that disclosure or refusal to provide the information will not subject the applicant or employee to any adverse treatment; and that the information will be used only in accordance with the regulations promulgated under 38 U.S.C. 4212.

(f) Subcontracts. The Contractor shall include the terms of this clause in every subcontract or purchase order of $10,000 or more unless exempted by rules, regulations, or orders of the Secretary.

(End of clause)

52.223-6 DRUG-FREE WORKPLACE (MAY 2001)

(a) Definitions. As used in this clause --

"Controlled substance" means a controlled substance in schedules I through V of section 202 of the Controlled Substances Act (21 U.S.C.

812) and as further defined in regulation at 21 CFR 1308.11 - 1308.15.

"Conviction" means a finding of guilt (including a plea of nolo contendere) or imposition of sentence, or both, by any judicial body charged with the responsibility to deter- mine violations of the Federal or State criminal drug statutes.

"Criminal drug statute" means a Federal or non-Federal criminal statute involving the manufacture, distribution, dispensing, possession, or use of any controlled substance.

"Drug-free workplace" means the site(s) for the performance of work done by the Contractor in connection with a specific contract at which employees of the Contractor are prohibited from engaging in the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance.

"Employee" means an employee of a Contractor directly engaged in the performance of work under a Government contract. "Directly engaged" is defined to include all direct cost employees and any other Contractor employee who has other than a minimal impact or involvement in contract performance.

"Individual" means an offeror/contractor that has no more than one employee including the offeror/contractor.

(b) The Contractor, if other than an individual, shall-- within 30 days after award (unless a longer period is agreed to in writing for contracts of 30 days or more performance duration), or as soon as possible for contracts of less than 30 days performance duration--

(1) Publish a statement notifying its employees that the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance is prohibited in the Contractor's workplace and specifying the actions that will be taken against employees for violations of such prohibition;

(2) Establish an ongoing drug-free awareness program to inform such employees about--

(i) The dangers of drug abuse in the workplace;

(ii) The Contractor's policy of maintaining a drug-free workplace;

(iii) Any available drug counseling, rehabilitation, and employee assistance programs; and

(iv) The penalties that may be imposed upon employees for drug abuse violations occurring in the workplace;

(3) Provide all employees engaged in performance of the contract with a copy of the statement required by subparagraph (b)(1) of this clause;

(4) Notify such employees in writing in the statement required by subparagraph (b)(1) of this clause that, as a condition of continued employment on this contract, the employee will--

(i) Abide by the terms of the statement; and

(ii) Notify the employer in writing of the employee's conviction under a criminal drug statute for a violation occurring in the workplace no later than 5 days after such conviction.

(5) Notify the Contracting Officer in writing within 10 days after receiving notice under subdivision (b)(4)(ii) of this clause, from an employee or otherwise receiving actual notice of such conviction. The notice shall include the position title of the employee;

(6) Within 30 days after receiving notice under subdivision (b)(4)(ii) of this clause of a conviction, take one of the following actions with respect to any employee who is convicted of a drug abuse violation occurring in the workplace:

(i) Taking appropriate personnel action against such employee, up to and including termination; or

(ii) Require such employee to satisfactorily participate in a drug abuse assistance or rehabilitation program approved for such purposes by a Federal, State, or local health, law enforcement, or other appropriate agency; and

(7) Make a good faith effort to maintain a drug-free workplace through implementation of subparagraphs (b)(1) though (b)(6) of this clause.

(c) The Contractor, if an individual, agrees by award of the contract or acceptance of a purchase order, not to engage in the unlawful manufacture, distribution, dispensing, possession, or use of a controlled substance while performing this contract.

(d) In addition to other remedies available to the Government, the Contractor's failure to comply with the requirements of paragraph (b) or (c) of this clause may, pursuant to FAR 23.506, render the Contractor subject to suspension of contract payments, termination of the contract for default, and suspension or debarment.

(End of clause)

52.223-14 TOXIC CHEMICAL RELEASE REPORTING (AUG 2003)

(a) Unless otherwise exempt, the Contractor, as owner or operator of a facility used in the performance of this contract, shall file by July 1 for the prior calendar year an annual Toxic Chemical Release Inventory Form (Form R) as described in sections 313(a) and (g) of the Emergency Planning and Community Right-to-Know Act of 1986 (EPCRA) (42 U.S.C. 11023(a) and (g)), and section 6607 of the Pollution Prevention Act of 1990 (PPA) (42 U.S.C. 13106). The Contractor shall file, for each facility subject to the Form R filing and reporting requirements, the annual Form R throughout the life of the contract.

(b) A Contractor-owned or -operated facility used in the performance of this contract is exempt from the requirement to file an annual Form R if--

(1) The facility does not manufacture, process, or otherwise use any toxic chemicals listed in 40 CFR 372.65;

(2) The facility does not have 10 or more full-time employees as specified in section 313(b)(1)(A) of EPCRA, 42 U.S.C. 11023(b)(1)(A);

(3) The facility does not meet the reporting thresholds of toxic chemicals established under of EPCRA, 42 U.S.C. 11023(f) (including the alternate thresholds at 40 CFR 372.27, provided an appropriate certification form has been filed with EPA);

(4) The facility does not fall within the following Standard Industrial Classification (SIC) codes or their corresponding North American Industry Classification System sectors:

(i) Major group code 10 (except 1011, 1081, and 1094.

(ii) Major group code 12 (except 1241).

(iii) Major group codes 20 through 39.

(iv) Industry code 4911, 4931, or 4939 (limited to facilities that combust coal and/or oil for the purpose of generating power for distribution in commerce).

(v) Industry code 4953 (limited to facilities regulated under the Resource Conservation and Recovery Act, Subtitle C (42 U.S.C. 6921, et seq.)), 5169, 5171, or 7389 (limited to facilities primarily engaged in solvent recovery services on a contract or fee basis); or

(5) The facility is not located in the United States or its outlying areas.

(c) If the Contractor has certified to an exemption in accordance with one or more of the criteria in paragraph (b) of this clause, and after award of the contract circumstances change so that any of its owned or operated facilities used in the performance of this contract is no longer exempt--

(1) The Contractor shall notify the Contracting Officer; and

(2) The Contractor, as owner or operator of a facility used in the performance of this contract that is no longer exempt, shall (i) submit a Toxic Chemical Release Inventory Form (Form R) on or before July 1 for the prior calendar year during which the facility becomes eligible; and (ii) continue to file the annual Form R for the life of the contract for such facility.

(d) The Contracting Officer may terminate this contract or take other action as appropriate, if the Contractor fails to comply accurately and fully with the EPCRA and PPA toxic chemical release filing and reporting requirements.

(e) Except for acquisitions of commercial items, as defined in FAR Part 2, the Contractor shall--

(1) For competitive subcontracts expected to exceed $100,000 (including all options), include a solicitation provision substantially the same as the provision at FAR 52.223-13, Certification of Toxic Chemical Release Reporting; and

(2) Include in any resultant subcontract exceeding $100,000 (including all options), the substance of this clause, except this paragraph (e).

(End of clause)

52.225-11 BUY AMERICAN ACT--CONSTRUCTION MATERIALS UNDER TRADE AGREEMENTS (JAN 2005)

(a) Definitions. As used in this clause--

Caribbean Basin country construction material means a construction material that--

(1) Is wholly the growth, product, or manufacture of a Caribbean Basin country; or

(2) In the case of a construction material that consists in whole or in part of materials from another country, has been substantially transformed in a Caribbean Basin country into a new and different construction material distinct from the materials from which it was transformed.

Component means an article, material, or supply incorporated directly into a construction material.

Construction material means an article, material, or supply brought to the construction site by the Contractor or subcontractor for incorporation into the building or work. The term also includes an item brought to the site preassembled from articles, materials, or supplies. However, emergency life safety systems, such as emergency lighting, fire alarm, and audio evacuation systems, that are discrete systems incorporated into a public building or work and that are produced as complete systems, are evaluated as a single and distinct construction material regardless of when or how the individual parts or components of those systems are delivered to the construction site. Materials purchased directly by the Government are supplies, not construction material.

Cost of components means--

(1) For components purchased by the Contractor, the acquisition cost, including transportation costs to the place of incorporation into the construction material (whether or not such costs are paid to a domestic firm), and any applicable duty (whether or not a duty-free entry certificate is issued); or

(2) For components manufactured by the Contractor, all costs associated with the manufacture of the component, including transportation costs as described in paragraph (1) of this definition, plus allocable overhead costs, but excluding profit. Cost of components does not include any costs associated with the manufacture of the construction material.

Designated country means any of the following countries:

(1) A World Trade Organization Government Procurement Agreement country (Aruba, Austria, Belgium, Canada, Cyprus, Czech Republic, Denmark, Estonia, Finland, France, Germany, Greece, Hong Kong, Hungary, Iceland, Ireland, Israel, Italy, Japan, Korea (Republic of), Latvia, Liechtenstein, Lithuania, Luxembourg, Malta, Netherlands, Norway, Poland, Portugal, Singapore, Slovak Republic, Slovenia, Spain, Sweden, Switzerland, or United Kingdom);

(2) A Free Trade Agreement country (Australia, Canada, Chile, Mexico, Morocco, or Singapore);

(3) A least developed country (Afghanistan, Angola, Bangladesh, Benin, Bhutan, Burkina Faso, Burundi, Cambodia, Cape Verde, Central African Republic, Chad, Comoros, Democratic Republic of Congo, Djibouti, East Timor, Equatorial Guinea, Eritrea, Ethiopia, Gambia, Guinea, Guinea-Bissau, Haiti, Kiribati, Laos, Lesotho, Madagascar, Malawi, Maldives, Mali, Mauritania, Mozambique, Nepal, Niger, Rwanda, Samoa, Sao Tome and Principe, Senegal, Sierra Leone, Solomon Islands, Somalia, Tanzania, Togo, Tuvalu, Uganda, Vanuatu, Yemen, or Zambia); or

(4) A Caribbean Basin country (Antigua and Barbuda, Aruba, Bahamas, Barbados, Belize, British Virgin Islands, Costa Rica, Dominica, Dominican Republic, El Salvador, Grenada, Guatemala, Guyana, Haiti, Honduras, Jamaica, Montserrat, Netherlands Antilles, Nicaragua, St. Kitts and Nevis, St. Lucia, St. Vincent and the Grenadines, or Trinidad and Tobago).

Designated country construction material means a construction material that is a WTO GPA country construction material, an FTA country construction material, a least developed country construction material, or a Caribbean Basin country construction material.

Domestic construction material means--

(1) An unmanufactured construction material mined or produced in the United States; or

(2) A construction material manufactured in the United States, if the cost of its components mined, produced, or manufactured in the United States exceeds 50 percent of the cost of all its components. Components of foreign origin of the same class or kind for which nonavailability determinations have been made are treated as domestic.

Foreign construction material means a construction material other than a domestic construction material.

Least developed country construction material means a construction material that--

(1) Is wholly the growth, product, or manufacture of a least developed country; or

(2) In the case of a construction material that consists in whole or in part of materials from another country, has been substantially transformed in a least developed country into a new and different construction material distinct from the materials from which it was transformed.

United States means the 50 States, the District of Columbia, and outlying areas.

WTO GPA country construction material means a construction material that--

(1) Is wholly the growth, product, or manufacture of a WTO GPA country; or

(2) In the case of a construction material that consists in whole or in part of materials from another country, has been substantially transformed in a WTO GPA country into a new and different construction material distinct from the materials from which it was transformed.

(b) Construction materials. (1) This clause implements the Buy American Act (41 U.S.C. 10a-10d) by providing a preference for domestic construction material. In addition, the Contracting Officer has determined that the WTO GPA and Free Trade Agreements (FTAs) apply to this acquisition. Therefore, the Buy American Act restrictions are waived for designated country construction materials.

(2) The Contractor shall use only domestic, designated country construction material in performing this contract, except as provided in paragraphs (b)(3) and (b)(4) of this clause.

(3) The requirement in paragraph (b)(2) of this clause does not apply to the construction materials or components listed by the Government as follows:

None

(4) The Contracting Officer may add other foreign construction material to the list in paragraph (b)(3) of this clause if the Government determines that--

(i) The cost of domestic construction material would be unreasonable. The cost of a particular domestic construction material subject to the restrictions of the Buy American Act is unreasonable when the cost of such material exceeds the cost of foreign material by more than 6 percent;

(ii) The application of the restriction of the Buy American Act to a particular construction material would be impracticable or inconsistent with the public interest; or

(iii) The construction material is not mined, produced, or manufactured in the United States in sufficient and reasonably available commercial quantities of a satisfactory quality.

(c) Request for determination of inapplicability of the Buy American Act.

(1)(i) Any Contractor request to use foreign construction material in accordance with paragraph (b)(4) of this clause shall include adequate information for Government evaluation of the request, including--

(A) A description of the foreign and domestic construction materials;

(B) Unit of measure;

(C) Quantity;

(D) Price;

(E) Time of delivery or availability;

(F) Location of the construction project;

(G) Name and address of the proposed supplier; and

(H) A detailed justification of the reason for use of foreign construction materials cited in accordance with paragraph (b)(3) of this clause.

(ii) A request based on unreasonable cost shall include a reasonable survey of the market and a completed price comparison table in the format in paragraph (d) of this clause.

(iii) The price of construction material shall include all delivery costs to the construction site and any applicable duty (whether or not a duty-free certificate may be issued).

(iv) Any Contractor request for a determination submitted after contract award shall explain why the Contractor could not reasonably foresee the need for such determination and could not have requested the determination before contract award. If the Contractor does not submit a satisfactory explanation, the Contracting Officer need not make a determination.

(2) If the Government determines after contract award that an exception to the Buy American Act applies and the Contracting Officer and the Contractor negotiate adequate consideration, the Contracting Officer will modify the contract to allow use of the foreign construction material. However, when the basis for the exception is the unreasonable price of a domestic construction material, adequate consideration is not less than the differential established in paragraph (b)(4)(i) of this clause.

(3) Unless the Government determines that an exception to the Buy American Act applies, use of foreign construction material is noncompliant with the Buy American Act.

(d) Data. To permit evaluation of requests under paragraph (c) of this clause based on unreasonable cost, the Contractor shall include the following information and any applicable supporting data based on the survey of suppliers:

Foreign and Domestic Construction Materials Price Comparison

Construction material description	Unit of measure	Quantity	Price (dollars) \1\
Item 1:			
Foreign construction material....	.....	.....	.....
Domestic construction material...	.....	.....	.....
Item 2:			
Foreign construction material....	.....	.....	.....
Domestic construction material...	.....	.....	.....

\1\ Include all delivery costs to the construction site and any applicable duty (whether or not a duty-free entry certificate is issued).

List name, address, telephone number, and contact for suppliers surveyed. Attach copy of response; if oral, attach summary.

Include other applicable supporting information.

(End of clause)

52.226-1 UTILIZATION OF INDIAN ORGANIZATIONS AND INDIAN-OWNED ECONOMIC ENTERPRISES (JUN 2000)

(a) Definitions. As used in this clause:

"Indian" means any person who is a member of any Indian tribe, band, group, pueblo or community that is recognized by the Federal Government as eligible for services from the Bureau of Indian Affairs (BIA) in accordance with 25 U.S.C. 1452(c) and any ``Native" as defined in the Alaska Native Claims Settlement Act (43 U.S.C. 1601).

"Indian organization" means the governing body of any Indian tribe or entity established or recognized by the governing body of an Indian tribe for the purposes of 25 U.S.C., chapter 17.

"Indian-owned economic enterprise" means any Indian-owned (as determined by the Secretary of the Interior) commercial, industrial, or business activity established or organized for the purpose of profit, provided that Indian ownership constitutea not less than 51 percent of the enterprise.

"Indian tribe" means any Indian tribe, band, group, pueblo or community, including native villages and native groups (including corporations organized by Kenai, Juneau, Sitka, and Kodiak) as defined in the Alaska Native Claims Settlement Act, that is recognized by the Federal Government as eligible for services from BIA in accordance with 25 U.S.C. 1542(c).

"Interested party" means a prime contractor or an actual or prospective offeror whose direct economic interest would be affected by the award of a subcontract or by the failure to award a subcontract.

(b) The Contractor shall use its best efforts to give Indian organizations and Indian-owned economic enterprises (25 U.S.C. 1544) the maximum practicable opportunity to participate in the subcontracts it awards to the fullest extent consistent with efficient performance of its contract.

(1) The Contracting Officer and the Contractor, acting in good faith, may rely on the representation of an Indian organization or Indian-owned economic enterprise as to its eligibility, unless an
interested party challenges its status or the Contracting Officer has independent reason to question that status. In the event of a challenge to the representation of a subcontractor, the Contracting Officer will refer the matter to the U.S. Department of the Interior, Bureau of Indian Affairs (BIA), Attn: Chief, Division of
Contracting and Grants Administration, 1849 C Street, NW., MS 2626-MIB, Washington, DC 20240-4000.

The BIA will determine the eligibility and notify the Contracting Officer. No incentive payment will be made within 50 working days of subcontract award or while a challenge is pending. If a subcontractor is determined to be an ineligible participant, no incentive payment will be made under the Indian Incentive Program.

(2) The Contractor may request an adjustment under the Indian Incentive Program to the following:

(i) The estimated cost of a cost-type contract.

(ii) The target cost of a cost-plus-incentive-fee prime contract.

(iii) The target cost and ceiling price of a fixed-price incentive prime contract.

(iv) The price of a firm-fixed-price prime contract.

(3) The amount of the adjustment to the prime contract is 5 percent of the estimated cost, target cost, or firm-fixed-price included in the subcontract initially awarded to the Indian organization or Indian-owned economic enterprise.

(4) The Contractor has the burden of proving the amount claimed and must assert its request for an adjustment prior to completion of contract performance.

(c) The Contracting Officer, subject to the terms and conditions of the contract and the availability of funds, will authorize an incentive payment of 5 percent of the amount paid to the subcontractor. The Contracting Officer will seek funding in accordance with agency procedures.

(End of clause)

52.227-1 AUTHORIZATION AND CONSENT (JUL 1995)

(a) The Government authorizes and consents to all use and manufacture, in performing this contract or any subcontract at any tier, of any invention described in and covered by a United States patent (1) embodied in the structure or composition of any article the delivery of which is accepted by the Government under this contract or (2) used in machinery, tools, or methods whose use necessarily results from compliance by the Contractor or a subcontractor with (i) specifications or written provisions forming a part of this contract or (ii) specific written instructions given by the Contracting Officer directing the manner of performance. The entire liability to the Government for infringement of a patent of the United States shall be determined solely by the provisions of the indemnity clause, if any, included in this contract or any subcontract hereunder (including any lower-tier subcontract), and the Government assumes liability for all other infringement to the extent of the authorization and consent hereinabove granted.

(b) The Contractor agrees to include, and require inclusion of, this clause, suitably modified to identify the parties, in all subcontracts at any tier for supplies or services (including construction, architect-engineer services, and materials, supplies, models, samples, and design or testing services expected to exceed the simplified acquisition threshold (however, omission of this clause from any subcontract, including those at or below the simplified acquisition threshold, does not affect this authorization and consent.)

(End of clause)

52.227-4 PATENT INDEMNITY--CONSTRUCTION CONTRACTS (APR 1984)

Except as otherwise provided, the Contractor agrees to indemnify the Government and its officers, agents, and employees against liability, including costs and expenses, for infringement upon any United States patent (except a patent issued upon an application that is now or may hereafter be withheld from issue pursuant to a Secrecy Order under 35 U.S.C. 181) arising out of performing this contract or out of the use or disposal by or for the account of the Government of supplies furnished or work performed under this contract.

(End of clause)

52.228-1 BID GUARANTEE (SEP 1996)

(a) Failure to furnish a bid guarantee in the proper form and amount, by the time set for opening of bids, may be cause for rejection of the bid.

(b) The bidder shall furnish a bid guarantee in the form of a firm commitment, e.g., bid bond supported by good and sufficient surety or sureties acceptable to the Government, postal money order, certified check, cashier's check, irrevocable letter of credit, or, under Treasury Department regulations, certain bonds or notes of the United States. The Contracting Officer will return bid guarantees, other than bid bonds, (1) to unsuccessful bidders as soon as practicable after the opening of bids, and (2) to the successful bidder upon execution of contractual documents and bonds (including any necessary coinsurance or reinsurance agreements), as required by the bid as accepted.-

(c) The amount of the bid guarantee shall be 20 percent of the bid price or $3,000,000.00, whichever is less.-

(d) If the successful bidder, upon acceptance of its bid by the Government within the period specified for acceptance, fails to execute all contractual documents or furnish executed bond(s) within 10 days after receipt of the forms by the bidder, the Contracting Officer may terminate the contract for default.-

(e) In the event the contract is terminated for default, the bidder is liable for any cost of acquiring the work that exceeds the amount of its bid, and the bid guarantee is available to offset the difference.

(End of clause)

52.228-2 ADDITIONAL BOND SECURITY (OCT 1997)

The Contractor shall promptly furnish additional security required to protect the Government and persons supplying labor or materials under this contract if--

(a) Any surety upon any bond, or issuing financial institution for other security, furnished with this contract becomes unacceptable to the Government.

(b) Any surety fails to furnish reports on its financial condition as required by the Government;

(c) The contract price is increased so that the penal sum of any bond becomes inadequate in the opinion of the Contracting Officer; or

(d) An irrevocable letter of credit (ILC) used as security will expire before the end of the period of required security. If the Contractor does not furnish an acceptable extension or replacement ILC, or other acceptable substitute, at least 30 days before an ILC's scheduled expiration, the Contracting officer has the right to immediately draw on the ILC.

(End of clause)

52.228-11 PLEDGES OF ASSETS (FEB 1992)

(a) Offerors shall obtain from each person acting as an individual surety on a bid guarantee, a performance bond, or a payment bond--

(1) Pledge of assets; and

(2) Standard Form 28, Affidavit of Individual Surety.

(b) Pledges of assets from each person acting as an individual surety shall be in the form of--

(1) Evidence of an escrow account containing cash, certificates of deposit, commercial or Government securities, or other assets described in

FAR 28.203-2 (except see 28.203-2(b)(2) with respect to Government securities held in book entry form) and/or;

(2) A recorded lien on real estate. The offeror will be required to provide--

(i) Evidence of title in the form of a certificate of title prepared by a title insurance company approved by the United States Department of Justice. This title evidence must show fee simple title vested in the surety along with any concurrent owners; whether any real estate taxes are due and payable; and any recorded encumbrances against the property, including the lien filed in favor of the Government as required by FAR 28.203-3(d);

(ii) Evidence of the amount due under any encumbrance shown in the evidence of title;

(iii) A copy of the current real estate tax assessment of the property or a current appraisal dated no earlier than 6 months prior to the date of the bond, prepared by a professional appraiser who certifies that the appraisal has been conducted in accordance with the generally accepted appraisal standards as reflected in the Uniform Standards of Professional Appraisal Practice, as promulgated by the Appraisal Foundation.

(End of clause)

52.228-12 PROSPECTIVE SUBCONTRACTOR REQUESTS FOR BONDS. (OCT 1995)

In accordance with Section 806(a)(3) of Pub. L. 102-190, as amended by Sections 2091 and 8105 of Pub. L. 103-355, upon the request of a prospective subcontractor or supplier offering to furnish labor or material for the performance of this contract for which a payment bond has been furnished to the Government pursuant to the Miller Act, the Contractor shall promptly provide a copy of such payment bond to the requester.

(End of clause)

52.228-13 ALTERNATIVE PAYMENT PROTECTIONS (JULY 2000)

(a) The Contractor shall submit one of the following payment protections:

(i) a payment bond; or (ii) an irrevocable letter of credit (ILC).

(b) The amount of the payment protection shall be 100 percent of the contract price.

(c) The submission of the payment protection is required within 10 calendar days of contract award.

(d) The payment protection shall provide protection for the full contract performance period plus a one-year period.

(e) Except for escrow agreements and payment bonds, which provide their own protection procedures, the Contracting Officer is authorized to access funds under the payment protection when it has been alleged in writing by a supplier of labor or material that a nonpayment has occurred, and to withhold such funds pending resolution by administrative or judicial proceedings or mutual agreement of the parties.

(f) When a tripartite escrow agreement is used, the Contractor shall utilize only suppliers of labor and material that signed the escrow agreement.

(End of clause)

52.228-14 IRREVOCABLE LETTER OF CREDIT (DEC 1999)

(a) “Irrevocable letter of credit” (ILC), as used in this clause, means a written commitment by a federally insured financial institution to pay all or part of a stated amount of money, until the expiration date of the letter, upon presentation by the Government (the beneficiary) of a

written demand therefor. Neither the financial institution nor the offeror/Contractor can revoke or condition the letter of credit.

(b) If the offeror intends to use an ILC in lieu of a bid bond, or to secure other types of bonds such as performance and payment bonds, the letter of credit and letter of confirmation formats in paragraphs (e) and (f) of this clause shall be used.

(c) The letter of credit shall be irrevocable, shall require presentation of no document other than a written demand and the ILC (including confirming letter, if any), shall be issued/confirmed by an acceptable federally insured financial institution as provided in paragraph (d) of this clause, and--

(1) If used as a bid guarantee, the ILC shall expire no earlier than 60 days after the close of the bid acceptance period;

(2) If used as an alternative to corporate or individual sureties as security for a performance or payment bond, the offeror/Contractor may submit an ILC with an initial expiration date estimated to cover the entire period for which financial security is required or may submit an ILC with an initial expiration date that is a minimum period of one year from the date of issuance. The ILC shall provide that, unless the issuer provides the beneficiary written notice of non-renewal at least 60 days in advance of the current expiration date, the ILC is automatically extended without amendment for one year from the expiration date, or any future expiration date, until the period of required coverage is completed and the Contracting Officer provides the financial institution with a written statement waiving the right to payment. The period of required coverage shall be:

(i) For contracts subject to the Miller Act, the later of--

(A) One year following the expected date of final payment;

(B) For performance bonds only, until completion of any warranty period; or

(C) For payment bonds only, until resolution of all claims filed against the payment bond during the one-year period following final payment.

(ii) For contracts not subject to the Miller Act, the later of--

(A) 90 days following final payment; or

(B) For performance bonds only, until completion of any warranty period.

(d) Only federally insured financial institutions rated investment grade or higher shall issue or confirm the ILC. The offeror/Contractor shall provide the Contracting Officer a credit rating that indicates the financial institution has the required rating(s) as of the date of issuance of the ILC. Unless the financial institution issuing the ILC had letter of credit business of less than $25 million in the past year, ILCs over $5 million must be confirmed by another acceptable financial institution that had letter of credit business of less than $25 million in the past year.

(e) The following format shall be used by the issuing financial institution to create an ILC:

_____

[Issuing Financial Institution's Letterhead or Name and Address]

Issue Date _____

IRREVOCABLE LETTER OF CREDIT NO. _____

Account party's name _____

Account party's address _____

For Solicitation No. _____(for reference only)

TO: [U.S. Government agency]

[U.S. Government agency's address]

1. We hereby establish this irrevocable and transferable Letter of Credit in your favor for one or more drawings up to United States $_____. This Letter of Credit is payable at [issuing financial institution's and, if any, confirming financial institution's] office at [issuing financial institution's address and, if any, confirming financial institution's address] and expires with our close of business on _____, or any automatically extended expiration date.

2. We hereby undertake to honor your or the transferee's sight draft(s) drawn on the issuing or, if any, the confirming financial institution, for all or any part of this credit if presented with this Letter of Credit and confirmation, if any, at the office specified in paragraph 1 of this Letter of Credit on or before the expiration date or any automatically extended expiration date.

3. [This paragraph is omitted if used as a bid guarantee, and subsequent paragraphs are renumbered.] It is a condition of this Letter of Credit that it is deemed to be automatically extended without amendment for one year from the expiration date hereof, or any future expiration date, unless at least 60 days prior to any expiration date, we notify you or the transferee by registered mail, or other receipted means of delivery, that we elect not to consider this Letter of Credit renewed for any such additional period. At the time we notify you, we also agree to notify the account party (and confirming financial institution, if any) by the same means of delivery.

4. This Letter of Credit is transferable. Transfers and assignments of proceeds are to be effected without charge to either the beneficiary or the transferee/assignee of proceeds. Such transfer or assignment shall be only at the written direction of the Government (the beneficiary) in a form satisfactory to the issuing financial institution and the confirming financial institution, if any.

5. This Letter of Credit is subject to the Uniform Customs and Practice (UCP) for Documentary Credits, 1993 Revision, International Chamber of Commerce Publication No. 500, and to the extent not inconsistent therewith, to the laws of _____ [state of confirming financial institution, if any, otherwise state of issuing financial institution].

6. If this credit expires during an interruption of business of this financial institution as described in Article 17 of the UCP, the financial institution specifically agrees to effect payment if this credit is drawn against within 30 days after the resumption of our business.

Sincerely,

_____

[Issuing financial institution]

(f) The following format shall be used by the financial institution to confirm an ILC:

_____
[Confirming Financial Institution's Letterhead or Name and Address]

(Date) _____

Our Letter of Credit Advice Number _____

Beneficiary: _____ [U.S. Government agency]

Issuing Financial Institution: _____

Issuing Financial Institution's LC No.: _____

Gentlemen:

1. We hereby confirm the above indicated Letter of Credit, the original of which is attached, issued by _____ [name of issuing financial institution] for drawings of up to United States dollars _____/U.S. $_____ and expiring with our close of business on _____ [the expiration date], or any automatically extended expiration date.

2. Draft(s) drawn under the Letter of Credit and this Confirmation are payable at our office located at _____.

3. We hereby undertake to honor sight draft(s) drawn under and presented with the Letter of Credit and this Confirmation at our offices as specified herein.

4. [This paragraph is omitted if used as a bid guarantee, and subsequent paragraphs are renumbered.] It is a condition of this confirmation that it be deemed automatically extended without amendment for one year from the expiration date hereof, or any automatically extended expiration date, unless:

(a) At least 60 days prior to any such expiration date, we shall notify the Contracting Officer, or the transferee and the issuing financial institution, by registered mail or other receipted means of delivery, that we elect not to consider this confirmation extended for any such additional period; or

(b) The issuing financial institution shall have exercised its right to notify you or the transferee, the account party, and ourselves, of its election not to extend the expiration date of the Letter of Credit.

5. This confirmation is subject to the Uniform Customs and Practice (UCP) for Documentary Credits, 1993 Revision, International Chamber of Commerce Publication No. 500, and to the extent not inconsistent therewith, to the laws of _____ [state of confirming financial institution].

6. If this confirmation expires during an interruption of business of this financial institution as described in Article 17 of the UCP, we specifically agree to effect payment if this credit is drawn against within 30 days after the resumption of our business.

Sincerely,

_____

[Confirming financial institution]

(g) The following format shall be used by the Contracting Officer for a sight draft to draw on the Letter of Credit:

SIGHT DRAFT

_____

[City, State]

(Date) _____

[Name and address of financial institution]

Pay to the order of _____ [Beneficiary Agency] _____ the sum of United States $_____. This draft is drawn under Irrevocable Letter of Credit No. _____.

_____

[Beneficiary Agency]

By: _____

(End of clause)

52.228-15 PERFORMANCE AND PAYMENT BONDS--CONSTRUCTION (JUL 2000)-

(a) Definitions. As used in this clause--

Original contract price means the award price of the contract; or, for requirements contracts, the price payable for the estimated total quantity; or, for indefinite-quantity contracts, the price payable for the specified minimum quantity. Original contract price does not include the price of any options, except those options exercised at the time of contract award.

(b) Amount of required bonds. Unless the resulting contract price is $100,000 or less, the successful offeror shall furnish performance and payment bonds to the Contracting Officer as follows:

(1) Performance bonds (Standard Form 25). The penal amount of performance bonds at the time of contract award shall be 100 percent of the original contract price.

(2) Payment Bonds (Standard Form 25-A). The penal amount of payment bonds at the time of contract award shall be 100 percent of the original contract price.

(3) Additional bond protection. (i) The Government may require additional performance and payment bond protection if the contract price is increased. The increase in protection generally will equal 100 percent of the increase in contract price.

(ii) The Government may secure the additional protection by directing the Contractor to increase the penal amount of the existing bond or to obtain an additional bond.

(c) Furnishing executed bonds. The Contractor shall furnish all executed bonds, including any necessary reinsurance agreements, to the Contracting Officer, within the time period specified in the Bid Guarantee provision of the solicitation, or otherwise specified by the Contracting Officer, but in any event, before starting work.

(d) Surety or other security for bonds. The bonds shall be in the form of firm commitment, supported by corporate sureties whose names appear on the list contained in Treasury Department Circular 570, individual sureties, or by other acceptable security such as postal money order, certified check, cashier's check, irrevocable letter of credit, or, in accordance with Treasury Department regulations, certain bonds or notes of the United States. Treasury Circular 570 is published in the Federal Register or may be obtained from the U.S. Department of Treasury, Financial Management Service, Surety Bond Branch, 401 14th Street, NW, 2nd Floor, West Wing, Washington, DC 20227.

(e) Notice of subcontractor waiver of protection (40 U.S.C. 270b(c). Any waiver of the right to sue on the payment bond is void unless it is in writing, signed by the person whose right is waived, and executed after such person has first furnished labor or material for use in the performance of the contract.

(End of clause)

52.229-3 FEDERAL, STATE, AND LOCAL TAXES (APR 2003)

(a) As used in this clause--

"Contract date" means the date set for bid opening or, if this is a negotiated contract or a modification, the effective date of this contract or modification.

"All applicable Federal, State, and local taxes and duties" means all taxes and duties, in effect on the contract date, that the taxing authority is imposing and collecting on the transactions or property covered by this contract.

"After-imposed Federal tax" means any new or increased Federal excise tax or duty, or tax that was exempted or excluded on the contract date but whose exemption was later revoked or reduced during the contract period, on the transactions or property covered by this contract that the Contractor is required to pay or bear as the result of legislative, judicial, or administrative action taking effect after the contract date. It does not include social security tax or other employment taxes.

"After-relieved Federal tax" means any amount of Federal excise tax or duty, except social security or other employment taxes, that would otherwise have been payable on the transactions or property covered by this contract, but which the Contractor is not required to pay or bear,

or for which the Contractor obtains a refund or drawback, as the result of legislative, judicial, or administrative action taking effect after the contract date.

Local taxes includes taxes imposed by a possession or territory of the United States, Puerto Rico, or the Northern Mariana Islands, if the contract is performed wholly or partly in any of those areas.

(b) The contract price includes all applicable Federal, State, and local taxes and duties.

(c) The contract price shall be increased by the amount of any after-imposed Federal tax, provided the Contractor warrants in writing that no amount for such newly imposed Federal excise tax or duty or rate increase was included in the contract price, as a contingency reserve or otherwise.

(d) The contract price shall be decreased by the amount of any after-relieved Federal tax.

(e) The contract price shall be decreased by the amount of any Federal excise tax or duty, except social security or other employment taxes, that the Contractor is required to pay or bear, or does not obtain a refund of, through the Contractor's fault, negligence, or failure to follow instructions of the Contracting Officer.

(f) No adjustment shall be made in the contract price under this clause unless the amount of the adjustment exceeds $250.

(g) The Contractor shall promptly notify the Contracting Officer of all matters relating to any Federal excise tax or duty that reasonably may be expected to result in either an increase or decrease in the contract price and shall take appropriate action as the Contracting Officer directs.

(h) The Government shall, without liability, furnish evidence appropriate to establish exemption from any Federal, State, or local tax when the Contractor requests such evidence and a reasonable basis exists to sustain the exemption.

(End of clause)

52.232-5 PAYMENTS UNDER FIXED-PRICE CONSTRUCTION CONTRACTS (SEP 2002)

(a) Payment of price. The Government shall pay the Contractor the contract price as provided in this contract.

(b) Progress payments. The Government shall make progress payments monthly as the work proceeds, or at more frequent intervals as determined by the Contracting Officer, on estimates of work accomplished which meets the standards of quality established under the contract, as approved by the Contracting Officer.

(1) The Contractor's request for progress payments shall include the following substantiation:

(i) An itemization of the amounts requested, related to the various elements of work required by the contract covered by the payment requested.

(ii) A listing of the amount included for work performed by each subcontractor under the contract.

(iii) A listing of the total amount of each subcontract under the contract.

(iv) A listing of the amounts previously paid to each such subcontractor under the contract.

(v) Additional supporting data in a form and detail required by the Contracting Officer.

(2) In the preparation of estimates, the Contracting Officer may authorize material delivered on the site and preparatory work done to be taken into consideration. Material delivered to the Contractor at locations other than the site also may be taken into consideration if--

(i) Consideration is specifically authorized by this contract; and

(ii) The Contractor furnishes satisfactory evidence that it has acquired title to such material and that the material will be used to perform this contract.

(c) Contractor certification. Along with each request for progress payments, the Contractor shall furnish the following certification, or payment shall not be made: (However, if the Contractor elects to delete paragraph (c)(4) from the certification, the certification is still acceptable.)

I hereby certify, to the best of my knowledge and belief, that--

(1) The amounts requested are only for performance in accordance with the specifications, terms, and conditions of the contract;

(2) All payments due to subcontractors and suppliers from previous payments received under the contract have been made, and timely payments will be made from the proceeds of the payment covered by this certification, in accordance with subcontract agreements and the requirements of chapter 39 of Title 31, United States Code;

(3) This request for progress payments does not include any amounts which the prime contractor intends to withhold or retain from a subcontractor or supplier in accordance with the terms and conditions of the subcontract; and

(4) This certification is not to be construed as final acceptance of a subcontractor's performance.

_____

(Name)

_____

(Title)

_____

(Date)

(d) Refund of unearned amounts. If the Contractor, after making a certified request for progress payments, discovers that a portion or all of such request constitutes a payment for performance by the Contractor that fails to conform to the specifications, terms, and conditions of this contract (hereinafter referred to as the "unearned amount"), the Contractor shall--

(1) Notify the Contracting Officer of such performance deficiency; and

(2) Be obligated to pay the Government an amount (computed by the Contracting Officer in the manner provided in paragraph (j) of this clause) equal to interest on the unearned amount from the 8th day after the date of receipt of the unearned amount until--

(i) The date the Contractor notifies the Contracting Officer that the performance deficiency has been corrected; or

(ii) The date the Contractor reduces the amount of any subsequent certified request for progress payments by an amount equal to the unearned amount.

(e) Retainage. If the Contracting Officer finds that satisfactory progress was achieved during any period for which a progress payment is to be made, the Contracting Officer shall authorize payment to be made in full. However, if satisfactory progress has not been made, the Contracting Officer may retain a maximum of 10 percent of the amount of the payment until satisfactory progress is achieved. When the work is substantially complete, the Contracting Officer may retain from previously withheld funds and future progress payments that amount the Contracting Officer considers adequate for protection of the Government and shall release to the Contractor all the remaining withheld funds. Also, on completion and acceptance of each separate building, public work, or other division of the contract, for which the price is stated separately in the contract, payment shall be made for the completed work without retention of a percentage.

(f) Title, liability, and reservation of rights. All material and work covered by progress payments made shall, at the time of payment, become the sole property of the Government, but this shall not be construed as--

(1) Relieving the Contractor from the sole responsibility for all material and work upon which payments have been made or the restoration of any damaged work; or

(2) Waiving the right of the Government to require the fulfillment of all of the terms of the contract.

(g) Reimbursement for bond premiums. In making these progress payments, the Government shall, upon request, reimburse the Contractor for the amount of premiums paid for performance and payment bonds (including coinsurance and reinsurance agreements, when applicable) after the Contractor has furnished evidence of full payment to the surety. The retainage provisions in paragraph (e) of this clause shall not apply to that portion of progress payments attributable to bond premiums.

(h) Final payment. The Government shall pay the amount due the Contractor under this contract after--

(1) Completion and acceptance of all work;

(2) Presentation of a properly executed voucher; and

(3) Presentation of release of all claims against
the Government arising by virtue of this contract, other than claims, in stated amounts, that the Contractor has specifically excepted from the operation of the release. A release may also be required of the assignee if the Contractor's claim to amounts payable under this contract has been assigned under the Assignment of Claims Act of 1940 (31 U.S.C. 3727 and 41 U.S.C. 15).

(i) Limitation because of undefinitized work. Notwithstanding any provision of this contract, progress payments shall not exceed 80 percent on work accomplished on undefinitized contract actions. A "contract action" is any action resulting in a contract, as defined in FAR Subpart 2.1, including contract modifications for additional supplies or services, but not including contract modifications that are within the scope and under the terms of the contract, such as contract modifications issued pursuant to the Changes clause, or funding and other administrative changes.

(j) Interest computation on unearned amounts. In accordance with 31 U.S.C. 3903(c)(1), the amount payable under subparagraph (d)(2) of this clause shall be--

(1) Computed at the rate of average bond equivalent rates of 91-day Treasury bills auctioned at the most recent auction of such bills prior to the date the Contractor receives the unearned amount; and

(2) Deducted from the next available payment to the Contractor.

(End of clause)

52.232-17 INTEREST (JUNE 1996)

(a) Except as otherwise provided in this contract under a Price Reduction for Defective Cost or Pricing Data clause or a Cost Accounting Standards clause, all amounts that become payable by the Contractor to the Government under this contract (net of any applicable tax credit under the Internal Revenue Code (26 U.S.C. 1481)) shall bear simple interest from the date due until paid unless paid within 30 days of becoming due. The interest rate shall be the interest rate established by the Secretary of the Treasury as provided in Section 12 of the Contract Disputes Act of 1978 (Public Law 95-563), which is applicable to the period in which the amount becomes due, as provided in paragraph (b) of this clause, and then at the rate applicable for each six-month period as fixed by the Secretary until the amount is paid. reproduce, prepare derivative works, distribute copies to the public, and (b) Amounts shall be due at the earliest of the following dates:

(1) The date fixed under this contract.

(2) The date of the first written demand for payment consistent with this contract, including any demand resulting from a default termination.

(3) The date the Government transmits to the Contractor a proposed supplemental agreement to confirm completed negotiations establishing the amount of debt.

(4) If this contract provides for revision of prices, the date of written notice to the Contractor stating the amount of refund payable in connection with a pricing proposal or a negotiated pricing agreement not confirmed by contract modification.

(c) The interest charge made under this clause may be reduced under the procedures prescribed in 32.614-2 of the Federal Acquisition Regulation in effect on the date of this contract.

(End of clause)

52.232-23 ASSIGNMENT OF CLAIMS (JAN 1986)

(a) The Contractor, under the Assignment of Claims Act, as amended, 31 U.S.C. 3727, 41 U.S.C. 15 (hereafter referred to as "the Act"), may assign its rights to be paid amounts due or to become due as a result of the performance of this contract to a bank, trust company, or other financing institution, including any Federal lending agency. The assignee under such an assignment may thereafter further assign or reassign its right under the original assignment to any type of financing institution described in the preceding sentence.

(b) Any assignment or reassignment authorized under the Act and this clause shall cover all unpaid amounts payable under this contract, and shall not be made to more than one party, except that an assignment or reassignment may be made to one party as agent or trustee for two or more parties participating in the financing of this contract.

(c) The Contractor shall not furnish or disclose to any assignee under this contract any classified document (including this contract) or information related to work under this contract until the Contracting Officer authorizes such action in writing.

(End of clause)

52.232-27 PROMPT PAYMENT FOR CONSTRUCTION CONTRACTS (OCT 2003)

Notwithstanding any other payment terms in this contract, the Government will make invoice payments under the terms and conditions specified in this clause. The Government considers payment as being made on the day a check is dated or the date of an electronic funds transfer. Definitions of pertinent terms are set forth in sections 2.101, 32.001, and 32.902 of the Federal Acquisition Regulation. All days referred to in this clause are calendar days, unless otherwise specified. (However, see paragraph (a)(3) concerning payments due on Saturdays, Sundays, and legal holidays.)

(a) Invoice payments--(1) Types of invoice payments. For purposes of this clause, there are several types of invoice payments that may occur under this contract, as follows:

(i) Progress payments, if provided for elsewhere in this contract, based on Contracting Officer approval of the estimated amount and value of work or services performed, including payments for reaching milestones in any project.

(A) The due date for making such payments is 14 days after the designated billing office receives a proper payment request. If the designated billing office fails to annotate the payment request with the actual date of receipt at the time of receipt, the payment due date is the 14th day after the date of the Contractor's payment request, provided the designated billing office receives a proper payment request and there is no disagreement over quantity, quality, or Contractor compliance with contract requirements.

(B) The due date for payment of any amounts retained by the Contracting Officer in accordance with the clause at 52.232-5, Payments Under Fixed-Price Construction Contracts, is as specified in the contract or, if not specified, 30 days after approval by the Contracting Officer for release to the Contractor.

(ii) Final payments based on completion and acceptance of all work and presentation of release of all claims against the Government arising by virtue of the contract, and payments for partial deliveries that have been accepted by the Government (e.g., each separate building, public work, or other division of the contract for which the price is stated separately in the contract).

(A) The due date for making such payments is the later of the following two events:

(1) The 30th day after the designated billing office receives a proper invoice from the Contractor.

(2) The 30th day after Government acceptance of the work or services completed by the Contractor. For a final invoice when the payment amount is subject to contract settlement actions (e.g., release of claims), acceptance is deemed to occur on the effective date of the contract settlement.

(B) If the designated billing office fails to annotate the invoice with the date of actual receipt at the time of receipt, the invoice payment due date is the 30th day after the date of the Contractor's invoice, provided the designated billing office receives a proper invoice and there is no disagreement over quantity, quality, or Contractor compliance with contract requirements.

(2) Contractor's invoice. The Contractor shall prepare and submit invoices to the designated billing office specified in the contract. A proper invoice must include the items listed in paragraphs (a)(2)(i) through (a)(2)(xi) of this clause. If the invoice does not comply with these requirements, the designated billing office must return it within 7 days after receipt, with the reasons why it is not a proper invoice. When computing any interest penalty owed the Contractor, the Government will take into account if the Government notifies the Contractor of an improper invoice in an untimely manner.

(i) Name and address of the Contractor.

(ii) Invoice date and invoice number. (The Contractor should date invoices as close as possible to the date of mailing or transmission.)

(iii) Contract number or other authorization for work or services performed (including order number and contract line item number).

(iv) Description of work or services performed.

(v) Delivery and payment terms (e.g., discount for prompt payment terms).

(vi) Name and address of Contractor official to whom payment is to be sent (must be the same as that in the contract or in a proper notice of assignment).

(vii) Name (where practicable), title, phone number, and mailing address of person to notify in the event of a defective invoice.

(viii) For payments described in paragraph (a)(1)(i) of this clause, substantiation of the amounts requested and certification in accordance with the requirements of the clause at 52.232-5, Payments Under Fixed-Price Construction Contracts.

(ix) Taxpayer Identification Number (TIN). The Contractor shall include its TIN on the invoice only if required elsewhere in this contract.

(x) Electronic funds transfer (EFT) banking information.

(A) The Contractor shall include EFT banking information on the invoice only if required elsewhere in this contract.

(B) If EFT banking information is not required to be on the invoice, in order for the invoice to be a proper invoice, the Contractor shall have submitted correct EFT banking information in accordance with the applicable solicitation provision (e.g., 52.232-38, Submission of Electronic Funds Transfer Information with Offer), contract clause (e.g., 52.232-33, Payment by Electronic Funds Transfer--Central Contractor Registration, or 52.232-34, Payment by Electronic Funds Transfer--Other Than Central Contractor Registration), or applicable agency procedures.

(C) EFT banking information is not required if the Government waived the requirement to pay by EFT.

(xi) Any other information or documentation required by the contract.

(3) Interest penalty. The designated payment office will pay an interest penalty automatically, without request from the Contractor, if payment is not made by the due date and the conditions listed in paragraphs (a)(3)(i) through (a)(3)(iii) of this clause are met, if applicable. However, when the due date falls on a Saturday, Sunday, or legal holiday, the designated payment office may make payment on the following working day without incurring a late payment interest penalty.

(i) The designated billing office received a proper invoice.

(ii) The Government processed a receiving report or other Government documentation authorizing payment and there was no disagreement over quantity, quality, Contractor compliance with any contract term or condition, or requested progress payment amount.

(iii) In the case of a final invoice for any balance of funds due the Contractor for work or services performed, the amount was not subject to further contract settlement actions between the Government and the Contractor.

(4) Computing penalty amount. The Government will compute the interest penalty in accordance with the Office of Management and Budget prompt payment regulations at 5 CFR part 1315.

(i) For the sole purpose of computing an interest penalty that might be due the Contractor for payments described in paragraph (a)(1)(ii) of this clause, Government acceptance or approval is deemed to occur constructively on the 7th day after the Contractor has completed the work or services in accordance with the terms and conditions of the contract. If actual acceptance or approval occurs within the constructive acceptance or approval period, the Government will base the determination of an interest penalty on the actual date of acceptance or approval. Constructive acceptance or constructive approval requirements do not apply if there is a disagreement over quantity, quality, or Contractor compliance with a contract provision. These requirements also do not compel Government officials to accept work or services, approve Contractor estimates, perform contract administration functions, or make payment prior to fulfilling their responsibilities.

(ii) The prompt payment regulations at 5 CFR 1315.10(c) do not require the Government to pay interest penalties if payment delays are due to disagreement between the Government and the Contractor over the payment amount or other issues involving contract compliance, or on amounts temporarily withheld or retained in accordance with the terms of the contract. The Government and the Contractor shall resolve claims involving disputes, and any interest that may be payable in accordance with the clause at FAR 52.233-1, Disputes.

(5) Discounts for prompt payment. The designated payment office will pay an interest penalty automatically, without request from the Contractor, if the Government takes a discount for prompt payment improperly. The Government will calculate the interest penalty in accordance with the prompt payment regulations at 5 CFR part 1315.

(6) Additional interest penalty. (i) The designated payment office will pay a penalty amount, calculated in accordance with the prompt payment regulations at 5 CFR part 1315 in addition to the interest penalty amount only if--

(A) The Government owes an interest penalty of $1 or more;

(B) The designated payment office does not pay the interest penalty within 10 days after the date the invoice amount is paid; and

(C) The Contractor makes a written demand to the designated payment office for additional penalty payment, in accordance with paragraph (a)(6)(ii) of this clause, postmarked not later than 40 days after the date the invoice amount is paid.

(ii)(A) The Contractor shall support written demands for additional penalty payments with the following data. The Government will not request any additional data. The Contractor shall--

(1) Specifically assert that late payment interest is due under a specific invoice, and request payment of all overdue late payment interest penalty and such additional penalty as may be required;

(2) Attach a copy of the invoice on which the unpaid late payment interest was due; and

(3) State that payment of the principal has been received, including the date of receipt.

(B) If there is no postmark or the postmark is illegible--

(1) The designated payment office that receives the demand will annotate it with the date of receipt provided the demand is received on or before the 40th day after payment was made; or

(2) If the designated payment office fails to make the required annotation, the Government will determine the demand's validity based on the date the Contractor has placed on the demand, provided such date is no later than the 40th day after payment was made.

(b) Contract financing payments. If this contract provides for contract financing, the Government will make contract financing payments in accordance with the applicable contract financing clause.

(c) Subcontract clause requirements. The Contractor shall include in each subcontract for property or services (including a material supplier) for the purpose of performing this contract the following:

(1) Prompt payment for subcontractors. A payment clause that obligates the Contractor to pay the subcontractor for satisfactory performance under its subcontract not later than 7 days from receipt of payment out of such amounts as are paid to the Contractor under this contract.

(2) Interest for subcontractors. An interest penalty clause that obligates the Contractor to pay to the subcontractor an interest penalty for each payment not made in accordance with the payment clause--

(i) For the period beginning on the day after the required payment date and ending on the date on which payment of the amount due is made; and

(ii) Computed at the rate of interest established by the Secretary of the Treasury, and published in the Federal Register, for interest payments under section 12 of the Contract Disputes Act of 1978 (41 U.S.C. 611) in effect at the time the Contractor accrues the obligation to pay an interest penalty.

(3) Subcontractor clause flowdown. A clause requiring each subcontractor to use:

(i) Include a payment clause and an interest penalty clause conforming to the standards set forth in paragraphs (c)(1) and (c)(2) of this clause in each of its subcontracts; and

(ii) Require each of its subcontractors to include such clauses in their subcontracts with each lower-tier subcontractor or supplier.

(d) Subcontract clause interpretation. The clauses required by paragraph (c) of this clause shall not be construed to impair the right of the Contractor or a subcontractor at any tier to negotiate, and to include in their subcontract, provisions that--

(1) Retainage permitted. Permit the Contractor or a subcontractor to retain (without cause) a specified percentage of each progress payment otherwise due to a subcontractor for satisfactory performance under the subcontract without incurring any obligation to pay a late payment interest penalty, in accordance with terms and conditions agreed to by the parties to the subcontract, giving such recognition as the parties deem appropriate to the ability of a subcontractor to furnish a performance bond and a payment bond;

(2) Withholding permitted. Permit the Contractor or subcontractor to make a determination that part or all of the subcontractor's request for payment may be withheld in accordance with the subcontract agreement; and

(3) Withholding requirements. Permit such withholding without incurring any obligation to pay a late payment penalty if--

(i) A notice conforming to the standards of paragraph (g) of this clause previously has been furnished to the subcontractor; and

(ii) The Contractor furnishes to the Contracting Officer a copy of any notice issued by a Contractor pursuant to paragraph (d)(3)(i) of this clause.

(e) Subcontractor withholding procedures. If a Contractor, after making a request for payment to the Government but before making a payment to a subcontractor for the subcontractor's performance covered by the payment request, discovers that all or a portion of the payment otherwise due such subcontractor is subject to withholding from the subcontractor in accordance with the subcontract agreement, then the Contractor shall--

(1) Subcontractor notice. Furnish to the subcontractor a notice conforming to the standards of paragraph (g) of this clause as soon as practicable upon ascertaining the cause giving rise to a withholding, but prior to the due date for subcontractor payment;

(2) Contracting Officer notice. Furnish to the Contracting Officer, as soon as practicable, a copy of the notice furnished to the subcontractor pursuant to paragraph (e)(1) of this clause;

(3) Subcontractor progress payment reduction. Reduce the subcontractor's progress payment by an amount not to exceed the amount specified in the notice of withholding furnished under paragraph (e)(1) of this clause;

(4) Subsequent subcontractor payment. Pay the subcontractor as soon as practicable after the correction of the identified subcontract performance deficiency, and--

(i) Make such payment within--

(A) Seven days after correction of the identified subcontract performance deficiency (unless the funds therefor must be recovered from the Government because of a reduction under paragraph
(e)(5)(i)) of this clause; or

(B) Seven days after the Contractor recovers such funds from the Government; or

(ii) Incur an obligation to pay a late payment interest penalty computed at the rate of interest established by the Secretary of the Treasury, and published in the Federal Register, for interest payments under section 12 of the Contracts Disputes Act of 1978 (41 U.S.C. 611) in effect at the time the Contractor accrues the obligation to pay an interest penalty;

(5) Notice to Contracting Officer. Notify the Contracting Officer upon--

(i) Reduction of the amount of any subsequent certified application for payment; or

(ii) Payment to the subcontractor of any withheld amounts of a progress payment, specifying--

(A) The amounts withheld under paragraph (e)(1) of this clause; and

(B) The dates that such withholding began and ended; and

(6) Interest to Government. Be obligated to pay to the Government an amount equal to interest on the withheld payments (computed in the manner provided in 31 U.S.C. 3903(c)(1)), from the 8th day after receipt of the withheld amounts from the Government until--

(i) The day the identified subcontractor performance deficiency is corrected; or

(ii) The date that any subsequent payment is reduced under paragraph (e)(5)(i) of this clause.

(f) Third-party deficiency reports--(1) Withholding from subcontractor. If a Contractor, after making payment to a first-tier subcontractor, receives from a supplier or subcontractor of the first-tier subcontractor (hereafter referred to as a “second-tier subcontractor”) a written notice in accordance with section 2 of the Act of August 24, 1935 (40 U.S.C. 270b, Miller Act), asserting a deficiency in such first-tier subcontractor's performance under the contract for which the Contractor may be ultimately liable, and the Contractor determines that all or a portion of future payments otherwise due such first-tier subcontractor is subject to withholding in accordance with the subcontract agreement, the Contractor may, without incurring an obligation to pay an interest penalty under paragraph (e)(6) of this clause--

(i) Furnish to the first-tier subcontractor a notice conforming to the standards of paragraph (g) of this clause as soon as practicable upon making such determination; and

(ii) Withhold from the first-tier subcontractor's next available progress payment or payments an amount not to exceed the amount specified in the notice of withholding furnished under paragraph (f)(1)(i) of this clause.

(2) Subsequent payment or interest charge. As soon as practicable, but not later than 7 days after receipt of satisfactory written notification that the identified subcontract performance deficiency has been corrected, the Contractor shall--

(i) Pay the amount withheld under paragraph (f)(1)(ii) of this clause to such first-tier subcontractor; or

(ii) Incur an obligation to pay a late payment interest penalty to such first-tier subcontractor computed at the rate of interest established by the Secretary of the Treasury, and published in the Federal Register, for interest payments under section 12 of the Contracts DisputesAct of 1978 (41 U.S.C. 611) in effect at the time the Contractor accrues the obligation to pay an interest penalty.

(g) Written notice of subcontractor withholding. The Contractor shall issue a written notice of any withholding to a subcontractor (with a copy furnished to the Contracting Officer), specifying--

(1) The amount to be withheld;

(2) The specific causes for the withholding under the terms of the subcontract; and

(3) The remedial actions to be taken by the subcontractor in order to receive payment of the amounts withheld.

(h) Subcontractor payment entitlement. The Contractor may not request payment from the Government of any amount withheld or retained in accordance with paragraph (d) of this clause until such time as the Contractor has determined and certified to the Contracting Officer that the subcontractor is entitled to the payment of such amount.

(i) Prime-subcontractor disputes. A dispute between the Contractor and subcontractor relating to the amount or entitlement of a subcontractor to a payment or a late payment interest penalty under a clause included in the subcontract pursuant to paragraph (c) of this clause does not constitute a dispute to which the Government is a party. The Government may not be interpleaded in any judicial or administrative proceeding involving such a dispute.

(j) Preservation of prime-subcontractor rights. Except as provided in paragraph (i) of this clause, this clause shall not limit or impair any contractual, administrative, or judicial remedies otherwise available to the Contractor or a subcontractor in the event of a dispute involving late payment or nonpayment by the Contractor or deficient subcontract performance or nonperformance by a subcontractor.

(k) Non-recourse for prime contractor interest penalty. The Contractor's obligation to pay an interest penalty to a subcontractor pursuant to the clauses included in a subcontract under paragraph (c) of this clause shall not be construed to be an obligation of the Government for such interest penalty. A cost-reimbursement claim may not include any amount for reimbursement of such interest penalty.

(l) Overpayments. If the Contractor becomes aware of a duplicate contract financing or invoice payment or that the Government has otherwise overpaid on a contract financing or invoice payment, the Contractor shall immediately notify the Contracting Officer and request instructions for disposition of the overpayment.

(End of clause)

52.233-1 DISPUTES. (JUL 2002)

(a) This contract is subject to the Contract Disputes Act of 1978, as amended (41 U.S.C. 601-613).

(b) Except as provided in the Act, all disputes arising under or relating to this contract shall be resolved under this clause.

(c) Claim, as used in this clause, means a written demand or written assertion by one of the contracting parties seeking, as a matter of right, the payment of money in a sum certain, the adjustment or interpretation of contract terms, or other relief arising under or relating to this contract. However, a written demand or written assertion by the Contractor seeking the payment of money exceeding $100,000 is not a claim under the Act until certified. A voucher, invoice, or other routine request for payment that is not in dispute when submitted is not a claim under the Act. The submission may be converted to a claim under the Act, by complying with the submission and certification requirements of this clause, if it is disputed either as to liability or amount or is not acted upon in a reasonable time.

(d)(1) A claim by the Contractor shall be made in writing and, unless otherwise stated in this contract, submitted within 6 years after accrual of the claim to the Contracting Officer for a written decision. A claim by the Government against the Contractor shall be subject to a written decision by the Contracting Officer.

(2)(i) The contractors shall provide the certification specified in subparagraph (d)(2)(iii) of this clause when submitting any claim -

(A) Exceeding $100,000; or

(B) Regardless of the amount claimed, when using -

(1) Arbitration conducted pursuant to 5 U.S.C. 575-580; or

(2) Any other alternative means of dispute resolution (ADR) technique that the agency elects to handle in accordance with the Administrative Dispute Resolution Act (ADRA).

(ii) The certification requirement does not apply to issues in controversy that have not been submitted as all or part of a claim.

(iii) The certification shall state as follows: "I certify that the claim is made in good faith; that the supporting data are accurate and complete to the best of my knowledge and belief; that the amount requested accurately reflects the contract adjustment for which the Contractor believes the Government is liable; and that I am duly authorized to certify the claim on behalf of the Contractor.

(3) The certification may be executed by any person duly authorized to bind the Contractor with respect to the claim.

(e) For Contractor claims of $100,000 or less, the Contracting Officer must, if requested in writing by the Contractor, render a decision within 60 days of the request. For Contractor-certified claims over $100,000, the Contracting Officer must, within 60 days, decide the claim or notify the Contractor of the date by which the decision will be made.

(f) The Contracting Officer's decision shall be final unless the Contractor appeals or files a suit as provided in the Act.

(g) If the claim by the Contractor is submitted to the Contracting Officer or a claim by the Government is presented to the Contractor, the parties, by mutual consent, may agree to use alternative disput resolution (ADR). If the Contractor refuses an offer for ADR, the Contractor shall inform the Contracting Officer, in writing, of the Contractor's specific reasons for rejecting the request.

(h) The Government shall pay interest on the amount found due and unpaid from (1) the date the Contracting Officer receives the claim (certified, if required); or (2) the date that payment otherwise would be due, if that date is later, until the date of payment. With regard to claims having defective certifications, as defined in (FAR) 48 CFR 33.201, interest shall be paid from the date that the Contracting Officer initially receives the claim. Simple interest on claims shall be paid at the rate, fixed by the Secretary of the Treasury as provided in the Act, which is applicable to the period during which the Contracting Officer receives the claim and then at the rate applicable for each 6-month period as fixed by the Treasury Secretary during the pendency of the claim.

(i) The Contractor shall proceed diligently with performance of this contract, pending final resolution of any request for relief, claim, appeal, or action arising under the contract, and comply with any decision of the Contracting Officer.

(End of clause)

52.233-3 PROTEST AFTER AWARD (AUG. 1996)

(a) Upon receipt of a notice of protest (as defined in FAR 33.101) or a determination that a protest is likely (see FAR 33.102(d)), the Contracting Officer may, by written order to the Contractor, direct the Contractor to stop performance of the work called for by this contract. The order shall be specifically identified as a stop-work order issued under this clause. Upon receipt of the order, the Contractor shall immediately comply with its terms and take all reasonable steps to minimize the incurrence of costs allocable to the work covered by the order during the period of work stoppage. Upon receipt of the final decision in the protest, the Contracting Officer shall either--

(1) Cancel the stop-work order; or

(2) Terminate the work covered by the order as provided in the Default, or the Termination for Convenience of the Government, clause of this contract.

(b) If a stop-work order issued under this clause is canceled either before or after a final decision in the protest, the Contractor shall resume work. The Contracting Officer shall make an equitable adjustment in the delivery schedule or contract price, or both, and the contract shall be modified, in writing, accordingly, if--

(1) The stop-work order results in an increase in the time required for, or in the Contractor's cost properly allocable to, the performance of any part of this contract; and

(2) The Contractor asserts its right to an adjustment within 30 days after the end of the period of work stoppage; provided, that if the Contracting Officer decides the facts justify the action, the Contracting Officer may receive and act upon a proposal at any time before final payment under this contract.

(c) If a stop-work order is not canceled and the work covered by the order is terminated for the convenience of the Government, the Contracting Officer shall allow reasonable costs resulting from the stop-work order in arriving at the termination settlement.

(d) If a stop-work order is not canceled and the work covered by the order is terminated for default, the Contracting Officer shall allow, by equitable adjustment or otherwise, reasonable costs resulting from the stop-work order.

(e) The Government's rights to terminate this contract at any time are not affected by action taken under this clause.

(f) If, as the result of the Contractor's intentional or negligent misstatement, misrepresentation, or miscertification, a protest related to this contract is sustained, and the Government pays costs, as provided in FAR 33.102(b)(2) or 33.104(h)(1), the Government may require the Contractor to reimburse the Government the amount of such costs. In addition to any other remedy available, and pursuant to the requirements of Subpart 32.6, the Government may collect this debt by offsetting the amount against any payment due the Contractor under any contract between the Contractor and the Government.

(End of clause)

52.236-2 DIFFERING SITE CONDITIONS (APR 1984)

As prescribed in 36.502, insert the following clause in solicitations and contracts when a fixed-price construction contract or a fixed-price dismantling, demolition, or removal of improvements contract is contemplated and the contract amount is expected to exceed the small purchase limitation. The Contracting Officer may insert the clause in solicitations and contracts when a fixed-price construction or a fixed-price contract for dismantling, demolition, or removal of improvements is contemplated and the contract amount is expected to be within the small purchase limitation.

(a) The Contractor shall promptly, and before the conditions are disturbed, give a written notice to the Contracting Officer of

(1) subsurface or latent physical conditions at the site which differ materially from those indicated in this contract, or

(2) unknown physical conditions at the site, of an unusual nature, which differ materially from those ordinarily encountered and generally recognized as inhering in work of the character provided for in the contract.

(b) The Contracting Officer shall investigate the site conditions promptly after receiving the notice. If the conditions do materially so differ and cause an increase or decrease in the Contractor's cost of, or the time required for, performing any part of the work under this contract, whether or not changed as a result of the conditions, an equitable adjustment shall be made under this clause and the contract modified in writing accordingly.

(c) No request by the Contractor for an equitable adjustment to the contract under this clause shall be allowed, unless the Contractor has given the written notice required; provided, that the time prescribed in (a) above for giving written notice may be extended by the Contracting Officer.

(d) No request by the Contractor for an equitable adjustment to the contract for differing site conditions shall be allowed if made after final payment under this contract.

(End of clause)

52.236-3 SITE INVESTIGATION AND CONDITIONS AFFECTING THE WORK (APR 1984)

(a) The Contractor acknowledges that it has taken steps reasonably necessary to ascertain the nature and location of the work, and that it has investigated and satisfied itself as to the general and local conditions which can affect the work or its cost, including but not limited to

(1) conditions bearing upon transportation, disposal, handling, and storage of materials;

(2) the availability of labor, water, electric power, and roads;

(3) uncertainties of weather, river stages, tides, or similar physical conditions at the site;

(4) the conformation and conditions of the ground; and (5) the character of equipment and facilities needed preliminary to and during work performance. The Contractor also acknowledges that it has satisfied itself as to the character, quality, and quantity of surface and subsurface materials or obstacles to be encountered insofar as this information is reasonably ascertainable from an inspection of the site, including all exploratory work done by the Government, as well as from the drawings and specifications made a part of this contract. Any failure of the Contractor to take the actions described and acknowledged in this paragraph will not relieve the Contractor from responsibility for estimating properly the difficulty and cost of successfully performing the work, or for proceeding to successfully perform the work without additional expense to the Government.

(b) The Government assumes no responsibility for any conclusions or interpretations made by the Contractor based on the information made available by the Government. Nor does the Government assume responsibility for any understanding reached or representation made concerning conditions which can affect the work by any of its officers or agents before the execution of this contract, unless that understanding or representation is expressly stated in this contract.

(End of clause)

52.236-5 MATERIAL AND WORKMANSHIP (APR 1984)

(a) All equipment, material, and articles incorporated into the work covered by this contract shall be new and of the most suitable grade for the purpose intended, unless otherwise specifically provided in this contract. References in the specifications to equipment, material, articles, or patented processes by trade name, make, or catalog number, shall be regarded as establishing a standard of quality and shall not be construed as limiting competition. The Contractor may, at its option, use any equipment, material, article, or process that, in the judgment of the Contracting Officer, is equal to that named in the specifications, unless otherwise specifically provided in this contract.

(b) The Contractor shall obtain the Contracting Officer's approval of the machinery and mechanical and other equipment to be incorporated into the work. When requesting approval, the Contractor shall furnish to the Contracting Officer the name of the manufacturer, the model number, and other information concerning the performance, capacity, nature, and rating of the machinery and mechanical and other equipment. When required by this contract or by the Contracting Officer, the Contractor shall also obtain the Contracting Officer's approval of the material or articles which the Contractor contemplates incorporating into the work. When requesting approval, the Contractor shall provide full information concerning the material or articles. When directed to do so, the Contractor shall submit samples for approval at the Contractor's expense, with all shipping charges prepaid. Machinery, equipment, material, and articles that do not have the required approval shall be installed or used at the risk of subsequent rejection.

(c) All work under this contract shall be performed in a skillful and workmanlike manner. The Contracting Officer may require, in writing, that the Contractor remove from the work any employee the Contracting Officer deems incompetent, careless, or otherwise objectionable.
(End of clause)

52.236-6 SUPERINTENDENCE BY THE CONTRACTOR (APR 1984)

At all times during performance of this contract and until the work is completed and accepted, the Contractor shall directly superintend the work or assign and have on the worksite a competent superintendent who is satisfactory to the Contracting Officer and has authority to act for the Contractor.

(End of clause)

52.236-7 PERMITS AND RESPONSIBILITIES (NOV 1991)

The Contractor shall, without additional expense to the Government, be responsible for obtaining any necessary licenses and permits, and for complying with any Federal, State, and municipal laws, codes, and regulations applicable to the performance of the work. The Contractor shall also be responsible for all damages to persons or property that occur as a result of the Contractor's fault or negligence. The Contractor shall also be responsible for all materials delivered and work performed until completion and acceptance of the entire work, except for any completed unit of work which may have been accepted under the contract.

(End of clause)

52.236-8 OTHER CONTRACTS (APR 1984)

The Government may undertake or award other contracts for additional work at or near the site of the work under this contract. The Contractor shall fully cooperate with the other contractors and with Government employees and shall carefully adapt scheduling and performing the work under this contract to accommodate the additional work, heeding any direction that may be provided by the Contracting Officer. The Contractor shall not commit or permit any act that will interfere with the performance of work by any other contractor or by Government employees.

(End of clause)

52.236-9 PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS (APR 1984)

(a) The Contractor shall preserve and protect all structures, equipment, and vegetation (such as trees, shrubs, and grass) on or adjacent to the work site, which are not to be removed and which do not unreasonably interfere with the work required under this contract. The Contractor shall only remove trees when specifically authorized to do so, and shall avoid damaging vegetation that will remain in place. If any limbs or branches of trees are broken during contract performance, or by the careless operation of equipment, or by workmen, the Contractor shall trim those limbs or branches with a clean cut and paint the cut with a tree-pruning compound as directed by the Contracting Officer.

(b) The Contractor shall protect from damage all existing improvements and utilities

(1) at or near the work site, and

(2) on adjacent property of a third party, the locations of which are made known to or should be known by the Contractor. The Contractor shall repair any damage to those facilities, including those that are the property of a third party, resulting from failure to comply with the requirements of this contract or failure to exercise reasonable care in performing the work. If the Contractor fails or refuses to repair the damage promptly, the Contracting Officer may have the necessary work performed and charge the cost to the Contractor.

(End of clause)

52.236-10 OPERATIONS AND STORAGE AREAS (APR 1984)

(a) The Contractor shall confine all operations (including storage of materials) on Government premises to areas authorized or approved by the Contracting Officer. The Contractor shall hold and save the Government, its officers and agents, free and harmless from liability of any

nature occasioned by the Contractor's performance.

(b) Temporary buildings (e.g., storage sheds, shops, offices) and utilities may be erected by the Contractor only with the approval of the Contracting Officer and shall be built with labor and materials furnished by the Contractor without expense to the Government. The temporary buildings and utilities shall remain the property of the Contractor and shall be removed by the Contractor at its expense upon completion of the work. With the written consent of the Contracting Officer, the buildings and utilities may be abandoned and need not be removed.

(c) The Contractor shall, under regulations prescribed by the Contracting Officer, use only established roadways, or use temporary roadways constructed by the Contractor when and as authorized by the Contracting Officer. When materials are transported in prosecuting the work, vehicles shall not be loaded beyond the loading capacity recommended by the manufacturer of the vehicle or prescribed by any Federal, State, or local law or regulation. When it is necessary to cross curbs or sidewalks, the Contractor shall protect them from damage. The Contractor shall repair or pay for the repair of any damaged curbs, sidewalks, or roads.

(End of clause)

52.236-11 USE AND POSSESSION PRIOR TO COMPLETION (APR 1984)

(a) The Government shall have the right to take possession of or use any completed or partially completed part of the work. Before taking possession of or using any work, the Contracting Officer shall furnish the Contractor a list of items of work remaining to be performed or corrected on those portions of the work that the Government intends to take possession of or use. However, failure of the Contracting Officer to list any item of work shall not relieve the Contractor of responsibility for complying with the terms of the contract. The Government's possession or use shall not be deemed an acceptance of any work under the contract.

(b) While the Government has such possession or use, the Contractor shall be relieved of the responsibility for the loss of or damage to the work resulting from the Government's possession or use, notwithstanding the terms of the clause in this contract entitled "Permits and Responsibilities." If prior possession or use by the Government delays the progress of the work or causes additional expense to the Contractor, an equitable adjustment shall be made in the contract price or the time of completion, and the contract shall be modified in writing accordingly.

(End of clause)

52.236-12 CLEANING UP (APR 1984)

The Contractor shall at all times keep the work area, including storage areas, free from accumulations of waste materials. Before completing the work, the Contractor shall remove from the work and premises any rubbish, tools, scaffolding, equipment, and materials that are not the property of the Government. Upon completing the work, the Contractor shall leave the work area in a clean, neat, and orderly condition satisfactory to the Contracting Officer.

(End of clause)

52.236-13 ACCIDENT PREVENTION (NOV 1991)

(a) The Contractor shall provide and maintain work environments and procedures which will

(1) safeguard the public and Government personnel, property, materials, supplies, and equipment exposed to Contractor operations and activities;

(2) avoid interruptions of Government operations and delays in project completion dates; and

(3) control costs in the performance of this contract.

(b) For these purposes on contracts for construction or dismantling, demolition, or removal of improvements, the Contractor shall-

(1) Provide appropriate safety barricades, signs, and signal lights;

(2) Comply with the standards issued by the Secretary of Labor at 29 CFR Part 1926 and 29 CFR Part 1910; and

(3) Ensure that any additional measures the Contracting Officer determines to be reasonably necessary for the purposes are taken.

(c) If this contract is for construction or dismantling, demolition or removal of improvements with any Department of Defense agency or component, the Contractor shall comply with all pertinent provisions of the latest version of U.S. Army Corps of Engineers Safety and Health Requirements Manual, EM 385-1-1, in effect on the date of the solicitation.

(d) Whenever the Contracting Officer becomes aware of any noncompliance with these requirements or any condition which poses a serious or imminent danger to the health or safety of the public or Government personnel, the Contracting Officer shall notify the Contractor orally, with written confirmation, and request immediate initiation of corrective action. This notice, when delivered to the Contractor or the Contractor's representative at the work site, shall be deemed sufficient notice of the noncompliance and that corrective action is required. After receiving the notice, the Contractor shall immediately take corrective action. If the Contractor fails or refuses to promptly take corrective action, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. The Contractor shall not be entitled to any equitable adjustment of the contract price or extension of the performance schedule on any stop work order issued under this clause.

(d) The Contractor shall insert this clause, including this paragraph (e), with appropriate changes in the designation of the parties, in subcontracts.

(End of clause)

52.236-15 SCHEDULES FOR CONSTRUCTION CONTRACTS (APR 1984)

(a) The Contractor shall, within five days after the work commences on the contract or another period of time determined by the Contracting Officer, prepare and submit to the Contracting Officer for approval three copies of a practicable schedule showing the order in which the Contractor proposes to perform the work, and the dates on which the Contractor contemplates starting and completing the several salient features of the work (including acquiring materials, plant, and equipment). The schedule shall be in the form of a progress chart of suitable scale to indicate appropriately the percentage of work scheduled for completion by any given date during the period. If the Contractor fails to submit a schedule within the time prescribed, the Contracting Officer may withhold approval of progress payments until the Contractor submits the required schedule.

(b) The Contractor shall enter the actual progress on the chart as directed by the Contracting Officer, and upon doing so shall immediately deliver three copies of the annotated schedule to the Contracting Officer. If, in the opinion of the Contracting Officer, the Contractor falls behind the approved schedule, the Contractor shall take steps necessary to improve its progress, including those that may be required by the Contracting Officer, without additional cost to the Government. In this circumstance, the Contracting Officer may require the Contractor to increase the number of shifts, overtime operations, days of work, and/or the amount of construction plant, and to submit for approval any supplementary schedule or schedules in chart form as the Contracting Officer deems necessary to demonstrate how the approved rate of progress will be regained.

(c) Failure of the Contractor to comply with the requirements of the Contracting Officer under this clause shall be grounds for a determination by the Contracting Officer that the Contractor is not prosecuting the work with sufficient diligence to ensure completion within the time specified in the contract. Upon making this determination, the Contracting Officer may terminate the Contractor's right to proceed with the work, or any separable part of it, in accordance with the default terms of this contract.

(End of clause)

52.236-17 LAYOUT OF WORK (APR 1984)

The Contractor shall lay out its work from Government established base lines and bench marks indicated on the drawings, and shall be responsible for all measurements in connection with the layout. The Contractor shall furnish, at its own expense, all stakes, templates, platforms, equipment, tools, materials, and labor required to lay out any part of the work. The Contractor shall be responsible for executing the work to the lines and grades that may be established or indicated by the Contracting Officer. The Contractor shall also be responsible for maintaining and preserving all stakes and other marks established by the Contracting Officer until authorized to remove them. If such marks are destroyed by the Contractor or through its negligence before their removal is authorized, the Contracting Officer may replace them and deduct the expense of the replacement from any amounts due or to become due to the Contractor.

(End of clause)

52.236-21 SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION (FEB 1997)

(a) The Contractor shall keep on the work site a copy of the drawings and specifications and shall at all times give the Contracting Officer access thereto. Anything mentioned in the specifications and not shown on the drawings, or shown on the drawings and not mentioned in the specifications, shall be of like effect as if shown or mentioned in both. In case of difference between drawings and specifications, the specifications shall govern. In case of discrepancy in the figures, in the drawings, or in the specifications, the matter shall be promptly submitted to the Contracting Officer, who shall promptly make a determination in writing. Any adjustment by the Contractor without such a determination shall be at its own risk and expense. The Contracting Officer shall furnish from time to time such detailed drawings and other information as considered necessary, unless otherwise provided.

(b) Wherever in the specifications or upon the drawings the words "directed", "required", "ordered", "designated", "prescribed", or words of like import are used, it shall be understood that the "direction", "requirement", "order", "designation", or "prescription", of the Contracting Officer is intended and similarly the words "approved", "acceptable", "satisfactory", or words of like import shall mean "approved by," or "acceptable to", or "satisfactory to" the Contracting Officer, unless otherwise expressly stated.

(c) Where "as shown," as indicated", "as detailed", or words of similar import are used, it shall be understood that the reference is made to the drawings accompanying this contract unless stated otherwise. The word "provided" as used herein shall be understood to mean "provide complete in place," that is "furnished and installed".

(d) Shop drawings means drawings, submitted to the Government by the Contractor, subcontractor, or any lower tier subcontractor pursuant to a construction contract, showing in detail (1) the proposed fabrication and assembly of structural elements, and (2) the installation (i.e., fit, and attachment details) of materials or equipment. It includes drawings, diagrams, layouts, schematics, descriptive literature, illustrations, schedules, performance and test data, and similar materials furnished by the contractor to explain in detail specific portions of the work required by the contract. The Government may duplicate, use, and disclose in any manner and for any purpose shop drawings delivered under this contract.

(e) If this contract requires shop drawings, the Contractor shall coordinate all such drawings, and review them for accuracy, completeness, and compliance with contract requirements and shall indicate its approval thereon as evidence of such coordination and review. Shop drawings submitted to the Contracting Officer without evidence of the Contractor's approval may be returned for resubmission. The Contracting Officer will indicate an approval or disapproval of the shop drawings and if not approved as submitted shall indicate the Government's reasons therefor. Any work done before such approval shall be at the Contractor's risk. Approval by the Contracting Officer shall not relieve the Contractor from responsibility for any errors or omissions in such drawings, nor from responsibility for complying with the requirements of this contract, except with respect to variations described and approved in accordance with (f) below.

(f) If shop drawings show variations from the contract requirements, the Contractor shall describe such variations in writing, separate from the drawings, at the time of submission. If the Contracting Officer approves any such variation, the Contracting Officer shall issue an appropriate contract modification, except that, if the variation is minor or does not involve a change in price or in time of performance, a modification need not be issued.

(g) The Contractor shall submit to the Contracting Officer for approval four copies (unless otherwise indicated) of all shop drawings as called for under the various headings of these specifications. Three sets (unless otherwise indicated) of all shop drawings, will be retained by the Contracting Officer and one set will be returned to the Contractor.

(End of clause)

52.236-26 PRECONSTRUCTION CONFERENCE (FEB 1995)

If the Contracting Officer decides to conduct a preconstruction conference, the successful offeror will be notified and will be required to attend. The Contracting Officer's notification will include specific details regarding the date, time, and location of the conference, any need for attendance by subcontractors, and information regarding the items to be discussed.

(End of clause)

52.242-13 BANKRUPTCY (JUL 1995)

In the event the Contractor enters into proceedings relating to bankruptcy, whether voluntary or involuntary, the Contractor agrees to furnish, by certified mail or electronic commerce method authorized by the contract, written notification of the bankruptcy to the Contracting Officer responsible for administering the contract. This notification shall be furnished within five days of the initiation of the proceedings relating to bankruptcy filing. This notification shall include the date on which the bankruptcy petition was filed, the identity of the court in which the bankruptcy petition was filed, and a listing of Government contract numbers and contracting offices for all Government contracts against which final payment has not been made. This obligation remains in effect until final payment under this contract.

(End of clause)

52.242-14 SUSPENSION OF WORK (APR 1984)

(a) The Contracting Officer may order the Contractor, in writing, to suspend, delay, or interrupt all or any part of the work of this contract for the period of time that the Contracting Officer determines appropriate for the convenience of the Government.

(b) If the performance of all or any part of the work is, for an unreasonable period of time, suspended, delayed, or interrupted (1) by an act of the Contracting Officer in the administration of this contract, or (2) by the Contracting Officer's failure to act within the time specified in this contract (or within a reasonable time if not specified), an adjustment shall be made for any increase in the cost of performance of this contract (excluding profit) necessarily caused by the unreasonable suspension, delay, or interruption, and the contract modified in writing accordingly. However, no adjustment shall be made under this clause for any suspension, delay, or interruption to the extent that performance would have been so suspended, delayed, or interrupted by any other cause, including the fault or negligence of the Contractor, or for which an equitable adjustment is provided for or excluded under any other term or condition of this contract. (c) A claim under this clause shall not be allowed (1) for any costs incurred more than 20 days before the Contractor shall have notified the Contracting Officer in writing of the act or failure to act involved (but this requirement shall not apply as to a claim resulting from a suspension order), and (2) unless the claim, in an amount stated, is asserted in writing as soon as practicable after the termination of the suspension, delay, or interruption, but not later than the date of final payment under the contract.

(End of clause)

52.243-4 CHANGES (AUG 1987)

(a) The Contracting Officer may, at any time, without notice to the sureties, if any, by written order designated or indicated to be a change order, make changes in the work within the general scope of the contract, including changes--

(1) In the specifications (including drawings and designs);

(2) In the method or manner of performance of the work;

(3) In the Government-furnished facilities, equipment, materials, services, or site; or

(4) Directing acceleration in the performance of the work.

(b) Any other written or oral order (which, as used in this paragraph (b), includes direction, instruction, interpretation, or determination) from the Contracting Officer that causes a change shall be treated as a change order under this clause; provided, that the Contractor gives the Contracting Officer written notice stating

(1) the date, circumstances, and source of the order and

(2) that the Contractor regards the order as a change order.

(c) Except as provided in this clause, no order, statement, or conduct of the Contracting Officer shall be treated as a change under this clause or entitle the Contractor to an equitable adjustment.

(d) If any change under this clause causes an increase or decrease in the Contractor's cost of, or the time required for, the performance of any part of the work under this contract, whether or not changed by any such order, the Contracting Officer shall make an equitable adjustment and modify the contract in writing. However, except for an adjustment based on defective specifications, no adjustment for any change under paragraph (b) of this clause shall be made for any costs incurred more than 20 days before the Contractor gives written notice as required. In the case of defective specifications for which the Government is responsible, the equitable adjustment shall include any increased cost reasonably incurred by the Contractor in attempting to comply with the defective specifications.

(e) The Contractor must assert its right to an adjustment under this clause within 30 days after

(1) receipt of a written change order under paragraph (a) of this clause or (2) the furnishing of a written notice under paragraph (b) of this clause, by submitting to the Contracting Officer a written statement describing the general nature and amount of the proposal, unless this period is extended by the Government. The statement of proposal for adjustment may be included in the notice under paragraph (b) above.

(f) No proposal by the Contractor for an equitable adjustment shall be allowed if asserted after final payment under this contract.

(End of clause)

52.244-2 SUBCONTRACTS (AUG 1998)

(a) Definitions. As used in this clause--

Approved purchasing system means a Contractor's purchasing system that has been reviewed and approved in accordance with Part 44 of the Federal Acquisition Regulation (FAR).

Consent to subcontract means the Contracting Officer's written consent for the Contractor to enter into a particular subcontract.

Subcontract means any contract, as defined in FAR Subpart 2.1, entered into by a subcontractor to furnish supplies or services for performance of the prime contract or a subcontract. It includes, but is not limited to, purchase orders, and changes and modifications to purchase orders.

(b) This clause does not apply to subcontracts for special test equipment when the contract contains the clause at FAR 52.245-18, Special Test Equipment.

(c) When this clause is included in a fixed-price type contract, consent to subcontract is required only on unpriced contract actions (including unpriced modifications or unpriced delivery orders), and only if required in accordance with paragraph (d) or (e) of this clause.

(d) If the Contractor does not have an approved purchasing system, consent to subcontract is required for any subcontract that--

(1) Is of the cost-reimbursement, time-and-materials, or labor-hour type; or

(2) Is fixed-price and exceeds--

(i) For a contract awarded by the Department of Defense, the Coast Guard, or the National Aeronautics and Space Administration, the greater of the simplified acquisition threshold or 5 percent of the total estimated cost of the contract; or

(ii) For a contract awarded by a civilian agency other than the Coast Guard and the National Aeronautics and Space Administration, either the simplified acquisition threshold or 5 percent of the total estimated cost of the contract.

(e) If the Contractor has an approved purchasing system, the Contractor nevertheless shall obtain the Contracting Officer's written consent before placing the following subcontracts:

(f)(1) The Contractor shall notify the Contracting Officer reasonably in advance of placing any subcontract or modification thereof for which consent is required under paragraph (c), (d), or (e) of this clause, including the following information:

(i) A description of the supplies or services to be subcontracted.

(ii) Identification of the type of subcontract to be used.

(iii) Identification of the proposed subcontractor.

(iv) The proposed subcontract price.

(v) The subcontractor's current, complete, and accurate cost or pricing data and Certificate of Current Cost or Pricing Data, if required by other contract provisions.

(vi) The subcontractor's Disclosure Statement or Certificate relating to Cost Accounting Standards when such data are required by other provisions of this contract.

(vii) A negotiation memorandum reflecting--

(A) The principal elements of the subcontract price negotiations;

(B) The most significant considerations controlling establishment of initial or revised prices;

(C) The reason cost or pricing data were or were not required;

(D) The extent, if any, to which the Contractor did not rely on the subcontractor's cost or pricing data in determining the price objective and in negotiating the final price;

(E) The extent to which it was recognized in the negotiation that the subcontractor's cost or pricing data were not accurate, complete, or current; the action taken by the Contractor and the subcontractor; and the effect of any such defective data on the total price negotiated;

(F) The reasons for any significant difference between the Contractor's price objective and the price negotiated; and

(G) A complete explanation of the incentive fee or profit plan when incentives are used. The explanation shall identify each critical performance element, management decisions used to quantify each incentive element, reasons for the incentives, and a summary of all trade-off possibilities considered.

(2) The Contractor is not required to notify the Contracting Officer in advance of entering into any subcontract for which consent is not required under paragraph (c), (d), or (e) of this clause.

(g) Unless the consent or approval specifically provides otherwise, neither consent by the Contracting Officer to any subcontract nor approval of the Contractor's purchasing system shall constitute a determination--

(1) Of the acceptability of any subcontract terms or conditions;

(2) Of the allowability of any cost under this contract; or

(3) To relieve the Contractor of any responsibility for performing this contract.

(h) No subcontract or modification thereof placed under this contract shall provide for payment on a cost-plus-a-percentage-of-cost basis, and any fee payable under cost-reimbursement type subcontracts shall not exceed the fee limitations in FAR 15.404-4(c)(4)(i).

(i) The Contractor shall give the Contracting Officer immediate written notice of any action or suit filed and prompt notice of any claim made against the Contractor by any subcontractor or vendor that, in the opinion of the Contractor, may result in litigation related in any way to this contract, with respect to which the Contractor may be entitled to reimbursement from the Government.

(j) The Government reserves the right to review the Contractor's purchasing system as set forth in FAR Subpart 44.3.

(k) Paragraphs (d) and (f) of this clause do not apply to the following subcontracts, which were evaluated during negotiations:

(End of clause)

52.244-6 SUBCONTRACTS FOR COMMERCIAL ITEMS (DEC 2004)

(a) Definitions.

"Commercial item", has the meaning contained in Federal Acquistion Regulation 2.101, Definitions.

"Subcontract", includes a transfer of commercial items between divisions, subsidiaries, or affiliates of the Contractor or subcontractor at any tier.

(b) To the maximum extent practicable, the Contractor shall incorporate, and require its subcontractors at all tiers to incorporate, commercial items or nondevelopmental items as components of items to be supplied under this contract.

(c) (1) The Contractor shall insert the following clauses in subcontracts for commercial items:

(i) 52.219-8, Utilization of Small Business Concerns (MAY 2004) (15 U.S.C. 637(d)(2) and (3)), in all subcontracts that offer further subcontracting opportunities. If the subcontract (except subcontracts to small business concerns) exceeds $500,000 ($1,000,000 for construction of any public facility), the subcontractor must include 52.219-8 in lower tier subcontracts that offer subcontracting opportunities.

(ii) 52.222-26, Equal Opportunity (Apr 2002) (E.O. 11246).

(iii) 52.222-35, Equal Opportunity for Special Disabled Veterans, Veterans of the Vietnam Era and Other Eligible Veterans (DEC 2001) (38 U.S.C. 4212(a)).

(iv) 52.222-36, Affirmative Action for Workers with Disabilities (JUN 1998) (29 U.S.C. 793).

(v) 52.222-39, Notification of Employee Rights Concerning Payment of Union Dues or Fees (DEC 2004) (E.O. 13201). Flow down as required in accordance with paragraph (g) of FAR clause 52.222-39).

(vi) 52.247-64, Preference for Privately Owned U.S.-Flag Commercial Vessels (APR 2003) (46 U.S.C. Appx 1241 and 10 U.S.C. 2631) (flow down required in accordance with paragraph (d) of FAR clause 52.247-64).

(2) While not required, the Contractor may flow down to subcontracts for commercial items a minimal number of additional clauses necessary to satisfy its contractual obligations.

(d) The Contractor shall include the terms of this clause, including this paragraph (d), in subcontracts awarded under this contract.

(End of clause)

52.245-2 GOVERNMENT PROPERTY (FIXED-PRICE CONTRACTS) (MAY 2004)

(a) Government-furnished property.

(1) Overseas contracts. If this contract is to be performed outside of the United States and its outlying areas, the words ``Government'' and ``Government-furnished'' (wherever they appear in this clause) shall be construed as ``United States Government'' and ``United States Government-furnished,'' respectively.

(2) The delivery or performance dates for this contract are based upon the expectation that Government-furnished property suitable for use (except for property furnished "as is") will be delivered to the Contractor at the times stated in the Schedule or, if not so stated, in sufficient time to enable the Contractor to meet the contract's delivery or performance dates.

(3) If Government-furnished property is received by the Contractor in a condition not suitable for the intended use, the Contractor shall, upon receipt of it, notify the Contracting Officer, detailing the facts, and, as directed by the Contracting Officer and at Government expense, either repair, modify, return, or otherwise dispose of the property. After completing the directed action and upon written request of the Contractor, the Contracting Officer shall make an equitable adjustment as provided in paragraph (h) of this clause.

(4) If Government-furnished property is not delivered to the Contractor by the required time, the Contracting Officer shall, upon the Contractor's timely written request, make a determination of the delay, if any, caused the Contractor and shall make an equitable adjustment in accordance with paragraph (h) of this clause.

(b) Changes in Government-furnished property. (1) The Contracting Officer may, by written notice, (i) decrease the Government-furnished property provided or to be provided under this contract, or (ii) substitute other Government-furnished property for the property to be provided by the Government, or to be acquired by the Contractor for the Government, under this contract. The Contractor shall promptly take such action as the Contracting Officer may direct regarding the removal, shipment, or disposal of the property covered by such notice.

(2) Upon the Contractor's written request, the Contracting Officer shall make an equitable adjustment to the contract in accordance with paragraph (h) of this clause, if the Government has agreed in the Schedule to make the property available for performing this contract and there is any--

(i) Decrease or substitution in this property pursuant to subparagraph (b)(1) of this clause; or

(ii) Withdrawal of authority to use this property, if provided under any other contract or lease.

(c) Title in Government property. (1) The Government shall retain title to all Government-furnished property.

(2) All Government-furnished property and all property acquired by the Contractor, title to which vests in the Government under this paragraph (collectively referred to as "Government property"), are subject to the provisions of this clause. However, special tooling accountable to this contract is subject to the provisions of the Special Tooling clause and is not subject to the provisions of this clause. Title to Government property shall not be affected by its incorporation into or attachment to any property not owned by the Government, nor shall Government property become a fixture or lose its identity as personal property by being attached to any real property.

(3) Title to each item of facilities and special test equipment acquired by the Contractor for the Government under this contract shall pass to and vest in the Government when its use in performing this contract commences or when the Government has paid for it, whichever is earlier, whether or not title previously vested in the Government.

(4) If this contract contains a provision directing the Contractor to purchase material for which the Government will reimburse the Contractor as a direct item of cost under this contract--

(i) Title to material purchased from a vendor shall pass to and vest in the Government upon the vendor's delivery of such material; and

(ii) Title to all other material shall pass to and vest in the Government upon--

(A) Issuance of the material for use in contract performance;

(B) Commencement of processing of the material or its use in contract performance; or

(C) Reimbursement of the cost of the material by the Government, whichever occurs first.

(d) Use of Government property. The Government property shall be used only for performing this contract, unless otherwise provided in this contract or approved by the Contracting Officer.

(e) Property administration. (1) The Contractor shall be responsible and accountable for all Government property provided under this contract and shall comply with Federal Acquisition Regulation (FAR) Subpart 45.5, as in effect on the date of this contract.

(2) The Contractor shall establish and maintain a program for the use, maintenance, repair, protection, and preservation of Government property in accordance with sound industrial practice and the applicable provisions of Subpart 45.5 of the FAR.

(3) If damage occurs to Government property, the risk of which has been assumed by the Government under this contract, the Government shall replace the items or the Contractor shall make such repairs as the Government directs. However, if the Contractor cannot effect such repairs within the time required, the Contractor shall dispose of the property as directed by the Contracting Officer. When any property for which the Government is responsible is replaced or repaired, the Contracting Officer shall make an equitable adjustment in accordance with paragraph (h) of this clause.

(4) The Contractor represents that the contract price does not include any amount for repairs or replacement for which the Government is responsible. Repair or replacement of property for which the Contractor is responsible shall be accomplished by the Contractor at its own expense.

(f) Access. The Government and all its designees shall have access at all reasonable times to the premises in which any Government property is located for the purpose of inspecting the Government property.

(g) Risk of loss. Unless otherwise provided in this contract, the Contractor assumes the risk of, and shall be responsible for, any loss or destruction of, or damage to, Government property upon its delivery to the Contractor or upon passage of title to the Government under paragraph (c) of this clause. However, the Contractor is not responsible for reasonable wear and tear to Government property or for Government property properly consumed in performing this contract.

(h) Equitable adjustment. When this clause specifies an equitable adjustment, it shall be made to any affected contract provision in accordance with the procedures of the Changes clause. When appropriate, the Contracting Officer may initiate an equitable adjustment in favor of the Government. The right to an equitable adjustment shall be the Contractor's exclusive remedy. The Government shall not be liable to suit for breach of contract for--

(1) Any delay in delivery of Government-furnished property;

(2) Delivery of Government-furnished property in a condition not suitable for its intended use;

(3) A decrease in or substitution of Government-furnished property; or

(4) Failure to repair or replace Government property for which the Government is responsible.

(i) Government property disposal. Except as provided in paragraphs (i)(1)(i), (i)(2), and (i)(8)(i) of this clause, the Contractor shall not dispose of Government property until authorized to do so by the Plant Clearance Officer.

(1) Scrap (to which the Government has obtained title under paragraph (c) of this clause).--(i) Contractor with an approved scrap procedure.--(A) The Contractor may dispose of scrap resulting from production or testing under this contract without Government approval. However, if the scrap requires demilitarization or is sensitive property, the Contractor shall submit the scrap on an inventory disposal schedule.

(B) For scrap from other than production or testing the Contractor may prepare scrap lists in lieu of inventory disposal schedules (provided such lists are consistent with the approved scrap procedures), except that inventory disposal schedules shall be submitted for scrap aircraft or aircraft parts and scrap that--

(1) Requires demilitarization;

(2) Is a classified item;

(3) Is generated from classified items;

(4) Contains hazardous materials or hazardous wastes;

(5) Contains precious metals; or

(6) Is dangerous to the public health, safety, or welfare.

(ii) Contractor without an approved scrap procedure. The Contractor shall submit an inventory disposal schedule for all scrap.

(2) Pre-disposal requirements. When the Contractor determines that a property item acquired or produced by the Contractor, to which the Government has obtained title under paragraph (c) of this clause, is no longer needed for performance of this contract, the Contractor, in the following order of priority:

(i) May purchase the property at the **acquisition** cost.

(ii) Shall make reasonable efforts to return unused property to the appropriate supplier at fair market value (less, if applicable, a reasonable restocking fee that is consistent with the supplier's customary practices).

(iii) Shall list, on Standard Form 1428, Inventory Disposal Schedule, property that was not purchased under paragraph (i)(2)(i) of this clause, could not be returned to a supplier, or could not be used in the performance of other Government contracts.

(3) Inventory disposal schedules.--(i) The Contractor shall use Standard Form 1428, Inventory Disposal Schedule, to identify--

(A) Government-furnished property that is no longer required for performance of this contract, provided the terms of another Government contract do not require the Government to furnish that property for performance of that contract; and

(B) Property acquired or produced by the Contractor, to which the Government has obtained title under paragraph (c) of this clause, that is no longer required for performance of that contract.

(ii) The Contractor may annotate inventory disposal schedules to identify property the Contractor wishes to purchase from the Government.

(iii) Unless the Plant Clearance Officer has agreed otherwise, or the contract requires electronic submission of inventory disposal schedules, the Contractor shall prepare separate inventory disposal schedules for--

(A) Special test equipment with commercial components;

(B) Special test equipment without commercial components;

(C) Printing equipment;

(D) Computers, components thereof, peripheral equipment, and related equipment;

(E) Precious Metals;

(F) Nonnuclear hazardous materials or hazardous wastes; or

(G) Nuclear materials or nuclear wastes.

(iv) Property with the same description, condition code, and reporting location may be grouped in a single line item. The Contractor shall describe special test equipment in sufficient detail to permit an understanding of the special test equipment's intended use.

(4) Submission requirements. The Contractor shall submit inventory disposal schedules to the Plant Clearance Officer no later than--

(i) Thirty days following the Contractor's determination that a Government property item is no longer required for performance of the contract;

(ii) Sixty days, or such longer period as may be approved by the Plant Clearance Officer, following completion of contract deliveries or performance; or

(iii) One hundred twenty days, or such longer period as may be approved by the Plant Clearance Officer, following contract termination in whole or in part.

(5) Corrections. The Plant Clearance Officer may require the Contractor to correct an inventory disposal schedule or may reject a schedule if the property identified on the schedule is not accountable under this contract or is not in the quantity or condition indicated.

(6) Postsubmission adjustments. The Contractor shall provide the Plant Clearance Officer at least 10 working days advance written notice of its intent to remove a property item from an approved inventory disposal schedule. Unless the Plant Clearance Officer objects to the intended schedule adjustment within the notice period, the Contractor may make the adjustment upon expiration of the notice period.

(7) Storage.--

(i) The Contractor shall store the property identified on an inventory disposal schedule pending receipt of disposal instructions. The Government's failure to provide disposal instructions within 120 days following acceptance of an inventory disposal schedule might entitle the Contractor to an equitable adjustment for costs incurred to store such property on or after the 121st day.

(ii) The Contractor shall obtain the Plant Clearance Officer's approval to remove Government property from the premises at which the property is currently located prior to receipt of final disposition instructions. If approval is granted, any costs incurred by the Contractor to transport or store the property shall not increase the price or fee of any Government contract. The storage facility shall be appropriate for assuring the property's physical safety and suitability for use. Approval does not relieve the Contractor of any liability under this contract for such property.

(8) Disposition instructions.

(i) If the Government does not provide disposition instructions to the Contractor within 45 days following acceptance of a scrap list, the Contractor may dispose of the listed scrap in accordance with the Contractor's approved scrap procedures.

(ii) The Contractor shall prepare for shipment, deliver f.o.b. origin, or dispose of Government property as directed by the Plant Clearance Officer. The Contractor shall remove and destroy any markings identifying the property as Government property prior to disposing of the property.

(iii) The Contracting Officer may require the Contractor to demilitarize the property prior to shipment or disposal. Any equitable adjustment incident to the Contracting Officer's direction to demilitarize Government property shall be made in accordance with paragraph (h) of this clause.

(9) Disposal proceeds. The Contractor shall credit the net proceeds from the disposal of Government property to the price or cost of work covered by this contract or to the Government as the Contracting Officer directs.

(10) Subcontractor inventory disposal schedules. The Contractor shall require a subcontractor that is using property accountable under this contract at a subcontractor-managed site to submit inventory disposal schedules to the Contractor in sufficient time for the Contractor to comply with the requirements of paragraph (i)(4) of this clause.

(j) Abandonment of Government property.

(1) The Government will not abandon sensitive Government property without the Contractor's written consent.

(2) The Government, upon notice to the Contractor, may abandon any nonsensitive Government property in place at which time all obligations of the Government regarding such abandoned property shall cease.

(3) The Government has no obligation to restore or rehabilitate the Contractor's premises under any circumstances; however, if Government-furnished property is withdrawn or is unsuitable for the intended use, or if other Government property is substituted, then the equitable adjustment under paragraph (h) of this clause may properly include restoration or rehabilitation costs.

(k) Communications. All communications under this clause shall be in writing.

(l) Overseas contracts. If this contract is to be performed outside of the United States of America, its territories, or possessions, the words "Government" and "Government-furnished" (wherever they appear in this clause) shall be construed as "United States Government" and "United States Government-furnished," respectively.

(End of clause)

52.246-12 INSPECTION OF CONSTRUCTION (AUG 1996)

(a) Definition. "Work" includes, but is not limited to, materials, workmanship, and manufacture and fabrication of components.

(b) The Contractor shall maintain an adequate inspection system and perform such inspections as will ensure that the work performed under the contract conforms to contract requirements. The Contractor shall maintain complete inspection records and make them available to the Government. All work shall be conducted under the general direction of the Contracting Officer and is subject to Government inspection and test at all places and at all reasonable times before acceptance to ensure strict compliance with the terms of the contract.

(c) Government inspections and tests are for the sole benefit of the Government and do not--

(1) Relieve the Contractor of responsibility for providing adequate quality control measures;

(2) Relieve the Contractor of responsibility for damage to or loss of the material before acceptance;

(3) Constitute or imply acceptance; or

(4) Affect the continuing rights of the Government after acceptance of the completed work under paragraph (i) of this section.

(d) The presence or absence of a Government inspector does not relieve the Contractor from any contract requirement, nor is the inspector authorized to change any term or condition of the specification without the Contracting Officer's written authorization.

(e) The Contractor shall promptly furnish, at no increase in contract price, all facilities, labor, and material reasonably needed for performing such safe and convenient inspections and tests as may be required by the Contracting Officer. The Government may charge to the Contractor any additional cost of inspection or test when work is not ready at the time specified by the Contractor for inspection or test, or when prior rejection makes reinspection or retest necessary. The Government shall perform all inspections and tests in a manner that will not unnecessarily delay the work. Special, full size, and performance tests shall be performed as described in the contract.

(f) The Contractor shall, without charge, replace or correct work found by the Government not to conform to contract requirements, unless in the public interest the Government consents to accept the work with an appropriate adjustment in contract price. The Contractor shall promptly segregate and remove rejected material from the premises.

(g) If the Contractor does not promptly replace or correct rejected work, the Government may (1) by contract or otherwise, replace or correct the work and charge the cost to the Contractor or (2) terminate for default the Contractor's right to proceed.

(h) If, before acceptance of the entire work, the Government decides to examine already completed work by removing it or tearing it out, the Contractor, on request, shall promptly furnish all necessary facilities, labor, and material. If the work is found to be defective or nonconforming in any material respect due to the fault of the Contractor or its subcontractors, the Contractor shall defray the expenses of the examination and of satisfactory reconstruction. However, if the work is found to meet contract requirements, the Contracting Officer shall make an equitable adjustment for the additional services involved in the examination and reconstruction, including, if completion of the work was thereby delayed, an extension of time.

(i) Unless otherwise specified in the contract, the Government shall accept, as promptly as practicable after completion and inspection, all work required by the contract or that portion of the work the Contracting Officer determines can be accepted separately. Acceptance shall be final and conclusive except for latent defects, fraud, gross mistakes amounting to fraud, or the Government's rights under any warranty or guarantee.

(End of clause)

52.246-21 WARRANTY OF CONSTRUCTION (MAR 1994)

(a) In addition to any other warranties in this contract, the Contractor warrants, except as provided in paragraph (i) of this clause, that work performed under this contract conforms to the contract requirements and is free of any defect in equipment, material, or design furnished, or workmanship performed by the Contractor or any subcontractor or supplier at any tier.

(b) This warranty shall continue for a period of 1 year from the date of final acceptance of the work. If the Government takes possession of any part of the work before final acceptance, this warranty shall continue for a period of 1 year from the date the Government takes possession.

(c) The Contractor shall remedy at the Contractor's expense any failure to conform, or any defect. In addition, the Contractor shall remedy at the Contractor's expense any damage to Government-owned or controlled real or personal property, when that damage is the result of--

(1) The Contractor's failure to conform to contract requirements; or

(2) Any defect of equipment, material, workmanship, or design furnished.

(d) The Contractor shall restore any work damaged in fulfilling the terms and conditions of this clause. The Contractor's warranty with respect to work repaired or replaced will run for 1 year from the date of repair or replacement.

(e) The Contracting Officer shall notify the Contractor, in writing, within a reasonable time after the discovery of any failure, defect, or damage.

(f) If the Contractor fails to remedy any failure, defect, or damage within a reasonable time after receipt of notice, the Government shall have the right to replace, repair, or otherwise remedy the failure, defect, or damage at the Contractor's expense.
(g) With respect to all warranties, express or implied, from subcontractors, manufacturers, or suppliers for work performed and materials furnished under this contract, the Contractor shall--

(1) Obtain all warranties that would be given in normal commercial practice;

(2) Require all warranties to be executed, in writing, for the benefit of the Government, if directed by the Contracting Officer; and

(3) Enforce all warranties for the benefit of the Government, if directed by the Contracting Officer.

(h) In the event the Contractor's warranty under paragraph (b) of this clause has expired, the Government may bring suit at its expense to enforce a subcontractor's, manufacturer's, or supplier's warranty.

(i) Unless a defect is caused by the negligence of the Contractor or subcontractor or supplier at any tier, the Contractor shall not be liable for the repair of any defects of material or design furnished by the Government nor for the repair of any damage that results from any defect in Government-furnished material or design.

(j) This warranty shall not limit the Government's rights under the Inspection and Acceptance clause of this contract with respect to latent defects, gross mistakes, or fraud.

(End of clause)

52.248-3 VALUE ENGINEERING--CONSTRUCTION (FEB 2000)

(a) General. The Contractor is encouraged to develop, prepare, and submit value engineering change proposals (VECP's) voluntarily. The Contractor shall share in any instant contract savings realized from accepted VECP's, in accordance with paragraph (f) below.

(b) Definitions. "Collateral costs," as used in this clause, means agency costs of operation, maintenance, logistic support, or Government-furnished property.

"Collateral savings," as used in this clause, means those measurable net reductions resulting from a VECP in the agency's overall projected collateral costs, exclusive of acquisition savings, whether or not the acquisition cost changes.

"Contractor's development and implementation costs," as used in this clause, means those costs the Contractor incurs on a VECP specifically in developing, testing, preparing, and submitting the VECP, as well as those costs the Contractor incurs to make the contractual changes required by Government acceptance of a VECP.

"Government costs," as used in this clause, means those agency costs that result directly from developing and implementing the VECP, such as any net increases in the cost of testing, operations, maintenance, and logistic support. The term does not include the normal administrative costs of processing the VECP.

"Instant contract savings," as used in this clause, means the estimated reduction in Contractor cost of performance resulting from acceptance of the VECP, minus allowable Contractor's development and implementation costs, including subcontractors' development and implementation costs (see paragraph (h) below).

"Value engineering change proposal (VECP)" means a proposal that--

(1) Requires a change to this, the instant contract, to implement; and

(2) Results in reducing the contract price or estimated cost without impairing essential functions or characteristics; provided, that it does not involve a change--

(i) In deliverable end item quantities only; or

(ii) To the contract type only.

(c) VECP preparation. As a minimum, the Contractor shall include in each VECP the information described in subparagraphs (1) through (7) below. If the proposed change is affected by contractually required configuration management or similar procedures, the instructions in those procedures relating to format, identification, and priority assignment shall govern VECP preparation. The VECP shall include the following:

(1) A description of the difference between the existing contract requirement and that proposed, the comparative advantages and disadvantages of each, a justification when an item's function or characteristics are being altered, and the effect of the change on the end item's performance.

(2) A list and analysis of the contract requirements that must be changed if the VECP is accepted, including any suggested specification revisions.

(3) A separate, detailed cost estimate for

(i) the affected portions of the existing contract requirement and

(ii) the VECP. The cost reduction associated with the VECP shall take into account the Contractor's allowable development and implementation costs, including any amount attributable to subcontracts under paragraph (h) below.

(4) A description and estimate of costs the Government may incur in implementing the VECP, such as test and evaluation and operating and support costs.

(5) A prediction of any effects the proposed change would have on collateral costs to the agency.

(6) A statement of the time by which a contract modification accepting the VECP must be issued in order to achieve the maximum cost reduction, noting any effect on the contract completion time or delivery schedule.

(7) Identification of any previous submissions of the VECP, including the dates submitted, the agencies and contract numbers involved, and previous Government actions, if known.

(d) Submission. The Contractor shall submit VECP's to the Resident Engineer at the worksite, with a copy to the Contracting Officer.

(e) Government action.

(1) The Contracting Officer will notify the Contractor of the status of the VECP within 45 calendar days after the contracting office receives it. If additional time is required, the Contracting Officer will notify the Contractor within the 45-day period and provide the reason for the delay and the expected date of the decision. The Government will process VECP's expeditiously; however, it shall not be liable for any delay in acting upon a VECP.

If the VECP is not accepted, the Contracting Officer will notify the Contractor in writing, explaining the reasons for rejection. The Contractor may withdraw any VECP, in whole or in part, at any time before it is accepted by the Government. The Contracting Officer may require that the Contractor provide written notification before undertaking significant expenditures for VECP effort.

Any VECP may be accepted, in whole or in part, by the Contracting Officer's award of a modification to this contract citing this clause. The Contracting Officer may accept the VECP, even though an agreement on price reduction has not been reached, by issuing the Contractor a notice to proceed with the change. Until a notice to proceed is issued or a contract modification applies a VECP to this contract, the Contractor shall perform in accordance with the existing contract. The decision to accept or reject all or part of any VECP is a unilateral decision made solely at the discretion of the Contracting Officer.

(f) Sharing.

(1) Rates. The Government's share of savings is determined by subtracting Government costs from instant contract savings and multiplying the result by

(i) 45 percent for fixed-price contracts or

(ii) 75 percent for cost-reimbursement contracts.

(2) Payment. Payment of any share due the Contractor for use of a VECP on this contract shall be authorized by a modification to this contract to--

(i) Accept the VECP;

(ii) Reduce the contract price or estimated cost by the amount of instant contract savings; and

(iii) Provide the Contractor's share of savings by adding the amount calculated to the contract price or fee.

(g) Collateral savings. If a VECP is accepted, the Contracting Officer will increase the instant contract amount by 20 percent of any projected collateral savings determined to be realized in a typical year of use after subtracting any Government costs not previously offset. However, the Contractor's share of collateral savings will not exceed the contract's firm-fixed-price or estimated cost, at the time the VECP is accepted, or $100,000, whichever is greater. The Contracting Officer is the sole determiner of the amount of collateral savings.

(h) Subcontracts. The Contractor shall include an appropriate value engineering clause in any subcontract of $50,000 or more and may include one in subcontracts of lesser value. In computing any adjustment in this contract's price under paragraph (f) above, the Contractor's allowable development and implementation costs shall include any subcontractor's allowable development and implementation costs clearly resulting from a VECP accepted by the Government under this contract, but shall exclude any value engineering incentive payments to a subcontractor. The Contractor may choose any arrangement for subcontractor value engineering incentive payments; provided, that these payments shall not reduce the Government's share of the savings resulting from the VECP.

(i) Data. The Contractor may restrict the Government's right to use any part of a VECP or the supporting data by marking the following legend on the affected parts:

"These data, furnished under the Value Engineering-- Construction clause of contract . . . . . , shall not be disclosed outside the Government or duplicated, used, or disclosed, in whole or in part, for any purpose other than to evaluate a value engineering change proposal submitted under the clause. This restriction does not limit the Government's right to use information contained in these data if it has been obtained or is otherwise available from the Contractor or from another source without limitations." If a VECP is accepted, the Contractor hereby grants the Government unlimited rights in the VECP and supporting data, except that, with respect to data qualifying and submitted as limited rights technical data, the Government shall have the rights specified in the contract modification implementing the VECP and shall appropriately mark the data. (The terms "unlimited rights" and "limited rights" are defined in Part 27 of the Federal Acquisition Regulation.)

(End of clause)

52.249-2 TERMINATION FOR CONVENIENCE OF THE GOVERNMENT (FIXED-PRICE) (MAY 2004)

(a) The Government may terminate performance of work under this contract in whole or, from time to time, in part if the Contracting Officer determines that a termination is in the Government's interest. The Contracting Officer shall terminate by delivering to the Contractor a Notice of Termination specifying the extent of termination and the effective date.

(b) After receipt of a Notice of Termination, and except as directed by the Contracting Officer, the Contractor shall immediately proceed with the following obligations, regardless of any delay in determining or adjusting any amounts due under this clause:

(1) Stop work as specified in the notice.

(2) Place no further subcontracts or orders (referred to as subcontracts in this clause) for materials, services, or facilities, except as necessary to complete the continued portion of the contract.

(3) Terminate all subcontracts to the extent they relate to the work terminated.

(4) Assign to the Government, as directed by the Contracting Officer, all right, title, and interest of the Contractor under the subcontracts terminated, in which case the Government shall have the right to settle or to pay any termination settlement proposal arising out of those terminations.

(5) With approval or ratification to the extent required by the Contracting Officer, settle all outstanding liabilities and termination settlement proposals arising from the termination of subcontracts; the approval or ratification will be final for purposes of this clause.

(6) As directed by the Contracting Officer, transfer title and deliver to the Government (i) the fabricated or unfabricated parts, work in process, completed work, supplies, and other material produced or acquired for the work terminated, and (ii) the completed or partially completed plans, drawings, information, and other property that, if the contract had been completed, would be required to be furnished to the Government.

(7) Complete performance of the work not terminated.

(8) Take any action that may be necessary, or that the Contracting Officer may direct, for the protection and preservation of the property related to this contract that is in the possession of the Contractor and in which the Government has or may acquire an interest.

(9) Use its best efforts to sell, as directed or authorized by the Contracting Officer, any property of the types referred to in subparagraph (b)(6) of this clause; provided, however, that the Contractor (i) is not required to extend credit to any purchaser and (ii) may acquire the property under the conditions prescribed by, and at prices approved by, the Contracting Officer. The proceeds of any transfer or disposition will be applied to reduce any payments to be made by the Government under this contract, credited to the price or cost of the work, or paid in any other manner directed by the Contracting Officer.

(c) The Contractor shall submit complete termination inventory schedules no later than 120 days from the effective date of termination, unless extended in writing by the Contracting Officer upon written request of the Contractor within this 120-day period.

(d) After expiration of the plant clearance period as defined in Subpart 49.001 of the Federal Acquisition Regulation, the Contractor may submit to the Contracting Officer a list, certified as to quantity and quality, of termination inventory not previously disposed of, excluding items authorized for disposition by the Contracting Officer. The Contractor may request the Government to remove those items or enter into an agreement for their storage. Within 15 days, the Government will accept title to those items and remove them or enter into a storage agreement. The Contracting Officer may verify the list upon removal of the items, or if stored, within 45 days from submission of the list, and shall correct the list, as necessary, before final settlement.

(e) After termination, the Contractor shall submit a final termination settlement proposal to the Contracting Officer in the form and with the certification prescribed by the Contracting Officer. The Contractor shall submit the proposal promptly, but no later than 1 year from the effective date of termination, unless extended in writing by the Contracting Officer upon written request of the Contractor within this 1-year period. However, if the Contracting Officer determines that the facts justify it, a termination settlement proposal may be received and acted on after 1 year or any extension. If the Contractor fails to submit the proposal within the time allowed, the Contracting Officer may determine, on the basis of information available, the amount, if any, due the Contractor because of the termination and shall pay the amount determined.

(f) Subject to paragraph (e) of this clause, the Contractor and the Contracting Officer may agree upon the whole or any part of the amount to be paid or remaining to be paid because of the termination. The amount may include a reasonable allowance for profit on work done. However, the agreed amount, whether under this paragraph (g) or paragraph (g) of this clause, exclusive of costs shown in subparagraph (g)(3) of this clause, may not exceed the total contract price as reduced by (1) the amount of payments previously made and (2) the contract price of work not terminated. The contract shall be modified, and the Contractor paid the agreed amount. Paragraph (g) of this clause shall not limit, restrict, or affect the amount that may be agreed upon to be paid under this paragraph.

(g) If the Contractor and the Contracting Officer fail to agree on the whole amount to be paid because of the termination of work, the Contracting Officer shall pay the Contractor the amounts determined by the Contracting Officer as follows, but without duplication of any amounts agreed on under paragraph (f) of this clause:

(1) The contract price for completed supplies or services accepted by the Government (or sold or acquired under subparagraph (b)(9) of this clause) not previously paid for, adjusted for any saving of freight and other charges.

(2) The total of--

(i) The costs incurred in the performance of the work terminated, including initial costs and preparatory expense allocable thereto, but excluding any costs attributable to supplies or services paid or to be paid under subparagraph (f)(1) of this clause;

(ii) The cost of settling and paying termination settlement proposals under terminated subcontracts that are properly chargeable to the terminated portion of the contract if not included in subdivision (g)(2)(i) of this clause; and

(iii) A sum, as profit on subdivision (g)(2)(i) of this clause, determined by the Contracting Officer under 49.202 of the Federal Acquisition Regulation, in effect on the date of this contract, to be fair and reasonable; however, if it appears that the Contractor would have sustained a loss on the entire contract had it been completed, the Contracting Officer shall allow no profit under this subdivision (iii) and shall reduce the settlement to reflect the indicated rate of loss.

(3) The reasonable costs of settlement of the work terminated, including--

(i) Accounting, legal, clerical, and other expenses reasonably necessary for the preparation of termination settlement proposals and supporting data;

(ii) The termination and settlement of subcontracts (excluding the amounts of such settlements); and

(iii) Storage, transportation, and other costs incurred, reasonably necessary for the preservation, protection, or disposition of the termination inventory.

(h) Except for normal spoilage, and except to the extent that the Government expressly assumed the risk of loss, the Contracting Officer shall exclude from the amounts payable to the Contractor under paragraph (g) of this clause, the fair value, as determined by the Contracting Officer, of property that is destroyed, lost, stolen, or damaged so as to become undeliverable to the Government or to a buyer.

(i) The cost principles and procedures of Part 31 of the Federal Acquisition Regulation, in effect on the date of this contract, shall govern all costs claimed, agreed to, or determined under this clause.

(j) The Contractor shall have the right of appeal, under the Disputes clause, from any determination made by the Contracting Officer under paragraph (e), (g), or (l) of this clause, except that if the Contractor failed to submit the termination settlement proposal or request for equitable adjustment within the time provided in paragraph (e) or (l), respectively, and failed to request a time extension, there is no right of appeal.

(k) In arriving at the amount due the Contractor under this clause, there shall be deducted--

(1) All unliquidated advance or other payments to the Contractor under the terminated portion of this contract;

(2) Any claim which the Government has against the Contractor under this contract; and

(3) The agreed price for, or the proceeds of sale of, materials, supplies, or other things acquired by the Contractor or sold under the provisions of this clause and not recovered by or credited to the Government.

(l) If the termination is partial, the Contractor may file a proposal with the Contracting Officer for an equitable adjustment of the price(s) of the continued portion of the contract. The Contracting Officer shall make any equitable adjustment agreed upon. Any proposal by the Contractor for an equitable adjustment under this clause shall be requested within 90 days from the effective date of termination unless extended in writing by the Contracting Officer.

(m)(1) The Government may, under the terms and conditions it prescribes, make partial payments and payments against costs incurred by the Contractor for the terminated portion of the contract, if the Contracting Officer believes the total of these payments will not exceed the amount to which the Contractor will be entitled.

(2) If the total payments exceed the amount finally determined to be due, the Contractor shall repay the excess to the Government upon demand, together with interest computed at the rate established by the Secretary of the Treasury under 50 U.S.C. App. 1215(b)(2). Interest shall be computed for the period from the date the excess payment is received by the Contractor to the date the excess is repaid. Interest shall not be charged on any excess payment due to a reduction in the Contractor's termination settlement proposal because of retention or other disposition of termination inventory until 10 days after the date of the retention or disposition, or a later date determined by the Contracting Officer because of the circumstances.

(n) Unless otherwise provided in this contract or by statute, the Contractor shall maintain all records and documents relating to the terminated portion of this contract for 3 years after final settlement. This includes all books and other evidence bearing on the Contractor's costs and expenses under this contract. The Contractor shall make these records and documents available to the Government, at the Contractor's office,

at all reasonable times, without any direct charge. If approved by the Contracting Officer, photographs, microphotographs, or other authentic reproductions may be maintained instead of original records and documents.

(End of clause)

52.249-10 DEFAULT (FIXED-PRICE CONSTRUCTION) (APR 1984)

(a) If the Contractor refuses or fails to prosecute the work or any separable part, with the diligence that will insure its completion within the time specified in this contract including any extension, or fails to complete the work within this time, the Government may, by written notice to the Contractor, terminate the right to proceed with the work (or the separable part of the work) that has been delayed. In this event, the Government may take over the work and complete it by contract or otherwise, and may take possession of and use any materials, appliances, and plant on the work site necessary for completing the work. The Contractor and its sureties shall be liable for any damage to the Government resulting from the Contractor's refusal or failure to complete the work within the specified time, whether or not the Contractor's right to proceed with the work is terminated. This liability includes any increased costs incurred by the Government in completing the work.

(b) The Contractor's right to proceed shall not be terminated nor the Contractor charged with damages under this clause, if--

(1) The delay in completing the work arises from unforeseeable causes beyond the control and without the fault or negligence of the Contractor. Examples of such causes include

(i) acts of God or of the public enemy,

(ii) acts of the Government in either its sovereign or contractual capacity,

(iii) acts of another Contractor in the performance of a contract with the Government,

(iv) fires,

(v) floods,

(vi) epidemics,

(vii) quarantine restrictions,

(viii) strikes,

(ix) freight embargoes,

(x) unusually severe weather, or delays of subcontractors or suppliers at any tier arising from unforeseeable causes beyond the control and without the fault or negligence of both the Contractor and the subcontractors or suppliers; and

(2) The Contractor, within 10 days from the beginning of any delay (unless extended by the Contracting Officer), notifies the Contracting Officer in writing of the causes of delay. The Contracting Officer shall ascertain the facts and the extent of delay. If, in the judgment of the Contracting Officer, the findings of fact warrant such action, the time for completing the work shall be extended. The findings of the Contracting Officer shall be final and conclusive on the parties, but subject to appeal under the Disputes clause.

(c) If, after termination of the Contractor's right to proceed, it is determined that the Contractor was not in default, or that the delay was excusable, the rights and obligations of the parties will be the same as if the termination had been issued for the convenience of the Government.

The rights and remedies of the Government in this clause are in addition to any other rights and remedies provided by law or under this contract.

(End of clause)

52.253-1 COMPUTER GENERATED FORMS (JAN 1991)

(a) Any data required to be submitted on a Standard or Optional Form prescribed by the Federal Acquisition Regulation (FAR) may be submitted on a computer generated version of the form, provided there is no change to the name, content, or sequence of the data elements on the form, and provided the form carries the Standard or Optional Form number and edition date.

(b) Unless prohibited by agency regulations, any data required to be submitted on an agency unique form prescribed by an agency supplement to the FAR may be submitted on a computer generated version of the form provided there is no change to the name, content, or sequence of the data elements on the form and provided the form carries the agency form number and edition date.

(e) If the Contractor submits a computer generated version of a form that is different than the required form, then the rights and obligations of the parties will be determined based on the content of the required form.

(End of clause)

252.203-7001 PROHIBITION ON PERSONS CONVICTED OF FRAUD OR OTHER DEFENSE-CONTRACT-RELATED FELONIES (DEC 2004)

(a) Definitions. As used in this clause—

(1) “Arising out of a contract with the DoD” means any act in connection with—

(i) Attempting to obtain;

(ii) Obtaining, or

(iii) Performing a contract or first-tier subcontract of any agency, department, or component of the Department of Defense (DoD).

(2) “Conviction of fraud or any other felony” means any conviction for fraud or a felony in violation of state or Federal criminal statutes, whether entered on a verdict or plea, including a plea of *nolo contendere*, for which sentence has been imposed.

(3) “Date of conviction” means the date judgment was entered against the individual.

(b) Any individual who is convicted after September 29, 1988, of fraud or any other felony arising out of a contract with the DoD is prohibited from serving--

(1) In a management or supervisory capacity on this contract;

(2) On the board of directors of the Contractor;

(3) As a consultant, agent, or representative for the Contractor; or

(4) In any other capacity with the authority to influence, advise, or control the decisions of the Contractor with regard to this contract.

(c) Unless waived, the prohibition in paragraph (b) of this clause applies for not less than 5 years from the date of conviction.

(d) 10 U.S.C. 2408 provides that the Contractor shall be subject to a criminal penalty of not more than $500,000 if convicted of knowingly--

(1) Employing a person under a prohibition specified in paragraph (b) of this clause; or

(2) Allowing such a person to serve on the board of directors of the contractor or first-tier subcontractor.

(e) In addition to the criminal penalties contained in 10 U.S.C. 2408, the Government may consider other available remedies, such as—

(1) Suspension or debarment;

(2) Cancellation of the contract at no cost to the Government; or

(3) Termination of the contract for default.

(f) The Contractor may submit written requests for waiver of the prohibition in paragraph (b) of this clause to the Contracting Officer. Requests shall clearly identify—

(1) The person involved;

(2) The nature of the conviction and resultant sentence or punishment imposed;

(3) The reasons for the requested waiver; and

(4) An explanation of why a waiver is in the interest of national security.

(g) The Contractor agrees to include the substance of this clause, appropriately modified to reflect the identity and relationship of the parties, in all first-tier subcontracts exceeding the simplified acquisition threshold in Part 2 of the Federal Acquisition Regulation, except those for commercial items or components.

(h) Pursuant to 10 U.S.C. 2408(c), defense contractors and subcontractors may obtain information as to whether a particular person has been convicted of fraud or any other felony arising out of a contract with the DoD by contacting The Office of Justice Programs, The Denial of Federal Benefits Office, U.S. Department of Justice, telephone (301) 809-4904.

(End of clause)

252.203-7002 DISPLAY OF DOD HOTLINE POSTER (DEC 1991)

(a) The Contractor shall display prominently in common work areas within business segments performing work under Department of Defense (DoD) contracts, DoD Hotline Posters prepared by the DoD Office of the Inspector General.

(b) DoD Hotline Posters may be obtained from the DoD Inspector General, ATTN: Defense Hotline, 400 Army Navy Drive, Washington, DC 22202-2884.

(f) The Contractor need not comply with paragraph (a) of this clause if it has established a mechanism, such as a hotline, by which employees may report suspected instances of improper conduct, and instructions that encourage employees to make such reports.

(End of clause)

252.205-7000 PROVISION OF INFORMATION TO COOPERATIVE AGREEMENT HOLDERS (DEC 1991)

(a) Definition.

"Cooperative agreement holder" means a State or local government; a private, nonprofit organization; a tribal organization (as defined in section 4(c) of the Indian Self-Determination and Education Assistance Act (Pub. L. 93-268; 25 U.S.C. 450 (c))); or an economic enterprise (as defined in section 3(e) of the Indian Financing Act of 1974 (Pub. L. 93-362; 25 U.S.C. 1452(e))) whether such economic enterprise is organized for profit or nonprofit purposes; which has an agreement with the Defense Logistics Agency to furnish procurement technical assistance to business entities.

(b) The Contractor shall provide cooperative agreement holders, upon their request, with a list of those appropriate employees or offices responsible for entering into subcontracts under defense contracts. The list shall include the business address, telephone number, and area of responsibility of each employee or office.

(c) The Contractor need not provide the listing to a particular cooperative agreement holder more frequently than once a year.

(End of clause)

252.219-7003 SMALL, SMALL DISADVANTAGED AND WOMEN-OWNED SMALL BUSINESS SUBCONTRACTING PLAN (DOD CONTRACTS) (APR. 1996)

This clause supplements the Federal Acquisition Regulation 52.219-9, Small, Small Disadvantaged and Women-Owned Small Business Subcontracting Plan, clause of this contract.

(a) *Definitions. Historically black colleges and universities,* as used in this clause, means institutions determined by the Secretary of Education to meet the requirements of 34 CFR 608.2. The term also means any nonprofit research institution that was an integral part of such a college or university before November 14, 1986.

Minority institutions, as used in this clause, means institutions meeting the requirements of section 1046(3) of the Higher Education Act of 1965 (20 U.S.C. 1135d-5(3)). The term also includes Hispanic-serving institutions as defined in section 316(b)(1) of such Act (20 U.S.C. 1059c(b)(1)).

(b) Except for company or division-wide commercial items subcontracting plans, the term *small disadvantaged business,* when used in the FAR 52.219-9 clause, includes historically black colleges and universities and minority institutions, in addition to small disadvantaged business concerns.

(c) Work under the contract or its subcontracts shall be credited toward meeting the small disadvantaged business concern goal required by paragraph (d) of the FAR 52.219-9 clause when:

(1) It is performed on Indian lands or in joint venture with an Indian tribe or a tribally-owned corporation, and

(2) It meets the requirements of 10 U.S.C. 2323a.

(d) Subcontracts awarded to workshops approved by the Committee for Purchase from People Who are Blind or Severely Disabled (41 U.S.C. 46-48), may be counted toward the Contractor's small business subcontracting goal.

(e) A mentor firm, under the Pilot Mentor-Protege Program established under Section 831 of Pub. L. 101-510, as amended, may count toward its small disadvantaged business goal, subcontracts awarded--

(f) The master plan approval referred to in paragraph (f) of the FAR 52.219-9 clause is approval by the Contractor's cognizant contract administration activity.

(g) In those subcontracting plans which specifically identify small, small disadvantaged, and women-owned small businesses, the Contractor shall notify the Administrative Contracting Officer of any substitutions of firms that are not small, small disadvantaged, or women-owned small businesses for the firms listed in the subcontracting plan. Notifications shall be in writing and shall occur within a reasonable period of time after award of the subcontract. Contractor-specified formats shall be acceptable.

(End of clause)

252.223-7001 HAZARD WARNING LABELS (DEC 1991)

(a) "Hazardous material," as used in this clause, is defined in the Hazardous Material Identification and Material Safety Data clause of this contract.

(b) The Contractor shall label the item package (unit container) of any hazardous material to be delivered under this contract in accordance with the Hazard Communication Standard (29 CFR 1910.1200 et seq). The Standard requires that the hazard warning label conform to the requirements of the standard unless the material is otherwise subject to the labeling requirements of one of the following statutes:

(1) Federal Insecticide, Fungicide and Rodenticide Act;

(2) Federal Food, Drug and Cosmetics Act;

(3) Consumer Product Safety Act;

(4) Federal Hazardous Substances Act; or

(5) Federal Alcohol Administration Act.

(c) The Offeror shall list which hazardous material listed in the Hazardous Material Identification and Material Safety Data clause of this contract will be labeled in accordance with one of the Acts in paragraphs (b)(1) through
(5) of this clause instead of the Hazard Communication Standard. Any hazardous material not listed will be interpreted to mean that a label is required in accordance with the Hazard Communication Standard.

MATERIAL (If None, Insert "None.")	ACT
_____	_____
_____	_____

(d) The apparently successful Offeror agrees to submit, before award, a copy of the hazard warning label for all hazardous materials not listed in paragraph (c) of this clause. The Offeror shall submit the label with the Material Safety Data Sheet being furnished under the Hazardous Material Identification and Material Safety Data clause of this contract.

(e) The Contractor shall also comply with MIL-STD-129, Marking for Shipment and Storage (including revisions adopted during the term of this contract).

(End of clause)

252.223-7004 DRUG-FREE WORK FORCE (SEP 1988)

(a) Definitions.

(1) "Employee in a sensitive position," as used in this clause, means an employee who has been granted access to classified information; or employees in other positions that the Contractor determines involve national security; health or safety, or functions other than the foregoing requiring a high degree of trust and confidence.

(2) "Illegal drugs," as used in this clause, means controlled substances included in Schedules I and II, as defined by section 802(6) of title 21 of the United States Code, the possession of which is unlawful under chapter 13 of that Title. The term "illegal drugs" does not mean the use of a controlled substance pursuant to a valid prescription or other uses authorized by law.

(b) The Contractor agrees to institute and maintain a program for achieving the objective of a drug-free work force. While this clause defines criteria for such a program, contractors are encouraged to implement alternative approaches comparable to the criteria in paragraph (c) that are designed to achieve the objectives of this clause.

(c) Contractor programs shall include the following, or appropriate alternatives:

(1) Employee assistance programs emphasizing high level direction, education, counseling, rehabilitation, and coordination with available community resources;

(2) Supervisory training to assist in identifying and addressing illegal drug use by Contractor employees;

(3) Provision for self-referrals as well as supervisory referrals to treatment with maximum respect for individual confidentiality consistent with safety and security issues;

(4) Provision for identifying illegal drug users, including testing on a controlled and carefully monitored basis. Employee drug testing programs shall be established taking account of the following:

(i) The Contractor shall establish a program that provides for testing for the use of illegal drugs by employees in sensitive positions. The extent of and criteria for such testing shall be determined by the Contractor based on considerations that include the nature of the work being performed under the contract, the employee's duties, and efficient use of Contractor resources, and the risks to health, safety, or national security that could result from the failure of an employee adequately to discharge his or her position.

(ii) In addition, the Contractor may establish a program for employee drug testing--

(A) When there is a reasonable suspicion that an employee uses illegal drugs; or

(B) When an employees has been involved in an accident or unsafe practice;

(C) As part of or as a follow-up to counseling or rehabilitation for illegal drug use;

(D) As part of a voluntary employee drug testing program.

(iii) The Contractor may establish a program to test applicants for employment for illegal drug use.

(iv) For the purpose of administering this clause, testing for illegal drugs may be limited to those substances for which testing is prescribed by section 2..1 of subpart B of the "Mandatory Guidelines for Federal Workplace Drug Testing Programs" (53 FR 11980 (April 11, 1988), issued by the Department of Health and Human Services.

(d) Contractors shall adopt appropriate personnel procedures to deal with employees who are found to be using drugs illegally. Contractors shall not allow any employee to remain on duty or perform in a sensitive position who is found to use illegal drugs until such times as the Contractor, in accordance with procedures established by the Contractor, determines that the employee may perform in such a position.

(e) The provisions of this clause pertaining to drug testing program shall not apply to the extent that are inconsistent with state or local law, or with an existing collective bargaining agreement; provided that with respect to the latter, the Contractor agrees those issues that are in conflict will be a subject of negotiation at the next collective bargaining session.

(End of clause)

252.223-7006 PROHIBITION ON STORAGE AND DISPOSAL OF TOXIC AND HAZARDOUS MATERIALS (APR 1993)

(a) "Definitions".

As used in this clause --

(1) "Storage" means a non-transitory, semi-permanent or permanent holding, placement, or leaving of material. It does not include a temporary accumulation of a limited quantity of a material used in or a waste generated or resulting from authorized activities, such as servicing, maintenance, or repair of Department of Defense (DoD) items, equipment, or facilities.

(2) "Toxic or hazardous materials" means:

(i) Materials referred to in section 101(14) of the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) of 1980 (42 U.S.C. 9601(14)) and materials designated under section 102 of CERCLA (42 U.S.C. 9602) (40 CFR part 302);

(ii) Materials that are of an explosive, flammable, or pyrotechnic nature; or

(iii) Materials otherwise identified by the Secretary of Defense as specified in DoD regulations.

(b) In accordance with 10 U.S.C. 2692, the Contractor is prohibited from storing or disposing of non-DoD-owned toxic or hazardous materials on a DoD installation, except to the extent authorized by a statutory exception to 10 U.S.C. 2692 or as authorized by the Secretary of Defense or his designee.

(End of clause)

252.227-7033 RIGHTS IN SHOP DRAWINGS (APR 1966)

(a) Shop drawings for construction means drawings, submitted to the Government by the Construction Contractor, subcontractor or any lower-tier subcontractor pursuant to a construction contract, showing in detail (i) the proposed fabrication and assembly of structural elements and (ii) the installation (i.e., form, fit, and attachment details) of materials or equipment. The Government may duplicate, use, and disclose in any manner and for any purpose shop drawings delivered under this contract.

(b) This clause, including this paragraph (b), shall be included in all subcontracts hereunder at any tier.

252.231-7000 SUPPLEMENTAL COST PRINCIPLES (DEC 1991)

When the allowability of costs under this contract is determined in accordance with part 31 of the Federal Acquisition Regulation (FAR), allowability shall also be determined in accordance with part 231 of the Defense FAR Supplement, in effect on the date of this contract.

(End of clause)

252.232-7003 ELECTRONIC SUBMISSION OF PAYMENT REQUESTS (JAN 2004)

(a) Definitions. As used in this clause--

(1) Contract financing payment and invoice payment have the meanings given in section 32.001 of the Federal Acquisition Regulation.

(2) Electronic form means any automated system that transmits information electronically from the initiating system to all affected systems. Facsimile, e-mail, and scanned documents are not acceptable electronic forms for submission of payment requests. However, scanned documents are acceptable when they are part of a submission of a payment request made using one of the electronic forms provided for in paragraph (b) of this clause.

(3) Payment request means any request for contract financing payment or invoice payment submitted by the Contractor under this contract.

(b) Except as provided in paragraph (c) of this clause, the Contractor shall submit payment requests using one of the following electronic forms:

(1) Wide Area WorkFlow-Receipt and Acceptance (WAWF-RA). Information regarding WAWF-RA is available on the Internet at https://wawf.eb.mil.

(2) Web Invoicing System (WInS). Information regarding WInS is available on the Internet at https://ecweb.dfas.mil.

(3) American National Standards Institute (ANSI) X.12 electronic data interchange (EDI) formats.

(i) Information regarding EDI formats is available on the Internet at http://www.X12.org.

(ii) EDI implementation guides are available on the Internet at http://www.dfas.mil/ecedi.

(4) Another electronic form authorized by the Contracting Officer.

(c) If the Contractor is unable to submit a payment request in electronic form, or DoD is unable to receive a payment request in electronic form, the Contractor shall submit the payment request using a method mutually agreed to by the Contractor, the Contracting Officer, the contract administration office, and the payment office.

(d) In addition to the requirements of this clause, the Contractor shall meet the requirements of the appropriate payment clauses in this contract when submitting payments requests.

(End of clause)

252.236-7000 MODIFICATION PROPOSALS - PRICE BREAKDOWN. (DEC 1991)

(a) The Contractor shall furnish a price breakdown, itemized as required and within the time specified by the Contracting Officer, with any proposal for a contract modification.

(b) The price breakdown --

(1) Must include sufficient detail to permit an analysis of profit, and of all costs for --

(i) Material;

(ii) Labor;

(iii) Equipment;

(iv) Subcontracts; and

(v) Overhead; and

(2) Must cover all work involved in the modification, whether the work was deleted, added, or changed.

(c) The Contractor shall provide similar price breakdowns to support any amounts claimed for subcontracts.

(d) The Contractor's proposal shall include a justification for any time extension proposed.

252.236-7002 OBSTRUCTION OF NAVIGABLE WATERWAYS. (DEC 1991)

(a) The Contractor shall --

(1) Promptly recover and remove any material, plant, machinery, or appliance which the contractor loses, dumps, throws overboard, sinks, or misplaces, and which, in the opinion of the Contracting Officer, may be dangerous to or obstruct navigation;

(2) Give immediate notice, with description and locations of any such obstructions, to the Contracting Officer; and

(3) When required by the Contracting Officer, mark or buoy such obstructions until the same are removed.

(b) The Contracting Officer may --

(1) Remove the obstructions by contract or otherwise should the Contractor refuse, neglect, or delay compliance with paragraph (a) of this clause; and

(2) Deduct the cost of removal from any monies due or to become due to the Contractor; or

(3) Recover the cost of removal under the Contractor's bond.

(c) The Contractor's liability for the removal of a vessel wrecked or sunk without fault or negligence is limited to that provided in sections 15, 19, and 20 of the River and Harbor Act of March 3, 1899 (33 U.S.C. 410 et. seq.).

252.242-7000 POSTAWARD CONFERENCE (DEC 1991)

The Contractor agrees to attend any postaward conference convened by the contracting activity or contract administration office in accordance with Federal Acquisition Regulation subpart 42.5.

(End of clause)

252.243-7001 PRICING OF CONTRACT MODIFICATIONS (DEC 1991)

When costs are a factor in any price adjustment under this contract, the contract cost principles and procedures in FAR part 31 and DFARS part 231, in effect on the date of this contract, apply.

Section 00800 - Special Contract Requirements

CLAUSES INCORPORATED BY FULL TEXT

E4LC26 SMALL BUSINESS STANDARD FOR DREDGING

(a) FAR 52.219-1, SMALL BUSINESS PROGRAM REPRESENTATION, provides the SIC Code and small business size standard for dredging.
(b) Additionally, to be considered small, a firm must perform at least 40% of the yardage with its own dredging equipment or equipment owned by another small dredging firm.

52.211-10 COMMENCEMENT, PROSECUTION, AND COMPLETION OF WORK (APR 1984)

The Contractor shall be required to (a) commence work under this contract within 14 calendar days after the date the Contractor receives the notice to proceed, (b) prosecute the work diligently, and (c) complete the entire work ready for use not later than 90 calendar days of receipt of Notice to Proceed . * The time stated for completion shall include final cleanup of the premises.

*The Contracting Officer shall specify either a number of days after the date the contractor receives the notice to proceed, or a calendar date.

(End of clause)

Should the total quantity of material to be paid for and actually removed under this contract exceed the quantity from the Bidding Schedule, additional time will be allowed at the rate of one day for each 4,000 cubic yards in excess of the estimated quantity.

52.211-12 LIQUIDATED DAMAGES--CONSTRUCTION (SEP 2000)

(a) If the Contractor fails to complete the work within the time specified in the contract, the Contractor shall pay liquidated damages to the Government in the amount of $400.00 for each calendar day of delay until the work is completed or accepted.

(b) If the Government terminates the Contractor's right to proceed, liquidated damages will continue to accrue until the work is completed. These liquidated damages are in addition to excess costs of repurchase under the Termination clause.

(End of clause)

52.236-1 PERFORMANCE OF WORK BY THE CONTRACTOR (APR 1984)

The Contractor shall perform on the site, and with its own organization, work equivalent to at least forty (40) percent of the total amount of work to be performed under the contract. This percentage may be reduced by a supplemental agreement to this contract if, during performing the work, the Contractor requests a reduction and the Contracting Officer determines that the reduction would be to the advantage of the Government.
(End of clause)

52.236-4 PHYSICAL DATA (APR 1984)

Data and information furnished or referred to below is for the Contractor's information. The Government shall not be responsible for any interpretation of or conclusion drawn from the data or information by the Contractor.

(a) The indications of physical conditions on the drawings and in the specifications are the result of site investigations by identified in Division 1 of the specification.

(b) Weather conditions: See Division 1 of the specification.

(c) Transportation facilities: See Division 1 of the specification.

(d) Other Physical Data: See Division 1 of the specification.

(End of clause)

52.249-5000 BASIS FOR SETTLEMENT OF PROPOSALS

Actual costs will be used to determine equipment costs for a settlement proposal submitted on the total cost basis under FAR 49.206-2(b). In evaluating a terminations settlement proposal using the total cost basis, the following principles will be applied to determine allowable equipment costs:

Actual costs for each piece of equipment, or groups of similar serial or series equipment, need not be available in the contractor's accounting records to determine total actual equipment costs.

If equipment costs have been allocated to a contract using predetermined rates , those charges will be adjusted to actual costs.

(3) Recorded job costs adjusted for unallowable expenses will be used to determine equipment operating expenses.

(4) Ownership costs (depreciation) will be determined using the contractor's depreciation schedule (subject to the provisions of FAR 31.205-11).

(5) License, taxes, storage and insurance costs are normally recovered as an indirect expense and unless the contractor charges these costs directly to contracts, they will be recovered through the indirect expense rate.

(End of Clause)

252.201-7000 CONTRACTING OFFICER'S REPRESENTATIVE (DEC 1991)

(a) "Definition. Contracting officer's representative" means an individual designated in accordance with subsection 201.602-2 of the Defense Federal Acquisition Regulation Supplement and authorized in writing by the contracting officer to perform specific technical or administrative functions.

(b) If the Contracting Officer designates a contracting officer's representative (COR), the Contractor will receive a copy of the written designation. It will specify the extent of the COR's authority to act on behalf of the contracting officer. The COR is not authorized to make any commitments or changes that will affect price, quality, quantity, delivery, or any other term or condition of the contract.

(End of clause)

252.236-7004 PAYMENT FOR MOBILIZATION AND DEMOBILIZATION (DEC 1991)

(a) The Government will pay all costs for the mobilization and demobilization of all of the Contractor's plant and equipment at the contract lump sum price for this item.

(1) Sixty (60) percent of the lump sum price upon completion of the contractor's mobilization at the work site.

(2) The remaining forty (40) percent upon completion of demobilization.

(b) The Contracting Officer may require the Contractor to furnish cost data to justify this portion of the bid if the Contracting Officer believes that the percentages in paragraphs (a) (1) and (2) of this clause do not bear a reasonable relation to the cost of the work in this contract.

(1) Failure to justify such price to the satisfaction of the Contracting Officer will result in payment, as determined by the Contracting Officer, of --

(i) Actual mobilization costs at completion of mobilization;

(ii) Actual demobilization costs at completion of demobilization; and

(iii) The remainder of this item in the final payment under this contract.

(2) The Contracting Officer's determination of the actual costs in paragraph (b)(1) of this clause is not subject to appeal.

E4LC12 REQUIRED INSURANCE

The contractor shall procure and maintain during the entire period of performance under this contract, the following minimum insurance:

TYPE	AMOUNT
Workers Compensation	As required by State law
Employer's Liability	$100,000 per person
General Liability	$500,000 per occurrence
Motor Vehicle Liability (for each motor vehicle):	
Bodily injury or death	$200,000 per person
	$500,000 per occurrence
Property damage	$20,000 per occurrence

Prior to commencement of work hereunder, the contractor shall furnish to the Contracting Officer a certificate or written statement of the above required insurance. The policies evidencing required insurance shall contain an endorsement to the effect that cancellation or any material change in the policies adversely affecting the interests of the Government in such insurance shall not be effective for such period as may be prescribed by the laws of the State in which this contract is to be performed and in no event less than 30 days after written notice thereof to
the Contracting Officer.

E4LC13 PERFORMANCE OF WORK BY CONTRACTOR

Offeror's attention is directed to FAR 52.236-1, "Performance of Work by Contractor." Contractor is required to furnish a description of the work which will be performed by his own organization, (e.g., earthwork, paving, etc.), the percentage of the total work this represents, and the estimated cost thereof. Such description of work to be performed by the contractor's own organization shall be provided to the Contracting Officer within 10 days of contract award.

E4LC 14 PERFORMANCE EVALUATION OF CONTRACTOR

As a minimum, the Contractor's performance will be evaluated upon final acceptance of the work. However, interim evaluations may be prepared at any time during contract performance when determined to be in the best interest of the Government. The format for the evaluation will be DD Form 2626, and the Contractor will be rated either "Outstanding," "Satisfactory," or "Unsatisfactory" in the areas of Contractor Quality Control, Timely Performance, Effectiveness of Management, Compliance with Labor Standards, and Compliance with Safety Standards. The Contractor will be advised on any unsatisfactory rating, either in an individual element or in the overall rating, prior to completing the evaluation; all contractor comments will be made a part of the official record. In compliance with DOD FAR Supplement 236.201, Performance Evaluation Reports will be available to all DOD Contracting Offices for their future use in determining contractor responsibility.

E4LC15 LOCATION OF SITE ON A GOVERNMENT RESERVATION

The site of the work is on a government reservation and all rules and regulations issued by the Commanding Officer covering general safety, security, and sanitary requirements, etc., shall be observed by the contractor.

E4LC16 ACCIDENT PREVENTION PLAN

In accordance with the clause entitled "Accident Prevention," the contractor will not be allowed to commence work on the job site until an acceptable accident prevention plan has been submitted. The contractor will receive official notification of the acceptance of his accident prevention plan.

E4LC28 IDENTIFICATION OF CORRESPONDENCE

All correspondence and data submitted by the contractor under this contract shall reference the contract number.

E4LC32 DEPARTMENT OF LABOR WAGE DECISION

Any contract awarded as a result of this solicitation will be subject to the U.S. Department of Labor Wage Decision(s) identified as VA030026 dated 10/22/2004.

General Decision Number: VA030026 10/22/2004 VA26

Superseded General Decision Number: VA020026

State: Virginia

Construction Types: Heavy Dredging

Counties: Virginia Statewide.

DREDGING CONSTRUCTION PROJECTS (Excluding HOPPER DREDGING)

Modification Number	Publication Date
0	06/13/2003
1	10/22/2004

* ENGI0025-003 02/01/2004

	Rates	Fringes
Clamshell Dredges		
Deckhand	$ 12.43	4.72+a
Engineer	$ 18.21	5.12+a
Handyman	$ 12.43	4.72+a
Mate	$ 16.41	4.92+a
Oiler	$ 13.25	4.72+a
Operator	$ 20.30	5.12+a
Scowman	$ 12.60	4.72+a
Welder	$ 17.02	4.92+a
Hydraulic Dredges 20" & Over		
Assistant Fill Placer	$ 16.21	5.12+a
Carpenter	$ 17.77	5.12+a
Deckhand	$ 12.43	4.72+a
Derrick Operator	$ 17.87	5.12+a
Electrician	$ 18.20	5.12+a
Engineer	$ 19.22	5.12+a
Fill Placer	$ 18.00	5.12+a
Handyman	$ 12.43	4.72+a
Leverman	$ 20.55	5.12+a
Mate	$ 16.75	4.92+a
Oiler	$ 13.25	4.72+a
Shoreman	$ 12.20	4.72+a
Spill Barge Operator	$ 17.53	4.92+a
Welder	$ 17.29	4.92+a
Steward Department (On Clamshell Dredges)		
2nd Cook	$ 12.43	4.72+a
Janitor	$ 12.43	4.72+a
Messman	$ 12.20	4.72+a
Night Cook	$ 12.43	4.72+a
Steward	$ 13.64	4.92+a
Tugs 600 HP to 1350 HP		
Tug Captain	$ 16.03	5.12+a
Tug Deckhand	$ 12.43	4.72+a
Tug Master	$ 17.37	5.12+a
Tugs Greater Than 1350 HP		
Tug Captain	$ 17.52	5.12+a

Tug Deckhand	$ 12.43	4.72+a
Tug Engineer	$ 17.52	5.12+a
Tug Master	$ 18.45	5.12+a
Tugs Less Than 600 HP		
Tug Captain	$ 15.87	5.12+a
Tug Deckhand	$ 12.43	4.72+a
Tug Master	$ 16.38	5.12+a

FOOTNOTE:

a. PAID HOLIDAYS: New Year's Day, Memorial Day, Independence Day, Good Friday, Labor Day, Thanksgiving Day, Christmas Day. Plus Vacation contribution of 7% of straight time pay for all hours worked.

SUVA1994-008 11/01/1994

	Rates	Fringes
Dipper Dredges		
Deckhand	$ 9.50	2.96+a
Engineer	$ 14.04	2.96+a
Handyman	$ 9.50	2.96+a
Launchman	$ 10.12	2.96+a
Mate	$ 12.39	2.96+a
Oiler	$ 10.12	2.96+a
Operator	$ 14.59	2.96+a
Rodman	$ 9.50	2.96+a
Scowman	$ 9.63	2.96+a
Welder	$ 12.78	2.96+a
Drill Boats		
Blaster	$ 13.69	2.96+a
Driller	$ 13.69	2.96+a
Engineer	$ 14.18	2.96+a
Hydraulic Dredges Under 20"		
Carpenter	$ 13.14	2.96+a
Deckhand	$ 9.50	2.96+a
Derrick Operator	$ 13.20	2.96+a
Electrician	$ 13.45	2.96+a
Engineer	$ 14.18	2.96+a
Handyman	$ 9.50	2.96+a
Janitor/Porter	$ 9.50	2.96+a
Leverman	$ 14.53	2.96+a
Mate	$ 12.39	2.96+a
Messman	$ 9.32	2.96+a
Night Cook	$ 9.50	2.96+a
Oiler	$ 10.12	2.96+a
Rodman	$ 9.50	2.96+a
Second Cook	$ 9.50	2.96+a
Shoreman	$ 9.32	2.96+a
Spider Barge Operator	$ 12.97	2.96+a
Spill Barge Operator	$ 12.97	2.96+a
Steward	$ 10.42	2.96+a
Tug Deckhand	$ 9.50	2.96+a
Tug Master	$ 12.29	2.96+a
Tug Mate	$ 11.76	2.96+a
Welder	$ 12.78	2.96+a

Steward Department (On Dipper Dredges)		
Cook	$ 9.27	2.96+a
Mess Cook	$ 8.74	2.96+a
Messman and Janitor	$ 8.61	2.96+a
Tug Boats (Tending Dipper Dredges)		
Assistant Engineer	$ 11.75	2.96+a
Cook	$ 9.63	2.96+a
Deckhand	$ 9.37	2.96+a
Engineer	$ 12.96	2.96+a
Tug Master	$ 13.16	2.96+a
Tug Mate	$ 11.87	2.96+a

FOOTNOTES APPLICABLE TO ALL ABOVE CRAFTS:

a. PAID HOLIDAYS AND VACATION:
New Year's Day, Memorial Day, Independence Day, Good Friday, Labor Day, Thanksgiving Day, and Christmas Day; plus vacation contribution of 7% of straight time pay for all hours worked.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

In the listing above, the "SU" designation means that rates listed under the identifier do not reflect collectively bargained wage and fringe benefit rates. Other designations indicate unions whose rates have been determined to be prevailing.

WAGE DETERMINATION APPEALS PROCESS

1.) Has there been an initial decision in the matter? This can be:

* an existing published wage determination
* a survey underlying a wage determination
* a Wage and Hour Division letter setting forth a position on a wage determination matter
* a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour Regional Office for the area in which the survey was conducted because those Regional Offices have responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations

Wage and Hour Division

U.S. Department of Labor

200 Constitution Avenue, N.W.

Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator

U.S. Department of Labor

200 Constitution Avenue, N.W.

Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board

U.S. Department of Labor

200 Constitution Avenue, N.W.

Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

==========

END OF GENERAL DECISION

MAINTENANCE DREDGING AND REALIGNMENT
LYNNHAVEN INLET,
BAY AND CONNECTING WATERS
VIRGINIA BEACH, VIRGINIA

PREPARED AND
ISSUED BY
DEPARTMENT OF THE ARMY
NORFOLK DISTRICT, CORPS OF ENGINEERS
OPERATIONS BRANCH
WATERFIELD BUILDING
803 FRONT STREET
NORFOLK, VIRGINIA 23510-1096

PROJECT TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

01006 POST AWARD MEETINGS
01140 ENVIRONMENTAL PERMIT WORK REQUIREMENTS
ENVIRONMENTAL PERMITS
01150 SPECIAL WORK REQUIREMENTS
01270 MEASUREMENT AND PAYMENT
01320 PROJECT SCHEDULE
01330 SUBMITTAL PROCEDURES
STANDARD FORM 4025 (TRANSMITTAL FORM SAMPLE)
STANDARD FORM 4288 (SUBMITTAL REGISTER SAMPLE)
01355 ENVIRONMENTAL PROTECTION
01420 SOURCES FOR REFERENCE PUBLICATIONS
01451 CONTRACTOR QUALITY CONTROL
SAMPLE FORMS FOR -
PREPARATORY AND INITIAL PHASE INSPECTIONS
CONTRACTOR QUALITY CONTROL REPORTS
REPORT OF OPERATIONS - DREDGES
01500 TEMPORARY CONSTRUCTION FACILITIES
01525 SAFETY AND OCCUPATIONAL HEALTH REQUIREMENTS
01850 DRAWING INDEX

DIVISION 02 - SITE CONSTRUCTION

02325 DREDGING

DIVISION 03 - Not Used

DIVISION 04 - Not Used

DIVISION 05 - Not Used

DIVISION 06 - Not Used

DIVISION 07 - Not Used

DIVISION 08 - Not Used

DIVISION 09 - Not Used

DIVISION 10 - Not Used

DIVISION 11 - Not Used

DIVISION 12 - Not Used

DIVISION 13 - Not Used

DIVISION 14 - Not Used

DIVISION 15 - Not Used

DIVISION 16 - Not Used

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01006

POST AWARD MEETINGS

01/05

PART 1 GENERAL

1.1 SUBMITTALS (NOT APPLICABLE)
1.2 PRECONSTRUCTION CONFERENCE
1.2.1 Scheduling
1.2.2 Purpose
1.2.3 Discussion Items
1.3 OTHER MEETINGS DURING THE CONTRACT
1.4 MINUTES OF MEETINGS

PART 2 PRODUCTS (THIS PART NOT USED)

PART 3 EXECUTION (THIS PART NOT USED)

-- End of Section Table of Contents --

SECTION 01006

POST AWARD MEETINGS
01/05

PART 1 GENERAL

1.1 SUBMITTALS (NOT APPLICABLE)

1.2 PRECONSTRUCTION CONFERENCE

1.2.1 Scheduling

After award of the construction contract and prior to the start of any construction work, the Contracting Officer (CO) will schedule and conduct a preconstruction conference. The Contractor's Project Manager, Superintendent and Quality Control System Manager shall attend this meeting. The Contractor is encouraged to have an officer of his company (Project Manager could be this person) and representation from each of his sub-contractors and major construction work divisions at the conference. This conference will be held at a location and time as specified by the CO.

1.2.2 Purpose

The purpose of this preconstruction conference is to enable the CO to outline the procedures that will be followed by the Government in its administration of this construction contract and to discuss the performance that will be expected from the Contractor. This conference will allow the Contractor an opportunity to ask questions about the Government's supervision and inspection of contract work, about security requirements, regulations, and other similar matters. The CO may invite other Government personnel involved in the work to attend this conference.

1.2.3 Discussion Items

The following is a sample list of items for discussion during the preconstruction conference; however, the Contracting Officer may modify this list or include additional items for discussion as conditions and the work require.

a. Authority of the Contracting Officer/Contracting Officer's Representative.

b. Contractor's Progress Schedule.

c. Correspondence Procedures.

d. Contractor Labor Standards Provisions.

e. Contract Modifications and Administrative Procedures.

f. Contractor's Administrative, Laydown and Storage Areas.

g. Procedures for Processing Submittals.

h. Payment Estimate Data and Procedures.

i. Contractor Utilities.

j. Security Requirements and Other Regulations, if applicable.

k. Government Furnished Equipment, if applicable.

l. Disposition of Salvage Property, if applicable.

m. Contractor Insurance Requirements.

n. Environmental Protection Plan.

o. Contractor Performance Evaluation.

p. Emergency and Safety Procedures.

q. Plant and Suitability to Perform the Work.

r. Turnover of Placement Areas After Dredging.

s. Contractor Required Notification Procedures.

t. Contractor's Submittal Register.

u. Contractor's Survey and Information Reporting Procedures

v. Contractor's Quality Control Plan and Activity Hazard Analysis Related to Testing at Placement Area and associated Procedures

1.3 OTHER MEETINGS DURING THE CONTRACT

Other meetings may be held after the Preconstruction Conference, for the purpose to discuss concerns and deficiencies that may include the following:

a. Contractor's Site Safety and Health Plan

b. Quality Control Plan

c. Environmental Protection Plan

d. Effluent Testing Procedures and Reporting

e. Progress Schedule updates.

1.4 MINUTES OF MEETINGS

The Government will prepare minutes of all meetings.

PART 2 PRODUCTS (THIS PART NOT USED)

PART 3 EXECUTION (THIS PART NOT USED)

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01140

ENVIRONMENTAL PERMIT WORK REQUIREMENTS

12/04

PART 1 GENERAL

1.1 GENERAL INFORMATION
1.2 SUBMITTALS
1.3 SPECIAL SCHEDULING REQUIREMENTS

PART 2 PRODUCTS

PART 3 EXECUTION

3.1 SPECIAL ENVIRONMENTAL TESTING REQUIREMENTS FOR UPLAND PLACEMENT AREA
3.1.1 Water Quality Monitoring Controls
3.1.1.1 Effluent Total Suspended Solids (TSS) Tests
3.1.2 Environmental Testing Quality Control
3.1.2.1 Inspections and Testing Requirements
3.1.2.2 Control of Upland Placement Area Effluent

-- End of Section Table of Contents --

SECTION 01140

ENVIRONMENTAL PERMIT WORK REQUIREMENTS
12/04

PART 1 GENERAL

1.1 GENERAL INFORMATION

This SECTION supplements the Contractor's responsibility under the CONTRACT CLAUSE "PERMITS AND RESPONSIBILITIES" to the extent that the Government has already obtained an environmental permit for the required maintenance dredging and dredged material placement. These special environmental requirements are an outgrowth of environmental commitments made by the Government during the project development. All dredging, transport and placement of dredged material under this contract shall be in strict compliance with the conditions set forth in the Virginia Department of Environmental Quality Water Protection Permit and the Virginia Marine Resources Commission Permits that are included as a part of this contract at the end of this SECTION. The contract plans and specifications have been prepared to comply with these permits that were established during the planning and development of this project. The Contractor is advised that any deviations from the construction methods and procedures indicated by the plans and specifications that are not prior approved in writing by the Contracting Officer, or any non-compliance with or violation of the conditions stated in the permits noted herein, shall be cause for the Contracting Officer issuing a stop work order. Any stop work orders issued for any of these causes will not be subject to time extensions or cost recovery by the Contractor. Any non-compliance with or violation of the conditions stated in the permits noted herein may result in revocation of the permit for the project and may result in criminal and civil penalties against the Contractor.

1.2 SUBMITTALS

The Contractor shall make submittals for the following listed reports and certificates as required by the specifications. The Contracting Officer may request submittals in addition to those specified when deemed necessary to adequately describe the work. Units of weights and measures used on all submittals shall be the same as those used in the contract drawings. Each submittal shall be complete and in sufficient detail to allow ready determination of compliance with contract requirements. Prior to submittal, all items shall be checked and approved by the Contractor's Quality Control (CQC) representative and each item shall be stamped, signed, and dated by the CQC representative indicating action taken in accordance with SECTION 01451. Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-06 Test Reports

Effluent Measurements

Records of effluent measurements, and corrective action taken when applicable, shall be submitted daily to the Contracting Officer.

1.3 SPECIAL SCHEDULING REQUIREMENTS

There are no time of year restrictions established in the Permits for conducting the work; however, the Government has established an Order of Work that is specified in SECTION 01150 SPECIAL WORK REQUIREMENTS.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 SPECIAL ENVIRONMENTAL TESTING REQUIREMENTS FOR UPLAND PLACEMENT AREA

3.1.1 Water Quality Monitoring Controls

In addition to the requirements specified in paragraph "Control of Upland Placement Area Effluent", the Contractor shall take all precautions that in the opinion of the Contracting Officer may be necessary to minimize the escape of dredged material into receiving waters. It is the Contractor's responsibility to operate the spill boxes in a manner which helps achieve the goal of releasing only clarified supernatant (water) from the spill boxes into the receiving waters. Effluent shall be visually checked at a minimum of six hour intervals at each operating spillbox. If at any time it is visually apparent that effluent other than clarified water is being released from the Placement Area, immediate action shall be taken by the Contractor to stop the release. Effluent total suspended solids (TSS) samples shall be taken at least twice daily at the weir crest of each operating spillbox, once approximately every twelve hours. When any solids are present in samples taken from the spillbox effluent as indentified below, the sample is considered to have failed and immediate action shall be taken by the Contractor to stop the release.

3.1.1.1 Effluent Total Suspended Solids (TSS) Tests

Effluent Total Suspended Solids tests shall be performed on all effluent samples as outlined in paragraph titled "Control of Upland Placement Area Effluent". The Contractor shall record all effluent sampling events and the sampling results shall be included on his Daily CQC Report. Dredged material placement operations shall be managed to meet the following effluent quality criteria:

The Contractor must maintain a daily average TSS concentration of less than 500 mg/l. The "less than" 500 mg/l TSS concentration is a threshold limit and is not a TSS target or goal. If at any time, the daily average of effluent sampling from a spillbox equals or exceeds 500 mg/l, the Contractor shall take immediate action to stop the flow from that spill box. The release of effluent from the spill box can

resume after there is a sufficient depth of clarified ponded water in front of the spill box to meet the TSS limit of less than 500 mg/l. The Contractor will immediately retest the effluent; a measurement to determine if the TSS concentration is less than 500 mg/l will be used as an indicator to continue effluent release from the spillbox. If the effluent TSS concentration cannot be maintained below the 500 mg/l, the Contractor must cease inflow into the Placement Area. For ponding and freeboard requirements, refer to PARAGRAPHS "Government Furnished Upland Placement Area" and "Placement Area Use and Maintenance During Placement Operations" of SECTION 02325 DREDGING.

3.1.2 Environmental Testing Quality Control

The Contractor shall establish and maintain a quality control system for all environmental testing for dredging operations to assure compliance with contract requirements and record his inspections and tests under this system.

3.1.2.1 Inspections and Testing Requirements

Inspections and testing shall be the responsibility of the Contractor, subject to the approval of the Contracting Officer.

3.1.2.2 Control of Upland Placement Area Effluent

The TSS concentration of the effluent samples taken in accordance with paragraph titled "Water Quality Monitoring Controls" shall be determined by a photometric method using a Hach 850/DR Colorimeter model #48450-00, program 94 "Suspended Solids", or approved equal. Effluent water samples shall be taken with a 1000 ml wide-mouth polyethylene bottle (Nalgene 2104-0032 or equal). The specified equipment provides for real time measurement of TSS concentration; therefore, the Contractor shall perform the TSS measurement in the field immediately after each effluent sampling is accomplished."

-- End of Section --

COMMONWEALTH of VIRGINIA

DEPARTMENT OF ENVIRONMENTAL QUALITY

W. Tayloe Murphy, Jr.
Secretary of Natural Resources

5636 Southern Boulevard
Virginia Beach, VA 23462
www.deq.state.va.us

Robert G. Burnley
Director

Francis L. Daniel
Tidewater Regional Director
(757) 518-2000

September 27, 2004

Mr. Matthew Byrne
Chief, Operations Branch
US Army Corps of Engineers
Norfolk District
803 Front Street
Norfolk, VA 23510-1096

RE: Virginia Water Protection Individual Permit Number 94-1284
Revocation and Re-issuance
Lynnhaven Inlet Federal Navigational Project
City of Virginia Beach, Virginia

Dear Mr. Byrne:

Pursuant to the Virginia Water Protection (VWP) Permit Program Regulation 9 VAC 25-210-10 et seq. and § 401 of the Clean Water Act Amendments of 1977, Public Law 95-217, the Department of Environmental Quality (DEQ) has enclosed the original VWP individual permit for the continued maintenance dredging by hydraulic method of the Lynnhaven Inlet Federal Navigation Project, which is comprised of the following five channels: entrance channel, mooring and turning basin, side channel, Long Creek channel, and the Narrows channel.

The provisions and conditions contained therein according to § 401(a)(1) of the Clean Water Act requires that:

> "any applicant for a Federal license or permit to conduct any activity including, but not limited to, the construction or operation of facilities, which may result in any discharge in the navigable waters, shall provide the licensing or permitting agency a certification from the State in which the discharge originates or will originate, or, if appropriate, from the interstate water pollution control agency having jurisdiction over the navigable waters at the point where the discharge originates or will originate, that any such discharge will comply with the applicable provisions of sections 301, 302, 303, 306, and 307 of this Act."

This permit is valid for 15 years from the date of issuance. Re-issuance of the permit may be necessary if any portion of the authorized activities or any permit requirement (including compensatory mitigation provisions) have not been completed. The permit term, including any extensions, cannot exceed the maximum of 15 years. The extension may be requested through written notification to the Department of Environmental Quality Tidewater Regional Office, provided that there are no changes in the authorized activities.

As provided by Rule 2A:2 of the Supreme Court of Virginia, you have 30 calendar days from the date of service (the date you actually received this decision or the date it was mailed to you, whichever occurred first) within which to appeal this decision by filing a notice of appeal in accordance with the Rules of the Supreme Court of Virginia with the Director, Department of Environmental Quality. In the event that this decision is served on you by mail, three days are added to that period. Refer to Part 2A of the Rules of the Supreme Court of Virginia for additional requirements governing appeals from administrative agencies.

Alternatively, any owner under §§62.1-44.16, 62.1-44.17 and 62.1-44.19 of the State Water Control Law aggrieved by any action of the board taken without a formal hearing, or by inaction of the board, may demand in writing a formal hearing of such owner's grievance, provided a petition requesting such hearing is filed with the board. Said petition must meet the requirements set forth in §1.23(b) of the board's Procedural Rule Number 1 (9 VAC 25-230-10 et seq. of the Virginia Administrative Code). In cases involving actions of the board, such petition must be filed within 30 calendar days after notice of such action is mailed to such owner.

If you have any questions, please contact Mark Kalnins at (757) 518-2160, or mgkalnins@deq.virginia.gov.

Sincerely,

Bert W. Parolari, Jr.
Virginia Water Protection Permit Manager

Enclosures: Permit Cover Page, Part I – Special Conditions, Part II – General Conditions

cc: Virginia Marine Resources Commission (w/enclosures)

COMMONWEALTH of VIRGINIA

DEPARTMENT OF ENVIRONMENTAL QUALITY

W. Tayloe Murphy, Jr.
Secretary of Natural Resources

5636 Southern Boulevard
Virginia Beach, VA 23462
www.deq.state.va.us

Robert G. Burnley
Director

Francis L. Daniel
Tidewater Regional Director
(757) 518-2000

VWP Individual Permit Number 94-1284
Effective Date: September 27, 2004
Expiration Date: September 26, 2019

VIRGINIA WATER PROTECTION PERMIT ISSUED PURSUANT TO THE STATE WATER CONTROL LAW AND SECTION 401 OF THE CLEAN WATER ACT

Based upon an examination of the information submitted by the owner and in compliance with § 401 of the Clean Water Act as amended (33 USC 1251 et seq.) and the State Water Control Law and regulations adopted pursuant thereto, the State Water Control Board (board) has determined that there is a reasonable assurance that the activity authorized by this permit, if conducted in accordance with the conditions set forth herein, will protect instream beneficial uses and will not violate applicable water quality standards. The board finds that the effect of the impact, together with other existing or proposed impacts to wetlands, will not cause or contribute to a significant impairment to state waters or fish and wildlife resources.

Permittee:	United States Army Corps of Engineers, Norfolk District Attn: Matthew Byrne, Chief, Operations Branch
Address:	803 Front Street, Norfolk, Virginia 23510-1096
Activity Location:	Lynnhaven Inlet Federal Navigational Project City of Virginia Beach, Virginia

Activity Description: This permit authorizes the maintenance dredging by hydraulic method of the Lynnhaven Inlet Federal Navigation Project, which is comprised of the following five channels: entrance channel, mooring and turning basin, side channel, Long Creek channel, and the Narrows channel. This permit also authorizes new dredging to realign the entrance channel in order to improve navigation.

The permitted activity shall be in accordance with this Permit Cover Page, Part I - Special Conditions, and Part II - General Conditions.

_____(for)
Director, Department of Environmental Quality

9/27/04
_____
Date

Part I – Special Conditions

A. Authorized Activities

1. This permit authorizes the maintenance dredging by hydraulic method of the Lynnhaven Inlet Federal Navigation Project, which is comprised of the following five channels: entrance channel, mooring and turning basin, side channel, Long Creek channel, and the Narrows channel. This permit also authorizes new dredging to realign the entrance channel in order to improve navigation. This project has been described in the Joint Permit Application, received on January 7, 2004. The project was deemed complete on June 8, 2004.

2. The project activities, including any conditions and limitations, shall be adhered to as described in the Joint Permit Application and any supplemental materials approved by DEQ.

3. The permittee shall notify the DEQ – Tidewater Regional Office of any additional impacts to surface waters, including wetlands or any change to the type of wetland impacts, associated with this project. Any additional impacts to surface waters, including wetlands, or any change to the type of wetland impacts, shall be subject to individual permit review or modification of this permit, and compensation may be required.

4. This permit is valid for 15 years from the date of issuance. Reissuance of the permit may be necessary if any portion of the authorized activities or any permit requirement (including compensation provisions) has not been completed. The original permit term and extension cannot exceed the maximum of 15 years.

B. Standard Project Conditions

1. The activities authorized by this permit shall be executed in a manner to minimize any adverse impact on stream beneficial uses, as defined in § 62.1-10(b) of the Code.

2. No activity shall substantially disrupt the movement of aquatic life indigenous to the water body, including those species that normally migrate through the area, unless the primary purpose of the activity is to impound water. The activity shall not impede the passage of normal or expected high flows and the structure or discharge shall withstand expected high flows. No activity may cause more than the minimal adverse effect on navigation.

3. The permittee shall conduct activities in accordance with time-of-year (TOY) restrictions recommended by the Department of Game and Inland Fisheries or the

Virginia Marine Resources Commission. The permittee shall maintain a copy of such TOY restriction or notification that no restriction is necessary, for the duration of the construction phase of the project. No such TOY restriction had been recommended at the time of permit issuance.

4. All excavation, dredging, and/or filling in surface waters shall be accomplished in a manner that minimizes benthic sediment disturbances and turbidity increases in the water column.

5. Virginia Water Quality Standards shall not be violated in any surface water as a result of the project activities.

6. Temporary disturbances to wetlands during construction shall be avoided and minimized to the maximum extent practicable. All temporarily disturbed wetland areas shall be stabilized within 30 days of completing work, restored to pre-construction conditions, and planted or seeded with appropriate wetland vegetation according to cover type (emergent). The permittee shall take all appropriate measures to promote revegetation of temporarily disturbed wetland areas with wetland vegetation by the second year post-disturbance.

7. The permittee shall employ measures to prevent spills of fuels, lubricants, or other pollutants into surface waters.

8. All construction, construction access (for example, cofferdams, sheetpiling, and causeways) and demolition activities associated with this project shall be accomplished in a manner that minimizes construction or waste materials from entering surface waters to the maximum extent practicable, unless authorized by this permit.

9. All fill material shall be clean and free of contaminants in toxic concentrations or amounts in accordance with all applicable laws and regulations.

10. Wet or uncured concrete shall be prohibited from entry into surface waters.

11. In issuing this permit, DEQ has not taken into consideration the structural stability of any proposed structure.

C. <u>Construction Monitoring</u>

1. A photo station shall be established at each dredged material disposal site authorized by this permit. The photograph orientation at each station shall remain constant during all monitoring events. The photographs shall document site activities and conditions, which may include installation and maintenance of erosion and sediment controls;

flagged non-impact surface waters; construction access and staging areas; filling, excavation, and dredging activities; culvert installation; dredge disposal; and site stabilization, grading, and associated restoration activities. Photographs shall be taken prior to site activities, at the end of each month, and within one week of construction completion. Monthly photographs at an individual dredged material disposal site shall not be required until construction activities are initiated at that site. Monthly photographs at an individual dredged material disposal site shall not be required following completion of construction and achievement of final stabilization at that site. Each photograph shall be labeled to include the following information: permit number, dredged material disposal site and photo station number, date and time of the photograph, name of the person taking the photograph, photograph orientation, and photograph subject description.

D. Required Notifications and Submittals

1. All written communications required by this permit shall be submitted to the DEQ - Tidewater Regional Office, 5636 Southern Boulevard, Virginia Beach, Virginia 23462. The permit number shall be included on all correspondence.

2. All reports required by this permit and other information requested by DEQ shall be signed by the applicant or a person acting in the applicant's behalf, with the authority to bind the applicant. A person is a duly authorized representative only if:

   a. The authorization is made in writing by a person described above; and

   b. The authorization specifies either an individual or a position having responsibility for the overall operation of the regulated facility or activity, such as the position of plant manager, superintendent, or position of equivalent responsibility. A duly authorized representative may thus be either a named individual or any individual occupying a named position.

   c. If an authorization is no longer accurate because a different individual or position has responsibility for the overall operation of the facility, a new authorization shall be submitted to DEQ prior to or together with any separate information, or applications to be signed by an authorized representative.

3. All submittals required by this permit shall contain the following signed certification statement:

   I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of

my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violation.

4. Any fish kills or spills of fuels or oils shall be reported immediately upon discovery. If spills or fish kills occur between the hours of 8:15 AM to 5:00 PM Monday through Friday, DEQ shall be notified at (757) 518-2077; otherwise, the Department of Emergency Services shall be notified at 1-800-468-8892.

5. Violations of Virginia Water Quality Standards shall be reported within 24 hours to DEQ at (757) 518-2000.

6. DEQ shall be notified in writing when potential environmentally threatening conditions are encountered which require debris removal or involve potentially toxic substances. Measures to remove the obstruction, material, or toxic substance or to change the location of any structure are prohibited until approved by DEQ.

7. DEQ shall be notified in writing at least ten days prior to the initiation of construction activities authorized under this permit so that inspections of the project can be planned, if deemed necessary. The notification shall include identification of the impact and disposal sites at which work will occur and a projected schedule for completing work at each permitted impact and disposal site.

8. Construction monitoring reports shall be submitted to DEQ within 30 days of each monitoring event. The reports shall include, as appropriate, the following:

   a. A written narrative stating whether work was performed, a description of the work performed, when the work was initiated, and expected date of completion; a summary of activities conducted to comply with the permit conditions; a summary of permit non-compliance events or problems encountered, subsequent notifications, and corrective actions; a summary of anticipated work to be completed during the next reporting period; and an estimated date of project completion.

   b. A labeled site map depicting all impact and disposal sites and photo stations.

   c. Properly labeled photographs as described in Part I Section C.

9. Written notification and photographs shall be submitted within 30 days of restoration demonstrating that all temporarily disturbed wetland areas have been restored in compliance with the permit conditions.

10. DEQ shall be notified in writing within 30 days following the completion of all activities in permitted impact and disposal sites authorized under this permit.

E. Dredging

1. Dredging and excavation shall be limited to the minimum necessary to conduct the permitted activities. Dredging in each respective channel shall be limited to the following depths and dimensions: entrance channel to a depth of –12' MLLW, and approximately 150' wide and 3,500' long; mooring and turning basin to a depth of –12' MLLW, and approximately 750' wide and 1,250' long; side channel to a depth of –10' MLLW, and approximately 100' wide and 1,660' long; Long Creek channel to a depth of –11' MLLW, and approximately 90' wide and 10,000' long; and Narrows channel to a depth of –8' MLLW, and approximately 90' wide and 2,000' long. Dredging depths include all overdepth, advance maintenance, and margin of error.

2. A dredged material management plan for the designated disposal sites shall be submitted 30 days prior to the dredging activity.

3. The double handling of dredged material in surface waters shall not be permitted.

4. All dredged materials pumped by hydraulic method via pipeline to the disposal area will be done in such a manner as to prevent leakage or unauthorized discharge into surface waters. In the event of a ruptured pipeline, dredging/disposal operations shall immediately cease until repairs are accomplished.

5. During transport, dredged material shall be handled in accordance with the transport operation's spill prevention plan. In the event of a spill, the response portions of the plan shall be implemented immediately.

6. Barges used for the transportation of dredged material shall be filled in such a manner as to prevent any overflow of dredged material.

7. For navigation channels the following shall apply:

   a. A minimum of 15 feet shall be maintained between the top of the dredge cut and the channelward edge of vegetated wetlands.

   b. A buffer of four times the depth of the dredge cut shall be maintained between the top of the dredge cut and the channelward limit of wetlands..

8. Pre-dredging and post-dredging bathymetric surveys shall be submitted to DEQ within 30 days following completion of the dredging activity.

9. Each dredging event may remove approximately 15,000 yd^3 of material for a maximum of 50,000 yd^3 over a 10-year period from the Long Creek and Narrows channels. Each dredging event may also remove approximately 250,000 yd^3 of material for a maximum of 850,000 yd^3 over a 10-year period from the entrance channel, mooring and turning basin, and side channel.

10. Material from the Long Creek and Narrows channels shall be deposited at the Maple Street and First Landing State Park placement areas. Material from the entrance channel, mooring and turning basin, and side channel shall be deposited at the Ocean Park Beach for beach nourishment.

Part II – General Conditions

A. Duty to Comply

The permittee shall comply with all conditions of the VWP permit. Nothing in the VWP permit regulations shall be construed to relieve the permittee of the duty to comply with all applicable federal and state statutes, regulations and prohibitions. Any VWP permit violation is a violation of the law, and is grounds for enforcement action, VWP permit termination, revocation, modification, or denial of an application for a VWP permit extension or reissuance.

B. Duty to Cease or Confine Activity

It shall not be a defense for a permittee in an enforcement action that it would have been necessary to halt or reduce the activity for which a VWP permit has been granted in order to maintain compliance with the conditions of the VWP permit.

C. Duty to Mitigate

The permittee shall take all reasonable steps to minimize or prevent any impacts in violation of the permit which may have a reasonable likelihood of adversely affecting human health or the environment.

D. VWP Permit Action

1. A VWP permit may be modified, revoked and reissued, or terminated as set forth in 9 VAC 25-210 et seq.

2. If a permittee files a request for VWP permit modification, revocation, or termination, or files a notification of planned changes, or anticipated noncompliance, the VWP permit terms and conditions shall remain effective until the request is acted upon by the board. This provision shall not be used to extend the expiration date of the effective VWP permit. If the permittee wishes to continue an activity regulated by the VWP permit after the expiration date of the VWP permit, the permittee must apply for and obtain a new VWP permit or comply with the provisions of 9 VAC 25-210-185 (VWP Permit Extension).

3. VWP permits may be modified, revoked and reissued or terminated upon the request of the permittee or other person at the board's discretion, or upon board initiative to reflect the requirements of any changes in the statutes or regulations, or as a result of VWP permit noncompliance as indicated in the Duty to Comply subsection above, or for other reasons listed in 9 VAC 25-210-180 (Rules for Modification, Revocation and Reissuance, and Termination of VWP permits).

E. Inspection and Entry

Upon presentation of credentials, any duly authorized agent of the board may, at reasonable times and under reasonable circumstances:

1. Enter upon any permittee's property, public or private, and have access to, inspect and copy any records that must be kept as part of the VWP permit conditions;

2. Inspect any facilities, operations or practices (including monitoring and control equipment) regulated or required under the VWP permit, and

3. Sample or monitor any substance, parameter or activity for the purpose of ensuring compliance with the conditions of the VWP permit or as otherwise authorized by law.

F. Duty to Provide Information

1. The permittee shall furnish to the board any information which the board may request to determine whether cause exists for modifying, revoking, reissuing or terminating the VWP permit, or to determine compliance with the VWP permit. The permittee shall also furnish to the board, upon request, copies of records required to be kept by the permittee.

2. Plans, specifications, maps, conceptual reports and other relevant information shall be submitted as required by the board prior to commencing construction.

G. Monitoring and Records Requirements

1. Monitoring of parameters, other than pollutants, shall be conducted according to approved analytical methods as specified in the VWP permit. Analysis of pollutants will be conducted according to 40 CFR Part 136 (2000), Guidelines Establishing Test Procedures for the Analysis of Pollutants.

2. Samples and measurements taken for the purpose of monitoring shall be representative of the monitored activity.

3. The permittee shall retain records of all monitoring information, including all calibration and maintenance records and all original strip chart or electronic recordings for continuous monitoring instrumentation, copies of all reports required by the VWP permit, and records of all data used to complete the application for the VWP permit, for a period of at least three years from the date of the expiration of a granted VWP permit. This period may be extended by request of the board at any time.

4. Records of monitoring information shall include:

   a. The date, exact place and time of sampling or measurements;

b. The name of the individuals who performed the sampling or measurements;

c. The date and time the analyses were performed;

d. The name of the individuals who performed the analyses;

e. The analytical techniques or methods supporting the information such as observations, readings, calculations and bench data used;

f. The results of such analyses; and

g. Chain of custody documentation.

H. Transferability

This VWP permit may be transferred to a new permittee only by modification to reflect the transfer, by revoking and reissuing the permit, or by automatic transfer. Automatic transfer to a new permittee shall occur if:

1. The current permittee notifies the board within 30 days of the proposed transfer of the title to the facility or property;

2. The notice to the board includes a written agreement between the existing and proposed permittee containing a specific date of transfer of VWP permit responsibility, coverage and liability to the new permittee, or that the existing permittee will retain such responsibility, coverage, or liability, including liability for compliance with the requirements of any enforcement activities related to the permitted activity; and

3. The board does not within the 30-day time period notify the existing permittee and the new permittee of its intent to modify or revoke and reissue the VWP permit.

I. Property rights

The issuance of this permit does not convey any property rights in either real or personal property, or any exclusive privileges, nor does it authorize injury to private property or any invasion of personal rights or any infringement of federal, state or local law or regulation.

J. Reopener

Each VWP permit shall have a condition allowing the reopening of the VWP permit for the purpose of modifying the conditions of the VWP permit to meet new regulatory standards duly adopted by the board. Cause for reopening VWP permits includes, but is not limited to when the circumstances on which the previous VWP permit was based have materially and substantially changed, or special studies conducted by the board or the permittee show material

and substantial change, since the time the VWP permit was issued and thereby constitute cause for VWP permit modification or revocation and reissuance.

K. Compliance with State and Federal Law

Compliance with this VWP permit constitutes compliance with the VWP permit requirements of the State Water Control Law. Nothing in this VWP permit shall be construed to preclude the institution of any legal action under or relieve the permittee from any responsibilities, liabilities, or other penalties established pursuant to any other state law or regulation or under the authority preserved by § 510 of the Clean Water Act.

L. Severability

The provisions of this VWP permit are severable.

M. Permit Modification

A VWP permit may be modified, but not revoked and reissued except when the permittee agrees or requests, when any of the following developments occur:

1. When additions or alterations have been made to the affected facility or activity which require the application of VWP permit conditions that differ from those of the existing VWP permit or are absent from it;

2. When new information becomes available about the operation or activity covered by the VWP permit which was not available at VWP permit issuance and would have justified the application of different VWP permit conditions at the time of VWP permit issuance;

3. When a change is made in the promulgated standards or regulations on which the VWP permit was based;

4. When it becomes necessary to change final dates in schedules due to circumstances over which the permittee has little or no control such as acts of God, materials shortages, etc. However, in no case may a compliance schedule be modified to extend beyond any applicable statutory deadline of the Act;

5. When changes occur which are subject to "reopener clauses" in the VWP permit; or

6. When the board determines that minimum instream flow levels resulting from the permittee's withdrawal of water are detrimental to the instream beneficial use and the withdrawal of water should be subject to further net limitations or when an area is declared a Surface Water Management Area pursuant to §§ 62.1-242 through 62.1-253 of the Code of Virginia, during the term of the VWP permit.

N. Permit Termination

After notice and opportunity for a formal hearing pursuant to Procedural Rule No. 1 (9 VAC 25-230-100) a VWP permit can be terminated for cause. Causes for termination are as follows:

1. Noncompliance by the permittee with any condition of the VWP permit;

2. The permittee's failure in the application or during the VWP permit issuance process to disclose fully all relevant facts or the permittee's misrepresentation of any relevant facts at any time;

3. The permittee's violation of a special or judicial order;

4. A determination by the board that the permitted activity endangers human health or the environment and can be regulated to acceptable levels by VWP permit modification or termination;

5. A change in any condition that requires either a temporary or permanent reduction or elimination of any activity controlled by the VWP permit; and

6. A determination that the permitted activity has ceased and that the compensatory mitigation for unavoidable adverse impacts has been successfully completed.

O. Civil and Criminal Liability

Nothing in this VWP permit shall be construed to relieve the permittee from civil and criminal penalties for noncompliance.

P. Oil and Hazardous Substance Liability

Nothing in this VWP permit shall be construed to preclude the institution of legal action or relieve the permittee from any responsibilities, liabilities, or penalties to which the permittee is

or may be subject under § 311 of the Clean Water Act or §§ 62.1-44.34:14 through 62.1-44.34:23 of the State Water Control Law.

Q. Unauthorized Discharge of Pollutants

Except in compliance with this VWP permit, it shall be unlawful for the permittee to:

1. Discharge into state waters sewage, industrial wastes, other wastes, or any noxious or deleterious substances;

2. Excavate in a wetland;

3. Otherwise alter the physical, chemical, or biological properties of state waters and make them detrimental to the public health, to animal or aquatic life, to the uses of such waters for domestic or industrial consumption, for recreation, or for other uses.

5. On or after October 1, 2001 conduct the following activities in a wetland:
   a. New activities to cause draining that significantly alters or degrades existing wetland acreage or functions
   b. Filling or dumping
   c. Permanent flooding or impounding
   d. New activities that cause significant alteration or degradation of existing wetland acreage or functions.

R. Permit Extension

1. Any permittee with an effective VWP permit for an activity that is expected to continue after the expiration date of the VWP permit, without any change in the activity authorized by the VWP permit, shall submit written notification request if an extension. The permittee must file the request prior to the expiration date of the VWP permit. Under no circumstances will the extension be granted for more than 15 years beyond the original effective date of the VWP permit. If the request for extension if denied, the VWP permit will still expire on its original date and, therefore, care should be taken to allow for sufficient time for the board to evaluate the extension request and to process a full VWP permit modification, if required.

COMMONWEALTH of VIRGINIA

W. Tayloe Murphy, Jr.
Secretary of Natural Resources

Marine Resources Commission
2600 Washington Avenue
Third Floor
Newport News, Virginia 23607

William A. Pruitt
Commissioner

June 14, 2004

Mr. Matthew T. Byrne, P.E.
Chief, Operations Branch
U. S. Army Corps of Engineers
803 Front St.
Norfolk, VA 23510-1096

RE: VMRC #04-0038

Dear Mr. Byrne:

Enclosed is the Marine Resources Commission permit for your proposal to hydraulically place approximately 7,500 cubic yards of sandy dredged material, per dredge cycle, from the Narrows channel in Virginia Beach, on a previously used site along 1,000 linear feet of the First Landing Seashore State Park shoreline in Virginia Beach.

A yellow placard is also enclosed. This placard reflects the authorized activities for inspection purposes and must be conspicuously displayed at the work site throughout the construction phase. Failure to properly post the placard in a prominent location will be considered a violation of your permit conditions.

YOU ARE REMINDED THAT ANY DEVIATION FROM THE PERMIT OR ATTACHED DRAWINGS REQUIRES PRIOR AUTHORIZATION FROM THE MARINE RESOURCES COMMISSION. FAILURE TO OBTAIN THE NECESSARY MODIFICATION WILL BE CONSIDERED A VIOLATION AND COULD SUBJECT YOU TO CIVIL CHARGES IN AMOUNTS NOT TO EXCEED $10,000 PER VIOLATION.

June 14, 2004

The work authorized by this permit is to be completed by May 31, 2007. Please note that in conformance with Special Condition 17 of your permit you are to notify the Commission prior to commencement of your permitted project. The enclosed self-addressed, stamped post card is to be used for this purpose. All other conditions of the permit will remain in effect.

Please be advised that you may also require issuance of a U. S. Army Corps of Engineers permit before you begin work on this project. You may wish to contact them directly to verify any permitting requirements.

Sincerely,

Robert W. Grabb
Chief, Habitat Management

RWG/bac
HM
Enclosure
cc: U. S. Army Corps of Engineers
Virginia Beach Wetlands Board

MRC 30-317

VMRC# 04-0038
Applicant: Army Corps of Engineers

COMMONWEALTH OF VIRGINIA
MARINE RESOURCES COMMISSION
PERMIT

The Commonwealth of Virginia, Marine Resources Commission, hereinafter referred to as the Commission, on this **25th** day of **May 2004**, hereby grants unto:

Army Corps of Engineers
Chief, Operations Branch
Norfolk District
803 Front Street
Norfolk, Virginia 23510-1096

hereinafter referred to as the Permittee, permission to:

_x_ Encroach in, on, or over State-owned subaqueous bottoms pursuant to Chapter 12, Subtitle III, of Title 28.2 of the Code of Virginia.

____ Use or develop tidal wetlands pursuant to Chapter 13, Subtitle III, of Title 28.2 of the Code of Virginia.

Permittee is hereby authorized to hydraulically place approximately 7,500 cubic yards of sandy dredged material, per dredge cycle, from the Narrows channel in Virginia Beach, on a previously used site along 1,000 linear feet of the First Landing Seashore State Park shoreline in Virginia Beach. All activities authorized herein shall be accomplished in conformance with the plans and drawings dated received 1/08/04, and/or 4/29/04, which are attached and made a part of this permit.

This permit is granted subject to the following conditions:

(1) The work authorized by this permit shall be completed by **May 31, 2007**. The Permittee shall notify the Commission when the project is completed. The completion date may be extended by the Commission in its discretion. Any such application for extension of time shall be in writing prior to the above completion date and shall specify the reason for such extension and the expected date of completion of construction. All other conditions remain in effect until revoked by the Commission or the General Assembly.

(2) This permit grants no authority to the Permittee to encroach upon the property rights, including riparian rights, of others.

(3) The duly authorized agents of the Commission shall have the right to enter upon the premises at reasonable times, for the purpose of inspecting the work being done pursuant to this permit.

(4) The Permittee shall comply with the water quality standards as established by the Department of Environmental Quality, Water Division, and all other applicable laws, ordinances, rules and regulations affecting the conduct of the project. The granting of this permit shall not relieve the Permittee of the responsibility of obtaining any and all other permits or authority for the projects.

(5) This permit shall not be transferred without written consent of the Commissioner.

(6) This permit shall not affect or interfere with the right vouchsafed to the people of Virginia concerning fishing, fowling and the catching of and taking of oysters and other shellfish in and from the bottom of acres and waters not included within the terms of this permit.

(7) The Permittee shall, to the greatest extent practicable, minimize the adverse effects of the project upon adjacent properties and wetlands and upon the natural resources of the Commonwealth.

(8) This permit may be revoked at any time by the Commission upon the failure of the Permittee to comply with any of the terms and conditions hereof or at the will of the General Assembly of Virginia.

(9) There is expressly excluded from the permit any portion of the waters within the boundaries of the Baylor Survey.

(10) This permit is subject to any lease of oyster planting ground in effect on the date of this permit. Nothing in this permit shall be construed as allowing the Permittee to encroach on any lease without the consent of the leaseholder. The Permittee shall be liable for any damages to such lease.

(11) The issuance of this permit does not confer upon the Permittee any interest or title to the beds of the waters.

(12) All structures authorized by this permit which are not maintained in good repair shall be completely removed from State-owned bottom within three (3) months after notification by the Commission.

(13) The Permittee agrees to comply with all of the terms and conditions as set forth in this permit and that the project will be accomplished within the boundaries as outlined in the plans attached hereto. Any encroachment beyond the limits of this permit shall constitute a Class 1 misdemeanor.

(14) This permit authorizes no claim to archaeological artifacts which may be encountered during the course of construction. If, however, archaeological remains are encountered, the Permittee agrees to notify the Commission, who will, in turn notify the Department of Historic Resources. The Permittee further agrees to cooperate with agencies of the Commonwealth in the recovery of archaeological remains if deemed necessary.

(15) The Permittee agrees to indemnify and save harmless the Commonwealth of Virginia from any liability arising from the establishment, operation or maintenance of said project.

The following special conditions are imposed on this permit:

(16) The yellow placard accompanying this permit document must be conspicuously displayed at the work site throughout the construction phase of the authorized activity.

(17) Permittee agrees to notify the Commission a minimum of 15 days prior to the start of the construction activities authorized by this permit.

VMRC #04-0038

A permit issuing fee of: $100.00

and a royalty of: N/A (governmental exemption)

for a total of **$100.00** This permit consists of 6 sheets.

PERMITTEE

Permittee's signature is affixed hereto as evidence of acceptance of all of the terms and conditions herein.

In cases where the Permittee is a corporation, agency or political jurisdiction, please assure that the individual who signs for the Permittee has proper authorization to bind the organization to the financial and performance obligations which result from activity authorized by this permit.

PERMITTEE

Accepted for Army Corps of Engineers

9TH day of June, 2004 By Matt T. Byrne Ch, Operations Br
(Name) (Title)

State of Virginia
City (or County) of , to-wit:

I, Lois A. Wilkins a Notary Public in and for said City (or County) and State hereby certify that Matthew T. Byrne, Permittee, whose name is signed to the foregoing, has acknowledged the same before me in my City (or County) and State aforesaid.

Given under my hand this 9th day of June, 2004

My Commission Expires:

Notary Public Lois A. Wilkins

Lois A. Wilkins
NOTARY PUBLIC
Commonwealth of Virginia
My Commission Expires 10/31/07

COMMISSION

IN WITNESS WHEREOF, the Commonwealth of Virginia, Marine Resources Commission has caused these presents to be executed in its behalf by Robert W. Grabb, Chief, Habitat Management
(Name) (Title) Marine Resources Commission

14th day of June, 2004 by

State of Virginia
City of Newport News, to wit:

I, Barbara A. Cundiff, a Notary Public within and for said City, State of Virginia, hereby certify that Robert W. Grabb, whose name is signed to the foregoing, bearing the 25th day of May 2004, has acknowledged the same before me in City aforesaid.

Given under my hand this 14th day of June, 20 04

My Commission Expires: 4-30-2007

Notary Public Barbara A. Cundiff

04-0038



NOTE(S)

1. NOT INTENDED FOR CONSTRUCTION. FOR CONCEPTUAL USE ONLY.
2. DATUM IS IN MLLW, TIDE RANGE IS 1.39' (1960-70 TIDAL EPOCH).

RECEIVED
APR 29 2004
MARINE RESOURCES COMMISSION
By

ADDITIONAL INFO
REVISION

DEPARTMENT OF THE ARMY
NORFOLK DISTRICT, CORPS OF ENGINEERS
NORFOLK, VIRGINIA

VIRGINIA BEACH, VIRGINIA

LYNNHAVEN INLET THE NARROWS SHORELINE PLACEMENT SITE

CORPS OF ENGINEERS

U.S.ARMY



TYPICAL SECTION

RECEIVED
JAN 8 2004

PURPOSE: Navigation Datum: NOS, MLLW Not To Scale	First Landing State Park Typical Cross Section of Placement Area	LYNNHAVEN INLET NAVIGATION PROJECT Proposed Maintenance Dredging by Norfolk District Corps of Engineers

The Narrows Channel
Plan View
Lynnhaven Inlet

LEGEND:

- Federal Navigation Channel
- Oyster Grounds
- Placement Sites

0 500 Feet

1" = 500'

N

MARINE RESOURCES COMMISSION
RECEIVED
JAN 8 2004

US Army Corps of Engineers
Norfolk District

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01150

SPECIAL WORK REQUIREMENTS

12/04

PART 1 GENERAL

1.1 SUBMITTALS
1.2 CONTRACTOR'S NOTIFICATIONS
1.2.1 Dredging Intent Notification to the Virginia Department of Environmental Quality, Virginia Marine Resources Commission and U.S. Coast Guard
1.3 REFERENCES
1.4 CONTRACTOR WORK REQUIREMENTS
1.4.1 Security and Public Safety of Work Areas
1.4.2 Noise Control and Abatement
1.4.3 Coordination with Other Contractors
1.4.4 Before Dredging Surveys
1.4.5 Final Examination and Acceptance
1.5 PHYSICAL DATA
1.5.1 Physical Conditions Information
1.5.2 Site Related Weather Conditions
1.5.3 Obstruction of Channel
1.5.4 Responsibility
1.5.5 Condition of Dredging Area
1.5.6 Channel Traffic
1.5.7 Oyster Grounds and Tidal Wetlands
1.5.8 Fixed Bridges and Utility Crossings
1.6 PUMPING OF BILGES
1.7 FUEL OIL TRANSFER OPERATIONS
1.8 LAYOUT OF WORK AND SURVEYS
1.8.1 General
1.8.1.1 Dredge Electronic Survey and Positioning Systems
1.8.2 Datum and Bench Marks
1.9 INSPECTION
1.9.1 General Inspection Requirements
1.10 SHOALING
1.10.1 Shoaling Prior to Dredging
1.10.2 Shoaling Subsequent to Dredging
1.11 SIGNAL LIGHTS
1.12 EQUIPMENT OWNERSHIP AND OPERATING EXPENSE SCHEDULE
1.12.1 Costs
1.12.2 Rentals
1.12.3 Data
1.13 BRIDGE-TO-BRIDGE RADIO COMMUNICATION
1.13.1 Radio

1.14 SPECIAL COAST GUARD REQUIREMENTS
1.14.1 Local Notice To Mariners
1.14.2 Relocation of Navigation Aids
1.14.3 Use of Coast Guard Navigation Aid Structures
1.15 ENVIRONMENTAL LITIGATION
1.15.1 Litigation
1.16 HISTORICAL AND ARCHAEOLOGICAL FINDS
1.17 PROFIT
1.17.1 Weighted Guidelines
1.17.2 Values
1.17.2.1 Degree of Risk
1.17.2.2 Relative Difficulty of Work
1.17.2.3 Size of Job
1.17.2.4 Periods of Performance
1.17.2.5 Contractor's Investment
1.17.2.6 Assistance by Government
1.17.2.7 Subcontracting
1.18 PARTNERING
1.19 SUBCONTRACTS AND WORK COORDINATION
1.20 ACCOMMODATION ABOARD DREDGE FOR CONSTRUCTION REPRESENTATIVES
1.20.1 Accommodations
1.20.2 Costs
1.21 CONTINUITY OF WORK

PART 2 PRODUCTS (THIS PART NOT USED)

PART 3 EXECUTION (THIS PART NOT USED)

-- End of Section Table of Contents --

SECTION 01150

SPECIAL WORK REQUIREMENTS
12/04

PART 1 GENERAL

1.1 SUBMITTALS

The Contractor shall make submittals for the following listed reports and certificates as required by the specifications. The Contracting Officer may request submittals in addition to those specified when deemed necessary to adequately describe the work. Units of weights and measures used on all submittals shall be the same as those used in the contract drawings. Each submittal shall be complete and in sufficient detail to allow ready determination of compliance with contract requirements. Prior to submittal, all items shall be checked and approved by the Contractor's Quality Control (CQC) representative and each item shall be stamped, signed, and dated by the CQC representative indicating action taken in accordance with SECTION 01451. Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-01 Preconstruction and Postconstruction Submittals

* Dredging Intent Notifications to Department of Environmental Quality, Virginia Marine Resources Commission and U.S. Coast Guard

Prior to commencement of dredging, submit a copy of Dredging Intent Notifications to Department of Environmental Quality, Virginia Marine Resources Commission, U.S. Coast Guard and at the same time to the Contracting Officer.

* Advance Notice for Dredging

Contractor advance notice for dredging will constitute his request for Before Dredging Surveys.

* After Dredging Survey Requests

Contractor after dredging survey requests will constitute his request for After Dredging Surveys.

1.2 CONTRACTOR'S NOTIFICATIONS

Dredging Intent Notification shall be prepared and sent to the agencies identified below identifying the dredging locations, placement areas, and dates the Contractor intends to start and complete dredging. When the Contractor sends a Notification to an agency, proper signatures as required in the Permit shall be affixed. A copy of all Notifications furnished shall at the same time be provided to the Contracting Officer. The Contractor

shall include the Virginia Water Protection (VWP) Permit Number on all Notifications sent to an agency.

1.2.1 Dredging Intent Notification to the Virginia Department of Environmental Quality, Virginia Marine Resources Commission and U.S. Coast Guard

a. The Contractor shall notify the Virginia Department of Environmental Quality, attention Bert Parolari, 5636 Southern Boulevard, Virginia Beach, Virginia 23462, in writing, at least 15 calendar days prior to commencement of dredging operations under this contract.

b. The Contractor shall notify the Virginia Marine Resources Commission, Habitat Management Division, 2600 Washington Avenue, Post Office Box 756, Newport News, Virginia 23607-0756, in writing, at least 15 calendar days prior to commencement of dredging operations under this contract.

c. The Contractor shall notify the Commander, Fifth Coast Guard District of his intended operations to dredge and request that it be published in the Local Notice to Mariners. This Dredging Intent Notification to U.S. Coast Guard must be given in sufficient time so that it appears in the Notice to Mariners at least 5 workdays prior to the commencement of this contract.

1.3 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

COAST GUARD, DEPARTMENT OF TRANSPORTATION

CFR PART 156.120	OIL AND HAZARDOUS MATERIAL TRANSFER OPERATIONS - Requirements for Transfer

1.4 CONTRACTOR WORK REQUIREMENTS

Each Channel dredging area shall constitute an acceptance section for payment purposes. The Contractor shall submit for approval as a part of his Work Plan the timeliness in which each respective Channel dredging area is to be completed. All work in a respective Channel dredging area must be completed and accepted before commencing work on the next respective Channel dredging area. The contractor shall accomplish the dredging in the following order:

(a) Entrance Channel
(b) Mooring and Turning Basin
(c) Long Creek Side Channel
(d) Channel to Broad Bay
(e) Narrows Channel.

1.4.1 Security and Public Safety of Work Areas

The dredging and placement areas are accessible to the general public;

however, the Contractor is informed the Government will not undertake to exclude the public or restrict public access to the dredging or placement areas during the work. The Contractor shall be solely responsible for protection of the public at all times for the duration of the contract and fully comply with the provisions of OSHA safe working practices and the Safety and Accident Prevention requirements of these specifications. The Contractor shall employ the use of signs, barricades, barriers, flagmen, and any other devices and measures required to insure public and worker safety at the dredging and placement areas at all times. Unless directed otherwise, the Contractor may perform the scheduled dredging work 24 hours a day, 7 days a week. During actual dredging and material placement operations, the Contractor shall insure adequate monitoring of operations by competent employees at the placement areas and contact with the dredge by monitoring personnel is maintained at all times. All lighting associated with the project shall be limited to the immediate area of active construction only. Such lighting shall be shielded, low-pressure sodium vapor lights directed to the maximum extent practical away from populated areas where applicable and to avoid excessive illumination of the water. Red filters shall be placed over vehicle headlights of the Contractor's plant and equipment used on the beach at night when work is performed in proximity to private residence housing.

1.4.2 Noise Control and Abatement

The Contractor shall employ the use of properly installed and maintained mufflers, silencers, and manufacturer's recommended sound suppressors on all plant, machinery, and equipment used on this work. The use of sound signals such as whistles, horns, or bells shall not be used if two-way radio communication can accomplish the required function. During the time between 9:00pm and 7:00am, the Contractor shall plan and schedule his work operations to minimize operations of plant and equipment on the beach. Noise of alarms from the backward use of plant on the beach during this period will be kept to a minimum; accordingly, the Contractor shall operate plant in a forward mode and limit beach fill operations to the maximum extent practical during this time. The Contractor shall not use sound signals, with the exception of those signals required for vessel operations by the U.S. Coast Guard, during the time between sunset and sunrise.

1.4.3 Coordination with Other Contractors

During the period of this contract, other contracts may be in force for the construction of other features of work on or adjacent to the site of work being accomplished under this contract. The Contractor shall arrange his plant, and shall schedule and perform this work, so as to effectively cooperate with all other contractors and Government agencies. It shall be the responsibility of the Contractor on this contract to be fully informed of the extent of the limits of work to be performed by other contractors. Should there be any conflict between these limits, the Contractor shall immediately notify the Contracting Officer of the conflict, and the Contracting Officer's decision shall be final.

1.4.4 Before Dredging Surveys

For the purpose of requesting Before Dredging Surveys, the Contractor shall

give the Contracting Officer a written Advance Notice for Dredging at least 14 calendar days prior to arrival of the dredge plant at the first work area, and shall furnish written notice at least 14 calendar days in advance of need for subsequent before dredging surveys. It is understood that the surveys made in response to the initial Advance Notice for Dredging by the Contractor will constitute the before dredging survey and that any subsequent surveys occasioned through Contractor delays will be charged against the Contractor at a rate of $5,000 per day. The Contracting Officer will not be responsible for any delays in the commencement of work caused by incomplete surveys if the Contractor fails to provide adequate advance written notice as specified.

1.4.5 Final Examination and Acceptance

As soon as practicable after the completion of the entire work or any portion of the work which in the opinion of the Contracting Officer will not be subject to damage by further operations under the contract, such work will be thoroughly examined at the cost and expense of the Government by sounding, as determined by the Contracting Officer. The Contractor shall submit a written After Dredging Survey Request to the Contracting Officer within adequate time of the completion of dredging to insure prompt performance of the after dredging acceptance surveys as required by U.S. Army Corps of Engineers Hydrographic Survey Manual EM 1110-2-1003. If the Contractor fails to provide this advance notice or is untimely in doing so, the Contracting Officer will not be responsible for any delays caused by incomplete surveys. Should any shoals, lumps, or other lack of contract depth be disclosed by this examination, the Contractor will be required to remove same by dredging at the contract rate for dredging; however, if the bottom is soft and the shoal areas are small and form no material obstruction to navigation, the removal of such shoal may be waived at the discretion of the Contracting Officer. The Contractor will be notified when soundings are to be made and may accompany the survey party. When the area is found to be in satisfactory condition, it will be accepted. Should more than two sounding operations by the Government over an area be necessary by reason of work for the removal of shoals disclosed at a prior sounding, the cost of such third and any subsequent sounding operations will be charged against the Contractor at the rate of $5,000 per day for each day in which the Government Plant is engaged in sounding or is en route to or from the site or held at or near the said site for such operations. Final acceptance of the whole or a part of the work and the deductions or corrections of deductions made thereon will not be reopened after having once been made, except on evidence of collusion, fraud, or obvious error, and the acceptance of a completed section shall not change the time of payment of the retained percentages of the whole or any part of the work.

1.5 PHYSICAL DATA

1.5.1 Physical Conditions Information

The physical conditions indicated on the drawings and in the specifications are the result of site investigations and surveys. Information and data furnished or referred to below is furnished for the Contractor's information; however, it shall be expressly understood that the Government will not be responsible for any interpretation or conclusion drawn from

this information or data by the Contractor. The approximate mean range of tide is noted on the respective drawings.

1.5.2 Site Related Weather Conditions

The location of the work in the Entrance Channel is exposed and wind and sea conditions may at times cause suspension of work. The Basin, Long Creek Side Channel, Channel to Broad Bay and the Narrows Channel are generally protected; however, strong northeast winds may cause suspension of work in the Basin area. The dredging areas are tidal with a mean range of tide of approximately 2.8 feet in the Entrance Channel, 2.1 foot in the Basin and Long Creek Side Channel, 1.8 to 2.1 foot in the Channel to Broad Bay, and 1.4 foot in the Narrows Channel. Complete weather forecasts, records and reports may be obtained from the National Weather Service in Wakefield, Virginia, telephone (757) 899-4200, Menu selection service or operator assisted as applicable. The Contractor shall satisfy himself as to the hazards likely to arise from the weather conditions during the dredging period.

1.5.3 Obstruction of Channel

The Government will not undertake to keep the area of channels free from vessels or other obstructions, except to the extent of such regulations, if any, as may be prescribed by the Secretary of the Army, in accordance with the provisions of Section 7 of the River and Harbor Act, approved 3 August 1917. The Contractor will be required to conduct the work in such manner as to obstruct navigation as little as possible, and in case the Contractors' plant so obstructs the channel as to make difficult or endanger the passage of vessels, said plant shall be promptly moved on the approach of any vessel to such an extent as may be necessary to afford a practicable passage. Upon the completion of the work, the Contractor shall promptly remove his plant, including ranges, buoys, piles, and other marks placed by him under this contract in navigable water or on shore.

1.5.4 Responsibility

The Contractor shall hold and save harmless the United States, its officers, and employees from all claims that may arise as a result of the Contractor's negligence in connection with the work performed under the contract, from noncompliance by the Contractor with the provisions of the contract drawings and specifications, or from the instruction of the Contracting Officer.

1.5.5 Condition of Dredging Area

The plans for dredging show the condition of the dredging area at the dates shown. The dredging areas may contain trash, debris, and small obstructions not shown on the plans for dredging. There are privately owned structures, bulkheads, piers, docks, mooring piles, and other similar existing items in proximity to the areas to be dredged that are in various conditions ranging from total deterioration to properly maintained. The Contractor shall exercise due care in all dredging and attendant plant operations to prevent damage to all structures, bulkheads, piers, docks, mooring piles, and any other existing items that remain in the work area during dredging

operations. Under separate contract a sunken wreck was removed from the Entrance Channel; however, the Contractor is advised to use caution in this area as portions of the wreck and demolition debris may be present.

1.5.6 Channel Traffic

The traffic that may be encountered during dredging operations consists of pilot vessels, commercial fishing vessels, charter fishing vessels, private yachts, and a large number of pleasure boats and recreational craft. The Contractor shall expect that the traffic will cause periodic delays and interruptions of his operations.

1.5.7 Oyster Grounds and Tidal Wetlands

Leased and public oyster grounds and tidal wetlands are present in the project area and are depicted on the contract drawings. As part of the Contractor’s responsibility to layout the work, the boundaries of the oyster beds in the vicinity of the work areas shall be marked in the field by the licensed Professional Engineer or Surveyor. The boundary points shall be physically located with stakes or pipe and marked with orange flagging prior to dredging operations. These markings shall be maintained during the duration of dredging and placement operations and removed upon completion of the scheduled work. The locations shown for the oyster grounds are based on information furnished by the Virginia Marine Resources Commission. In order to avoid damage to oyster grounds, the Contractor shall not allow personnel or the operation of plant and attendant vessels, including placement or traversing of pipelines, across the bounds of the public and private leased oyster and shellfish grounds, except as approved by the Contracting Officer. To the maximum extent practical, the Contractor’s work operations over and in the vicinity of the oyster grounds shall be at high tide. The Contractor shall submit for approval, in writing, as a part of the Dredging and Dredged Material Placement Plan a detailed drawing showing the layout for the proposed pipeline from the dredge to where the pipeline enters the confined or beach placement areas. Any pipeline approved to cross the bounds of the public and private leased oyster and shellfish grounds shall be floating.

1.5.8 Fixed Bridges and Utility Crossings

The Contractor is informed there are several fixed bridges that cross the waterway at locations as indicated. The Contractor shall be responsible to verify clearance restrictions for these structures and plan use for his plant accordingly. It is the Contractor's responsibility to investigate the location of all utility crossings. The Contractor shall take precautions against damages which might result from his operations in the vicinity of the utility crossings. If any damage occurs as a result of his operations, the Contractor will be required to suspend dredging until the damage is repaired and approved by the Contracting Officer. Costs of such repairs and downtime of the dredge and attendant plant shall be at the Contractor's expense.

1.6 PUMPING OF BILGES

Contractors are warned that pumping oil or bilge water containing oil into

navigable waters, or into areas which would permit the oil to flow into such waters, is prohibited by Section 13 of the River and Harbor Act of 1899, approved 3 March 1899 (30 Stat. 1152; 33 U.S.C. 407). Violation of this prohibition is subject to the penalties under the referenced Acts.

1.7 FUEL OIL TRANSFER OPERATIONS

In accordance with U.S. Coast Guard regulations CFR PART 156.120, couplings used in fuel oil transfer operations on any vessel with a capacity of 250 or more barrels of oil shall be either a bolted or full-threaded connection; or a quick-connect coupling approved by the Commandant; or an automatic back-pressure shutoff nozzle used to fuel the vessel. An executed fuel oil transfer (Declaration) form signed by the tanker operator shall be submitted to the Contracting Officer for each refueling operation.

1.8 LAYOUT OF WORK AND SURVEYS

1.8.1 General

The Contractor shall be responsible for the expense and layout of all work. When the Contractor's work methods require physical markings to be placed for the purpose of dredged material placement control, including all placement area and easement control points and all range markers and buoys indicated or that otherwise are required to accomplish the work, shall be placed in the field and marked by a licensed Professional Engineer or Surveyor currently licensed in the Commonwealth of Virginia. The markings shall be minimum 1 inch diameter steel pipe marked with orange flagging, placed in the immediate work areas only and shall be removed once a work area has been accepted. The Government reserves the right to verify all in-place markings before dredging and placement operations commence, and at any time during the contract. The Contractor shall give the Contracting Officer a minimum of at least 14 calendar days notice prior to commencement of dredging operations to assure the completion of the initial Government verification review.

1.8.1.1 Dredge Electronic Survey and Positioning Systems

The Contractor shall utilize a differential GPS electronic survey and dredge positioning system to perform all scheduled dredging operations with accuracies equal to contract payment surveys as specified in the Project Classification Requirements as outlined in U.S. Army Corps of Engineers Hydrographic Survey Manual EM 1110-2-1003. The Contractor shall provide real time positioning on a computer screen during dredging, and have the capability of playback in 15 minute intervals. The position must be recorded on a disk every 15 minutes and submitted to the Contracting Officer on a weekly basis. All electronic survey and dredge positioning systems equipment and the work accomplished with the use of the systems must render results in the same coordinate syatem as indicated on the contract drawings. All completed work shall be reviewed and certified as accurate by the Contractor's Quality Control Manager. This signed certification shall be submitted as a part of the Daily Report of Operations in accordance with the requirements of SECTION 01451 to assure that all work performed with the use of the equipment and systems meets contract requirements.

1.8.2 Datum and Bench Marks

The plane of reference shall be Mean Lower Low Water (MLLW) as established by National Ocean Service (NOS), as used on the drawings and in these specifications. The following listed benchmarks are referenced on the drawings and shall be used by the Contractor for the locations specified:

(a) BENCH MARK: C.E. "LYNN, 1988"

Entrance Channel: Station 122+00 to 164+59
Bench Mark Elevation: 8.05 feet above MLLW (NOS)

Entrance Channel, Mooring and Turning Basin, Long Creek Side Channel, and the Narrows Channel to Broad Bay from Station Number 87+00 to Station Number 122+00:
Bench Mark Elevation: 7.78 feet above MLLW (NOS)

Bench mark is located in the City of Virginia Beach, Virginia approximately 0.1 mile east of Lesner Bridge on U.S. Highway 60, on the north shore of and near the west end of Long Creek and 14.1 feet south-southwest of the southwest corner of the Virginia Pilot Association Administration Building, 31.3 feet WSW from SW corner of steps, 2.4 feet NNW from 9th piling, and 14.63 feet from turn on anchor fence. The bench mark is a standard C.O.E. brass disk, stamped "LYNN, 1988", set flush in the center of a concrete bulkhead.

(b) Channel to Broad Bay from Station Number 45+00 to Station Number 87+00:

BENCH MARK: C.E. "BUC, 2001"
ELEVATION: 5.32 feet above MLLW (NOS)

Located in the City of Virginia Beach, Virginia, from the intersection of Shore Drive and West Great Neck Road, proceed Southwest approximately 0.4 mile on West Great Neck Road to the intersection of West Great Neck Road and Buccaneer Road, turn right on Buccaneer Road and proceed West approximately 0.2 mile to address 2944 Buccaneer Road. The bench mark is a standard Corps of Engineers brass disk stamped "BUC 2001", situated in front of the residence approximately 14.6 feet South of the centerline of the road, 26.7 feet East of a four inch willow tree, 9.45 feet North of the bulkhead, 63.62 feet Southeast of the mailbox, set in concrete flush with the ground.

(c) Channel to Broad Bay from Station Number 0+00 to Station Number 45+00

BENCHMARK: C.E. "SPERM 1981"
ELEVATION: 3.91 feet above MLLW (NOS)

Located in the City of Virginia Beach, Virginia. From the intersection of Shore Drive and Great Neck Road proceed

approximately 0.5 mile south along Great Neck Road to Long Creek Canal Bridge. Bear right on bridge on a road leading under the bridge. Proceed approximately 0.3 mile to 2784 Broad Bay road. The benchmark is situated on the South side of road between power pole no. KF-76 and edge of road. The benchmark is a standard C.E. brass disk, approximately 1.5 feet north of power pole no. KF-76 and 1 foot south of edge of road, stamped "SPERM 1981", set in concrete flush with the ground.

(d) Ocean Park Beach Placement Site

BENCHMARK: C.E. "RICK 2004"
ELEVATION: 13.39 feet above MLLW (NOS)

Located in the City of Virginia Beach, Virginia, at the west end of the Lesner Bridge, proceed South on East Stratford Street one block to Piedmont Circle, turn left and proceed on Piedmont Circle to the entrance of the City boat ramp parking lot. The benchmark is situated 32.17 feet south of a chisled "x" on top of curbing, 39.36 feet southwest of a "Boat Trailer Parking Only" sign, 96.65 feet southwest of the southeast corner of parking lot, and 33.00 feet southeast of light pole no. 919R150. The benchmark is a standard Corps of Engineers brass disk stamped "RICK 2004".

(e) Maple Street Upland Placement Site

BENCHMARK: C.E. "SRG 2004"
ELEVATION: 10.58 feet above MLLW (NOS)

Located in the City of Virginia Beach, Virginia, from the intersection of Shore Drive and North Great Neck Road proceed 0.2 mile South on North Great Neck Road to Lynnhaven Drive. Turn left on Lynnhaven Drive and proceed East 0.1 mile to Marina Shores Drive (Long Creek Cove Condos). Turn right and proceed 0.3 mile to the end of Marina Shores Drive. The benchmark is situated 5.93 feet east of the back face of the curb, 67.29 feet west of the light pole, 38.10 feet southeast of a light pole, and 46.13 feet south of the southeast corner of transformer concrete pad. The benchmark is a standard Corps of Engineers brass disk stamped "SRG 2004".

(d) 64th Street Beach Placement Site

BENCHMARK: C.E. "64th 2004"
ELEVATION: 11.45 feet above MLLW (NOS)

Located in the City of Virginia Beach, Virginia, from Shore Drive and Atlantic Avenue, proceed south on Atlantic Avenue 1.3 miles to the intersection of 64th Street. Proceed west on 64th Street 1.8 miles to the boat ramp and parking lot. The benchmark is situated 49.27 feet north of the wooden post on the wooden rail, 46.05 feet northeast of the corner of the restroom facility, 27.57 feet northeast of the corner of the restroom facility, 31.85 feet east of the corner of the restroom facility, and 60.24 feet southeast

of the wooden post sign. The benchmark is a standard Corps of Engineers brass disk stamped "64th 2004".

1.9 INSPECTION

1.9.1 General Inspection Requirements

The presence of the construction representative shall not relieve the Contractor of responsibility for the proper execution of the work in accordance with the specifications. The Contractor will be required:

a. To furnish, on the request of the Contracting Officer or any construction representative, the use of such boats, boatmen, laborers, and material forming a part of the ordinary and usual equipment and crew of the dredging plant as may be reasonably necessary in inspecting and supervising the dredging.

b. To furnish, on the request of the Contracting Officer or any construction representative, suitable transportation from all points within the placement area, to and from the various pieces of plant and the staging areas, and within the material placement area as may be reasonably necessary in inspecting and supervising the work. Should the Contractor refuse, neglect, or delay compliance with these requirements, the specific facilities may be furnished and maintained by the Contracting Officer, and any resultant cost incurred by the government will be deducted from any amounts due or to become due the Contractor.

1.10 SHOALING

1.10.1 Shoaling Prior to Dredging

The drawings and quantity estimates are based on the condition of the dredging area at the time of the most recent surveys; however, the actual quantities to be dredged will be computed from surveys made immediately before dredging. Any shoaling that has developed, subsequent to the surveys indicated on the drawings and contiguous to the areas indicated to be dredged under this contract, shall be removed by the Contractor at the contract unit price for dredging, including any applicable unit price adjustments if so directed by the Contracting Officer. Any such shoaling within contiguous areas will be included as part of the required dredging prism for the purposes of CONTRACT CLAUSE "VARIATION IN ESTIMATED QUANTITIES".

1.10.2 Shoaling Subsequent to Dredging

If, before the contract is completed, shoaling occurs in any section previously accepted because of the natural lowering of the side slopes, re-dredging at contract price, including any applicable unit price adjustments, within the limit of available funds, may be done if agreeable to both the Contractor and the Contracting Officer.

1.11 SIGNAL LIGHTS

The Contractor shall display signal lights and conduct his operations in accordance with the General Regulations of the Department of the Army and of the Coast Guard governing lights and day signals to be displayed by towing vessels with tows on which no signals can be displayed, vessels working on wrecks, dredges, and vessels engaged in laying cables or pipe or in submarine or bank protection operations, lights to be displayed on dredge pipe lines, and day signals to be displayed by vessels of more than 65-feet in length moored or anchored in a fairway or channel, and the passing by other vessels of floating plant working in navigable channels, as approved by the Secretary of the Army and the Commandant, U. S. Coast Guard.

1.12 EQUIPMENT OWNERSHIP AND OPERATING EXPENSE SCHEDULE

1.12.1 Costs

Allowable cost for construction and marine plant and equipment in sound workable condition owned or controlled and furnished by a Contractor or subcontractor at any tier shall be based on actual cost data when the Government can determine both ownership and operating costs for each piece of equipment or equipment groups of similar serial and series from the Contractor's accounting records. When both ownership and operating costs cannot be determined from the Contractor's accounting records, equipment costs shall be based upon the applicable provisions of EP 1110-1-8, "Construction Equipment Ownership and Operating Expense Schedule", Region II. Working conditions shall be considered to be average for determining equipment rates using the schedule unless specified otherwise by the Contracting Officer. For equipment not included in the schedule, rates for comparable pieces of equipment may be used or a rate may be developed using the formula provided in the schedule. For forward pricing, the schedule in effect at the time of negotiations shall apply. For retrospective pricing, the schedule in effect at the time the work was performed shall apply.

1.12.2 Rentals

Equipment rental costs are allowable, subject to the provisions of FAR 31.105(d)(ii) and FAR 31.205-36 substantiated by certified copies of paid invoices. Rates for equipment rented from an organization under common control, lease-purchase or sale-leaseback arrangements will be determined using the schedule except that rental costs leased from an organization under common control that has an established practice of leasing the same or similar equipment to unaffiliated lessees are allowable. Costs for major repairs and overhaul are unallowable.

1.12.3 Data

When actual equipment costs are proposed and the total amount of the pricing action is over $25,000, cost or pricing data shall be submitted on the Standard Form 1411, "Contract Pricing Proposal Cover Sheet". By submitting cost or pricing data, the Contractor grants to the Contracting Officer or an authorizing representative the right to examine those books, records, documents and other supporting data that will permit evaluation of

the proposed equipment costs. After price agreement the Contractor shall certify that the equipment costs or pricing data submitted are accurate, complete and current.

1.13 BRIDGE-TO-BRIDGE RADIO COMMUNICATION

In order that radio communication may be made with passing vessels, all dredges engaged in work under this contract shall be equipped with bridge-to-bridge radio telephone equipment in accordance with 33 USC CHAPTER 24 , as applicable. The radio telephone equipment shall operate on a single channel very high frequency (VHF), FM, on a frequency of 156.65 megahertz (Channel 13 and 16) with low power output having a communication range of approximately ten miles. The Federal Communications Commission has approved the frequency.

1.13.1 Radio

The Contractor shall provide the Government construction representative a portable radio capable of communicating with the dredge for the duration of work under this contract. The Contractor shall maintain the radio as required.

1.14 SPECIAL COAST GUARD REQUIREMENTS

1.14.1 Local Notice To Mariners

The Local Notice To Mariners (LNM) for the Fifth Coast Guard District is available by phone at (757) 398-6367. Additionally, LNM are on the Internet at:

http://www.navcen.uscg.gov/lnm/d5/default.htm, and
e-mail address: D5Local@LANTD5.uscg.mil.

The LNM is the primary means for disseminating information concerning aids to navigation, hazards to navigation, and other items of marine information of interest to mariners on the waters of the United States, its territories, and possessions. These notices are essential to all navigators for the purpose of keeping their charts, light lists, Coast Pilots and other nautical publications up-to-date. These notices are published weekly. They may be obtained free of charge, by making application to the Fifth Coast Guard District, Federal Building, 431 Crawford Street, Portsmouth, Virginia 23704. If the Contractor encounters any objects on the channel bottom during dredging operations or transport of his plant that could be a hazard to navigation, he shall notify the Coast Guard immediately as to location and at the same time notify the Contracting Officer.

1.14.2 Relocation of Navigation Aids

The Contractor shall not relocate or move any aids to navigation that have been established by the U.S. Coast Guard. If it becomes necessary to have any aid to navigation moved in order to complete dredging operations under this contract, the Contractor shall notify the U.S. Coast Guard in writing at the address above with a copy to the Contracting Officer not less than

15 calendar days prior to such need for movement. The Contractor shall notify the U.S. Coast Guard of the approximate time the navigation aid may be relocated to its original position. All notifications to the U.S. Coast Guard shall at the same time be provided to the Contracting Officer and recorded in the Daily Report of Operations. In the event that the Contractor disturbs or damages any navigation aid during work operations, which includes during mobilization or demobilization of his plant, the Contractor shall immediately stop the activity which disturbed or damaged the navigation aid, take immediate corrective action to prevent further disturbances or damage, and shall notify the Coast Guard immediately as to location, and at the same time notify the Contracting Officer.

1.14.3 Use of Coast Guard Navigation Aid Structures

The Commander, Fifth Coast Guard District, has authorized the Norfolk District, Corps of Engineers, and its Contractors to use fixed Federal aids to navigation structures, established and maintained by the U. S. Coast Guard, for support of temporary dredging tide gauges when performing Federal dredging operations. If a Contractor chooses to use navigation aid structures for this purpose, he shall abide by the following requirements:

a. The Contractor shall advise the Commander, Fifth Coast Guard District, Aids to Navigation Branch, Federal Building, 431 Crawford Street, Portsmouth, Virginia 23704, in writing, of his intention to attach tide gauges to navigation aid and structures, prior to commencing a dredging project. This notice shall include the name of each aid to navigation to which tide gauges are to be attached, and the anticipated dates the gauges will be attached and removed. A copy of this notice shall be furnished at this time to the Contracting Officer.

b. The Contractor shall be required to remove any temporary tide gauges immediately upon completion of dredging operations and demobilization of dredging plant. The Contractor shall at his expense repair or replace any aids that he has damaged or destroyed as a result of the Contractor's use of such aids.

c. This provision refers only to Federal aids to navigation structures and does not authorize the Contractor to utilize aids that are not established and maintained by the U. S. Coast Guard. This provision also does not authorize the Contractor to utilize Federal navigation aid structures for any purposes other than the support of temporary tide gauges.

1.15 ENVIRONMENTAL LITIGATION

1.15.1 Litigation

If the performance of all or any part of the work is suspended, delayed, or interrupted due to an order of a court of competent jurisdiction as a result of environmental litigation, as defined below, the Contracting Officer, at the request of the Contractor, shall determine whether the order is due in any part to the acts or omissions of the Contractor or a subcontractor at any tier not required by the terms of this contract. If it is determined that the order is not due in any part to acts or omissions

of the Contractor or a subcontractor at any tier other than as required by the terms of this contract, such suspension, delay, or interruption shall be considered as if ordered by the Contracting Officer in the administration of this contract under the terms of the "Suspension of Work" clause of this contract. The period of such suspension, delay, or interruption shall be considered unreasonable, and an adjustment shall be made for any increase in the cost of performance of this contract (excluding profit) as provided in that clause, subject to all the provisions thereof. The term "environmental litigation" means, a lawsuit alleging that the work will have an adverse effect on the environment or that the Government has not duly considered, either substantively or procedurally, the effect of the work on the environment.

1.16 HISTORICAL AND ARCHAEOLOGICAL FINDS

Federal legislation provides for the protection, preservation, and collection of scientific, prehistoric, historic, and archaeological data, including relics and specimens that might otherwise be lost as a result of any Federal construction project. Should the Contractor, or any of the Contractor's employees, or parties operating or associated with the Contractor, in the performance of this contract discover evidence of possible scientific, prehistoric, historic, or archaeological data, the Contractor shall immediately cease work at that location, and notify the Contracting Officer, giving the location and nature of the findings. The Contractor shall forward written confirmation to the Contracting Officer as directed. The Contractor shall exercise care so as not to disturb or damage shipwrecks, artifacts or fossils uncovered during excavation, dredging and material placement operations, and shall provide such cooperation and assistance as may be necessary to preserve the findings for removal or other disposition. Any person who, without written permission, injures, destroys, excavates, appropriates, moves or removes any historic or prehistoric artifact, object of antiquity, or archaeological resource is subject to arrest and penalty of law. Where appropriate by reason of discovery, the Contracting Officer may order delays in the time of performance or changes in the work, or both. If such delays or changes are ordered, an equitable adjustment will be made in accordance with the applicable clauses of the contract.

1.17 PROFIT

1.17.1 Weighted Guidelines

Weighted guidelines method of determining profit shall be used on any equitable adjustment change order or modification issued under this contract. The profit factors, expressed as a percent, shall be as follows:

Factor	Rate	Weight	Value
Degree of Risk	20		
Relative difficulty of work	15		
Size of Job	15		
Period of performance	15		
Contractor's investment	5		
Assistance by Government	5		

Subcontracting $\frac{25}{100}$

1.17.2 Values

Based on the circumstances of each procurement action, each of the above factors shall be weighted from .03 to .12 as indicated below. The value shall be obtained by multiplying the rate by the weight. The value column when totaled indicates the fair and reasonable profit percentage under the circumstances of the particular procurement.

1.17.2.1 Degree of Risk

Where the work involves no risk or the degree of risk is very small, the weighting should be .03; as the degree of risk increases, the weighting should be increased up to a maximum of .12. Lump sum items will have, generally, a higher weighted value than the unit price items for which quantities are provided. Other things to consider: the portion of the work to be done by subcontractors, nature of work, where work is to be performed, reasonableness of negotiated costs, amount of labor included in costs, and whether the negotiation is before or after performance of work.

1.17.2.2 Relative Difficulty of Work

If the work is most difficult and complex, the weighting should be .12 and should be proportionately reduced to .03 on the simplest of jobs. This factor is tied in to some extent with the degree of risk. Some things to consider: the nature of the work, by whom it is to be done, where, and what is the time schedule.

1.17.2.3 Size of Job

All work not in excess of $100,000 shall be weighted at .12. Work estimated between $100,000 and $5,000,000 shall be proportionately weighted from .12 to .05.

1.17.2.4 Periods of Performance

Jobs in excess of 24 months are to be weighted at .12. Jobs of lesser duration are to be proportionately weighted to a minimum of .03 for jobs not to exceed 30 days. No weight where additional time not required.

1.17.2.5 Contractor's Investment

To be weighted from .03 to .12 on the basis of below average, average, and above average. Things to consider: amount of subcontracting, mobilization payment item, Government furnished property, equipment and facilities, and expediting assistance.

1.17.2.6 Assistance by Government

To be weighted from .12 to .03 on the basis of average to above average. Things to consider: use of Government owned property, equipment and facilities, and expediting assistance.

1.17.2.7 Subcontracting

Shall be weighted inversely proportional to the amount of subcontracting. Where 80 percent or more of the work is to be subcontracted, the weighting is to be .03 and such weighting proportionately increased to .12 where all the work is performed by the Contractor's own forces.

1.18 PARTNERING

In order to most effectively accomplish this contract, the Government is willing to form a cohesive partnership with the Contractor. This partnership would strive to draw on the strengths of each organization in an effort to achieve a quality project done correctly, within budget, and on time. This partnership would be bilateral in make-up and partnership will be totally voluntary. Any cost associated with effectuating this partnership will be agreed to by all parties and will be shared equally with no change in contract price.

1.19 SUBCONTRACTS AND WORK COORDINATION

Contract Clauses "SUBCONTRACTS", "PERMITS AND RESPONSIBILITIES", and "MATERIAL AND WORKMANSHIP" are supplemented as follows:

(a) Divisions or sections of specifications are not intended to control the Contractor in dividing the work among subcontractors, or to limit work performed by any trade.

(b) Contractor shall be responsible for coordination of the work of the trades, subcontractors, and materials.

(c) The Government or its representative will not undertake to settle any difference between the Contractor and Contractor's subcontractors, or between subcontractors.

(d) The Government reserves the right to refuse to permit employment on the work or require dismissal from the work of any subcontractor who, by reason of previous unsatisfactory work on Corps of Engineers projects, or for any other reason is considered by the Contracting Officer to be incompetent or otherwise objectionable.

1.20 ACCOMMODATION ABOARD DREDGE FOR CONSTRUCTION REPRESENTATIVES

1.20.1 Accommodations

(a) Work Space - The Contractor shall furnish regularly to Government construction representatives on board the dredge a suitable working and storage space, equipped and maintained to the satisfaction of the Contracting Officer or his representative. As a minimum the facilities shall include a desk with chair for plan study, and a file drawer, approximately 15" by 24", capable of being locked with a padlock. The working space need not be a separate room, but shall be properly lighted, ventilated, and heated.

1.20.2 Costs

The entire cost to the Contractor for furnishing, equipping, and maintaining the foregoing accommodations shall be included in the contract price. If the Contractor fails to meet these requirements, the Contracting Officer will secure the facilities referred to above, and their costs will be deducted from payments due to the Contractor.

1.21 CONTINUITY OF WORK

No payment will be made for work done in any area designated by the Contracting Officer until the full depth required under the contract is secured in the whole of such area, unless prevented by ledge rock, nor will payment be made for excavation in any area not adjacent to and in prolongation of areas where full depth has been secured, except by decision of the Contracting Officer. Should any such nonadjacent area be excavated to full depth during the operations carried on under the contract, payment for all work therein may be deferred until the required depth has been made in the area intervening. The Contractor may be required to suspend dredging at any time when, for any reason, the gauges or ranges cannot be seen or properly followed.

PART 2 PRODUCTS (THIS PART NOT USED)

PART 3 EXECUTION (THIS PART NOT USED)

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01270

MEASUREMENT AND PAYMENT

01/05

PART 1 GENERAL

1.1 SUBMITTALS
1.2 LUMP SUM PAYMENT ITEMS
1.2.1 Payment Item No. 0001 Mobilization and Demobilization
1.2.1.1 Mobilization
1.2.1.2 Demobilization
1.3 UNIT PRICE PAYMENT ITEMS
1.3.1 Payment Item No. 0002 Dredging
1.4 MISPLACED MATERIAL
1.5 EXCESSIVE DREDGING
1.6 MONTHLY PARTIAL PAYMENTS

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION (Not Applicable)

-- End of Section Table of Contents --

SECTION 01270

MEASUREMENT AND PAYMENT
01/05

PART 1 GENERAL

1.1 SUBMITTALS

Not Used.

1.2 LUMP SUM PAYMENT ITEMS

Payment items for the work of this contract for which contract lump sum payments will be made are listed in the BIDDING SCHEDULE and described below. All costs for items of work, which are not specifically mentioned to be included in a particular lump sum or unit price payment item, shall be included in the listed lump sum item most closely associated with the work involved. The lump sum price and payment made for each item listed shall constitute full compensation for furnishing all plant, labor, materials, and equipment, and performing any associated Contractor quality control, environmental protection, meeting safety requirements, tests and reports, and for performing all work required for which separate payment is not otherwise provided.

1.2.1 Payment Item No. 0001 Mobilization and Demobilization

All costs connected with the mobilization and demobilization of all of the Contractor's dredging plant and equipment as defined below will be paid for at the contract lump sum price for this item. Sixty percent of the lump sum price will be paid to the Contractor upon completion of his mobilization at the work site. The remaining forty percent will be paid to the Contractor upon completion of demobilization. In the event the Contracting Officer considers that the amount in this item, sixty percent which represents mobilization and forty percent which represents demobilization, does not bear a reasonable relation to the cost of the work in this contract, the Contracting Officer may require the Contractor to produce cost data to justify this portion of the bid. Failure to justify such price to the satisfaction of the Contracting Officer will result in payment of actual mobilization costs, as determined by the Contracting Officer, at the completion of mobilization, and actual demobilization costs, as determined by the Contracting Officer, at the completion of demobilization. The determination of the Contracting Officer is not subject to appeal.

1.2.1.1 Mobilization

Mobilization shall include all costs for operations accomplished prior to commencement of actual dredging operations. This shall include as a minimum the following:

a. Transfer of dredge and attendant plant, booster pumps, bulldozers and other like equipment and machinery for site work
b. Any required clearing or grading of the interior of the placement area
c. Repairs to dike and spillboxes, including removal of trash and debris to allow proper drainage through the spillbox, and replacement of inadequate weir boards and outfall piping
d. All initial installation of pipe
e. And any other associated work that is necessary in advance of the actual dredging operations.

1.2.1.2 Demobilization

Demobilization shall include general preparation for transfer of plant to its home base, removal of pipelines, cleanup of site of work including the placement area, and transfer of plant to its home base.

1.3 UNIT PRICE PAYMENT ITEMS

Payment items for the work of this contract on which the contract unit price payments will be made are listed in the BIDDING SCHEDULE and described below. The unit price and payment made for each item listed shall constitute full compensation for furnishing all plant, labor, materials, and equipment, and performing any associated Contractor quality control, environmental protection, meeting safety requirements, tests and reports, and for performing all work required for each of the unit price items.

1.3.1 Payment Item No. 0002 Dredging

Payment to be made for all costs associated with dredging shall include the cost of removal and placement of material as indicated and specified, exclusive of the mobilization and demobilization as defined above. The total amount of material removed and to be paid for under this payment item will be measured by the cubic yard in place by computing the volume between the bottom surface shown by soundings of the last surveys made before dredging, and the bottom surface shown by the soundings of surveys made as soon as practicable after the work has been completed. The volume for measurement and payment shall include the material within the limits of overdepth and side slopes described in paragraph "Required Dredging Prism, Overdepth, and Side Slopes" of SECTION 02325, less any deductions that may be required for misplaced material described in subparagraph "Misplaced Material", below. The drawings are believed to accurately represent conditions at the time of the surveys indicated. New soundings will be taken immediately before dredging as specified in paragraph "Before Dredging Surveys" of SECTION 01150. The Contractor's unit price for dredging, based on the above method of computation of the quantity for payment, shall include his evaluation of shoaling, other natural changes in the waterway, or changes caused by the Contractor's operations that might occur during the period between the surveys before dredging and the surveys for acceptance of the work. Computations for payment purposes will be made by the Government using, as defined in the USACE Hydrographic Survey Manual EM 1110-2-1003, the Average End Area (AEA) method, Triangulated Irregular Network (TIN) method, or a combination of these methods at the discretion

of the Government, utilizing proprietary electronic data processing software and machines for the calculations. Determination of quantities removed and the deductions made to determine quantities in place to be paid for in the areas specified, after having once been made, will not be reopened except on evidence of collusion, fraud, or obvious error.

1.4 MISPLACED MATERIAL

Any material that is deposited elsewhere than in places designated or approved by the Contracting Officer will not be paid for, and the Contractor may be required to remove such misplaced material and deposit it where directed by the Contracting Officer at the Contractor's expense.

1.5 EXCESSIVE DREDGING

Material taken from outside the specific areas to be dredged or beyond the limits as extended in paragraph "Required Dredging Prism, Overdepth, and Side Slopes" will be considered as excessive overdepth dredging, or excessive side slope dredging, for which payment will not be made. Nothing in these specifications shall be construed to prevent payment for the removal of shoals performed in accordance with the applicable provisions of Paragraphs SHOALING and FINAL EXAMINATION AND ACCEPTANCE of Section 01150.

1.6 MONTHLY PARTIAL PAYMENTS

Monthly partial payments will be based on estimated quantities determined by the Contracting Officer.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION (Not Applicable)

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01320

PROJECT SCHEDULE

01/05

PART 1 GENERAL

1.1 REFERENCES
1.2 QUALIFICATIONS
1.3 SUBMITTALS

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS
3.2 PROGRESS SCHEDULE
3.3 PROGRESS SCHEDULE FORMAT
3.3.1 Level of Detail Required
3.3.2 Activity Durations
3.3.3 Government Activities
3.3.4 Responsibility
3.3.5 Work Areas
3.3.6 Constraint of Last Activity
3.3.7 Standard Activity Coding Dictionary
3.4 UPDATED SCHEDULES

-- End of Section Table of Contents --

SECTION 01320

PROJECT SCHEDULE
01/05

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of the specification to the extent referenced. The publications are referenced in the text by basic designation only.

U.S. ARMY CORPS OF ENGINEERS (USACE)

ER 1-1-11 (1995) Progress, Schedules, and Network Analysis Systems

1.2 QUALIFICATIONS

The Contractor CQC representative shall be responsible for the preparation and certification as complete all required project Progress Schedule submittals and reports.

1.3 SUBMITTALS

The Contractor shall make submittals for the following listed reports and certificates as required by the specifications. The Contracting Officer may request submittals in addition to those specified when deemed necessary to adequately describe the work. Units of weights and measures used on all submittals shall be the same as those used in the contract drawings. Each submittal shall be complete and in sufficient detail to allow ready determination of compliance with contract requirements. Prior to submittal, all items shall be checked and approved by the Contractor's Quality Control (CQC) representative and each item shall be stamped, signed, and dated by the CQC representative indicating action taken in accordance with SECTION 01451. Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-01 Preconstruction and Postconstruction Submittals

Progress Schedule; G

Prior to commencement of dredging, submit a copy of Progress Schedule to Contracting Officer indicating the measures and processes the Contractor will employ to produce an end product that complies with the contract requirements.

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

Pursuant to the CONTRACT CLAUSE, SCHEDULE FOR CONSTRUCTION CONTRACTS, a project Progress Schedule as described below and specified in the CONTRACT CLAUSES shall be prepared. The scheduling of construction shall be the responsibility of the Contractor. Contractor management personnel shall actively participate in its development. Subcontractors and suppliers working on the project shall also contribute in developing and maintaining an accurate Project Schedule. The approved Project Schedule shall be used to measure the progress of the work, to aid in evaluating time extensions, and to provide the basis of all progress payments as applicable.

3.2 PROGRESS SCHEDULE

The Contractor shall submit his Progress Schedule to the Contracting Officer for approval at the Pre-Construction Conference specified in SECTION 01006 POST AWARD MEETINGS. The Progress Schedule shall be prepared and certified as complete by the Contractor's Quality Control Representative in the form of a chart graphically indicating the sequence proposed to accomplish each work feature or operation. The chart shall be prepared to show the starting and completion dates of all work features on a linear horizontal time scale beginning with date of Notice to Proceed, arrival date of Contractor's plant to the job site, all activities scheduled prior to dredging, dredging start and completion dates, calendar days to completion of all work, and contract completion date. Each activity in the construction shall be represented by an arrow and shall have a beginning and ending node (event). The entire project shall have only one beginning node and one ending node. The arrangement of arrows shall be such that they flow from the left to right. Each arrow representing an activity shall be annotated to show the activity description, duration and cost. The Contractor shall indicate on the chart the important work activities that are critical to the timely overall completion of the project. Key dates for important features or portions of work features are milestone dates and shall be so indicated on the chart.

3.3 PROGRESS SCHEDULE FORMAT

The computer software system or manual method(s) used by the Contractor to produce his Progress Schedule and any required associated information shall require approval by the Contracting Officer prior to submittal by the Contractor. Any computer software utilized by the Contractor to produce the Project Schedule shall be capable of providing all requirements of this specification. Failure of the Contractor to meet the requirements of this specification shall result in the disapproval of the schedule.

3.3.1 Level of Detail Required

The Project Schedule shall include an appropriate level of detail. Failure to develop or update the Project Schedule or provide data to the Contracting Officer at the appropriate level of detail, as specified herein

and directed by the Contracting Officer, shall result in the disapproval of the schedule. The Contracting Officer shall use as a minimum, but is not limited to, the following conditions to determine the appropriate level of detail to be used in the Project Schedule:

3.3.2 Activity Durations

Contractor submissions shall follow the direction of the Contracting Officer regarding reasonable activity durations. Reasonable durations are those that allow the progress of activities to be accurately determined between payment periods (usually less than 2 percent of all non-procurement activities' Original Durations are greater than 20 days).

3.3.3 Government Activities

Government and other agency activities that could impact progress shall be shown. These activities include, but are not limited to:

required Contractor submittals for Government approval
Government surveys for payment
inspections required by the contract.

3.3.4 Responsibility

All activities shall be identified in the project schedule by the party responsible to perform the work. Responsibility includes, but is not limited to: subcontractors, contractor's work force, and government personnel or agency performing a given task. Activities shall not belong to more than one responsible party. The responsible party for each activity shall be identified by a designated Responsibility Code.

3.3.5 Work Areas

All activities shall be identified in the project schedule by the work area in which the activity occurs. Activities shall not be allowed to cover more than one work area. The work area of each activity shall be identified by a designated Work Area Code.

3.3.6 Constraint of Last Activity

Completion of the last activity in the schedule shall be constrained by the contract completion date. Calculation on project updates shall be such that if the early finish of the last activity falls after the contract completion date, then the float calculation shall reflect a negative float on the critical path. The Contractor shall include as the last activity in the project schedule an activity called "End Project". The "End Project" activity shall have an "LF" constraint date equal to the completion date for the project, and a zero day duration.

3.3.7 Standard Activity Coding Dictionary

The Contractor shall use the activity coding structure defined in the Standard Data Exchange Format (SDEF) in ER 1-1-11, Appendix A. This exact structure is mandatory, even if some fields are not used.

3.4 UPDATED SCHEDULES

Update of the Progress Schedule shall be at weekly intervals or when the construction schedule has been revised. Reflect any changes occurring since the last update and certify by signature of the Contractor's Quality Control Officer and submit to the Contracting Officer as specified.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01330

SUBMITTAL PROCEDURES

01/05

PART 1 GENERAL

1.1 SUBMITTAL IDENTIFICATION AND CLASSIFICATION
1.1.1 Submittal Identification
1.1.2 Submittal Classification
1.2 APPROVAL OF SUBMITTALS
1.3 DISAPPROVED SUBMITTALS
1.4 WITHHOLDING OF PAYMENT

PART 2 PRODUCT

PART 3 EXECUTION

3.1 GENERAL
3.2 SCHEDULING
3.2.1 Submittal and Report Identification
3.3 SUBMITTAL REGISTER (ENG FORM 4288)
3.4 TRANSMITTAL FORM (ENG FORM 4025)

-- End of Section Table of Contents --

SECTION 01330

SUBMITTAL PROCEDURES
01/05

PART 1 GENERAL

1.1 SUBMITTAL IDENTIFICATION AND CLASSIFICATION

The Contractor shall insure all submittals as required in the Contract are submitted to the government as identified and in accordance with the procedures specified in this Section. Submittals may be required for work features and procedures in the specifications that are not listed or classified as indicated below. The Contractor shall still be required to list these submittals in his Submittal Register as required by the respective specification, and designate the submittal and action required in the register.

1.1.1 Submittal Identification

Submittals required are identified by SD numbers and titles with typical items to be submitted under this classification as follows:

SD-01 Preconstruction Submittals

Certificates of Insurance
List of Proposed Subcontractors
List of Proposed Products
Construction Progress Schedule
Submittal Register
Schedule of Values
Health and Safety Plan
Activity Hazard Analysis
Quality Control Plan
Environmental Protection Plan

SD-02 Shop Drawings

As used in this section, drawings, schedules, diagrams, and other data prepared specifically for this contract, by Contractor or through Contractor by way of subcontractor, manufacturer, supplier, distributor, or other lower tier contractor, to illustrate portion of work.

SD-03 Product Data

Preprinted material such as illustrations, standard schedules, performance charts, instructions, brochures, diagrams, manufacturer's descriptive literature, catalog data, and other data to illustrate portion of work, but not prepared exclusively

for this contract.

SD-04 Samples

Physical examples of products, materials, equipment, assemblies, or workmanship that are physically identical to portion of work, illustrating portion of work or establishing standards for evaluating appearance of finished work or both.

SD-05 Design Data

Placement plan with proposed equipment usage and datum used and benchmark locations.

SD-06 Test Reports

Report signed by authorized official of testing laboratory that a material, product or system identical to the material, product or system to be provided has been tested in accord with specified requirements.

Results of environmental testing.

Report which includes findings of a test required to be performed by the contractor on an actual portion of the work or prototype prepared for the project before shipment to job site.

Report which includes finding of a test made at the job site or on sample taken from the job site, on portion of work during or after installation.

Investigation reports.

Daily checklists.

Final acceptance test and operational test procedure.

SD-07 Certificates

Statements signed by responsible officials of manufacturer of product, system or material attesting that product, system or material meets specification requirements. Must be dated after award of project contract and clearly name the project.

Document required of Contractor, or of a supplier, installer or subcontractor through Contractor, the purpose of which is to further quality of orderly progression of a portion of the work by documenting procedures, acceptability of methods or personnel qualifications.

SD-08 Manufacturer's Instructions

Preprinted material describing installation of a product, system or material, including special notices and Material Safety Data

sheets concerning impedances, hazards and safety precautions.

SD-09 Manufacturer's Field Reports

Documentation of the testing and verification actions taken by manufacturer's representative to confirm compliance with manufacturer's standards or instructions.

Factory test reports.

SD-10 Closeout Submittals

Placement area profiles and surveys.

1.1.2 Submittal Classification

Submittals are classified as follows:

a. Government Approved

Government approval is required for extensions of design, critical materials, deviations, equipment whose compatibility with the entire system must be checked, and other items as designated by the Contracting Officer. Within the terms of the Contract Clause entitled "Specifications and Drawings for Construction," they are considered to be "shop drawings."

b. Information Only

All submittals not requiring Government approval will be for information only. They are not considered to be "shop drawings" within the terms of the Contract Clause referred to above.

1.2 APPROVAL OF SUBMITTALS

The approval of submittals by the Contracting Officer's Representative (COR), shall not be construed as a complete check, but will indicate only that the general method of construction, work scheduling, and other information are satisfactory. Approval will not relieve the Contractor of the responsibility for any error which may exist, as the Contractor under the Contractor Quality Control (CQC) requirements of this contract is responsible for the dimensions, layout, and satisfactory construction of all work as indicated and specified. After submittals have been approved by the COR, resubmittal for the purpose of changing the approved Work Plan, Progress Schedule, designated Acceptance Sections, or for any other reason, will not be given consideration unless accompanied by an explanation as to why a change is necessary.

1.3 DISAPPROVED SUBMITTALS

The Contractor shall make all corrections required by the COR and promptly furnish a corrected submittal with the Daily CQC Report as specified for the initial submittal. If the Contractor considers any correction indicated on the submittal(s) to constitute a change to the contract,

notice as required under the Contract Clause entitled "Changes" shall be given at the same time to the COR.

1.4 WITHHOLDING OF PAYMENT

Payment for any part of the scheduled work accomplished by the Contractor, including transportation of the Contractor's plant to or from the site of the work, will not be made if required approvals for all parts of the scheduled work have not been obtained.

PART 2 PRODUCT (Not Used)

PART 3 EXECUTION

3.1 GENERAL

The Contractor shall submit all items required and specified in these specifications, and as may be required by other portions of the scheduled work. Proposed deviations from the contract requirements shall be clearly identified. The required submittals shall be listed in the Contractor's Work Plan and on the Contractor's Submittal Register Form 4288-R. All requirements of submittals shall be coordinated with SECTION 01451. Any questions regarding submittals required of the Contractor will be discussed at the Preconstruction Conference specified in SECTION 01006. At this Conference, and during the progress of the work, the COR may request submittals in addition to those listed when deemed necessary to adequately describe the work covered in the respective sections. Dimensions and units of weights and measures used on all submittals shall be the same as indicated and specified. Each submittal shall be complete and in sufficient detail to allow ready determination of compliance with contract requirements. Prior to submittal, all items shall be checked and approved as complete by the CQC representative as specified in SECTION 01451.

3.2 SCHEDULING

Submittals covering component items forming a system or items that are interrelated, such as access/egress to the work area, and delivery/storage of materials prior to construction of features shall be scheduled to be coordinated with the requirements specified and submitted concurrently.

3.2.1 Submittal and Report Identification

All submittals and reports shall be complete, properly marked, adequately detailed, and identified with location of occurrence in the respective specification section with paragraph number, drawing number and location, and respective Plan or Report requirement, as applicable. The Contractor's CQC representative shall sign and date each submittal and report as complete.

3.3 SUBMITTAL REGISTER (ENG FORM 4288)

At the end of this SECTION is a sample Submittal Register (ENG Form 4288-R) showing those plans, lists, and items of equipment and materials for which submittals are required by the specifications. The Contractor is informed

this sample form may not list all submittals that may be required of the Contractor; however, the Contractor shall utilize this form as a guide to provide, with his CQC Plan for approval, a complete Submittal Register listing all submittals required for the duration of the contract. The Submittal Register shall consist of individual pages representing the respective Specification Sections as shown in the attached sample. Columns "d" through "q" of the sample form indicate the method the Contractor is to use in identification of his submittals. In the respective Specification Sections and when so directed by specified requirements in other parts of the contract for a particular type of submittal, the Classification status to be inserted in Columns "p" and "q" is indicated. The Contractor's Quality Control Representative shall certify in writing as part of the CQC Plan the appropriate designation for all submittals has been made. The remainder of columns and how they are to be utilized during administration of the contract will be addressed at the Pre-Construction Conference as noted in SECTION 01006.

3.4 TRANSMITTAL FORM (ENG FORM 4025)

At the end of this SECTION is a sample Transmittal Form (ENG Form 4025) which shall be used for transmittal coordination of all submittals. This form shall be completed by the Contractor identifying each item to be submitted. Special care shall be exercised to ensure proper listing of the date of the submittal transmittal, specification section and paragraph number pertinent to the data submitted for each item, and numerical sequence coordination with the Submittal Register Form 4288-R, Column "b".

-- End of Section --

Instructions For Completing ENG FORM 4025-R, Mar 95

A. Enter date the submittal is issued.

B. Enter the Transmittal Number under which the submittal was made.

The Transmittal Number shall have the following format:

A-B.C

Where: A is the specification section

B is a consecutive number where 1 would be the first transmittal under the given specification section, 2 would be the second transmittal, etc.

C is a consecutive number identifying resubmittals. Number 1 would be the first resubmittal, 2 the second, etc.

Examples of Transmittal Numbers under Specification Section 01451:

01451-1
01451-2
01451-1.1 (first resubmittal of 01451-1)
01451-3

C. Enter name and address of Corps of Engineers reviewing office.

D. Enter name and address of Contractor.

E. Enter contract number.

F. If this is the first submittal of information for this item number, check the box for "New Submittal". If not, check the box for "Resubmittal".

G. If the "Resubmittal" box is checked, enter the previous Transmittal No.

H. Enter the specification section that applies to this Transmittal Form. A separate Transmittal Form shall be used for submittals under separate sections of the specifications.

I. Enter name and location of project.

J. Indicate whether the submittal is "For Information Only (FIO)" or for "Government Approval (Gov't Approval)".

K. Enter the Item No. as identified on the Submittal Register.

L. Enter the Description of the item submitted as identified on the Submittal Register.

M. Enter information as necessary. When a sample of material or Manufacturer's Certificate of Compliance is transmitted, indicate "Sample" or "Certification.

N. Enter the number of copies of submittal data attached.

O. Enter the specification paragraph number as identified on the Submittal Register using the following format:

Spec. Section - Paragraph number

P. Enter information as necessary.

Q. Enter Contractor Action Code. See reverse side of ENG Form 4025 for applicable codes.

R. A check shall be placed in the "Variation" column when a submittal is not in accordance with the plans and specifications. Attach a written statement describing the variation.

S. Review code assigned by the Government reviewer.

T. Remarks from the Contractor or Government review comments. Government review comments may also be placed on a separate sheet of paper.

U. Signature of Contractor reviewer.

V. Number of enclosures being returned to the Contractor by the Government reviewer

W. Signature and title of Government approving authority.

X. Date of review by the Government.

Other: In submitting manufacturer's literature or similar information, the Contractor shall clearly identify the item proposed for use.

TRANSMITTAL OF SHOP DRAWINGS, EQUIPMENT DATA, MATERIAL SAMPLES, OR MANUFACTURER'S CERTIFICATES OF COMPLIANCE *(Read instructions on the reverse side prior to initiating this form)*	DATE 1 Jan 97	TRANSMITTAL NO.

SECTION I - REQUEST FOR APPROVAL OF THE FOLLOWING ITEMS *(This section will be initiated by the contractor)*

TO:	FROM:	CONTRACT NO.	CHECK ONE: ☐ THIS IS A NEW TRANSMITTAL ☐ THIS IS A RESUBMITTAL OF TRANSMITTAL _____
SPECIFICATION SEC. NO. *(Cover only one section with each transmittal)*	PROJECT TITLE AND LOCATION		

ITEM NO. a	DESCRIPTION OF ITEM SUBMITTED *(Type size, model number/etc.)* b	MFG OR CONTR. CAT., CURVE DRAWING OR BROCHURE NO. *(See instruction no. 8)* c	NO. OF COPIES d	CONTRACT REFERENCE DOCUMENT: SPEC. PARA. NO. e	CONTRACT REFERENCE DOCUMENT: DRAWING SHEET NO. f	FOR CONTRACTOR USE CODE g	VARIATION f	

REMARKS

I certify that the above submitted items have been reviewed in detail and are correct and in strict conformance with the contract drawings and specifications except as otherwise stated.

_____
NAME AND SIGNATURE OF CONTRACTOR

SECTION II - APPROVAL ACTION

ENCLOSURES RETURNED *(List by Item No.)*	NAME, TITLE AND SIGNATURE OF APPROVING AUTHORITY	DATE

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
Maintenance Dredging and Realignment Lynnhaven

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	CONTRACTOR ACTION ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	APPROVING AUTHORITY DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		01140	SD-06 Test Reports															
			Effluent Measurements															
		01150	SD-01 Preconstruction Submittals															
			Dredging Intent Notifications to															
			Department of Environmental															
			Quality, Virginia Marine Resources															
			Commission and U.S. Coast															
			Guard															
			Advance Notice for Dredging	1.4.4														
			After Dredging Survey Requests															
		01320	SD-01 Preconstruction Submittals															
			Progress Schedule		G													
		01355	SD-01 Preconstruction Submittals															
			Environmental Protection Plan		G													
		01451	SD-01 Preconstruction Submittals															
			Quality Control Plan	3.2.1	G													
			SD-11 Closeout Submittals															
			Daily Quality Control Reports	3.7														
		01525	SD-01 Preconstruction Submittals															
			Accident Prevention Plan (APP)	1.8														
			Activity Hazard Analysis (AHA)	1.9														
			SD-06 Test Reports															
			Reports	1.13														
			Accident Reports	1.13.1														
			Monthly Exposure Reports															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
Maintenance Dredging and Realignment Lynnhaven

CONTRACTOR

ACTIVITY NO (a)	TRANSMITTAL NO (b)	SPEC SECT (c)	DESCRIPTION ITEM SUBMITTED (d)	PARAGRAPH # (e)	CLASSIFICATION (f)	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES SUBMIT (g)	APPROVAL NEEDED BY (h)	MATERIAL NEEDED BY (i)	CONTRACTOR ACTION CODE (j)	DATE OF ACTION (k)	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR (l)	APPROVING AUTHORITY DATE FWD TO OTHER REVIEWER (m)	DATE RCD FROM OTH REVIEWER (n)	ACTION CODE (o)	DATE OF ACTION (p)	MAILED TO CONTR/ DATE RCD FRM APPR AUTH (q)	REMARKS (r)
		01525	Regulatory Citations and Violations	1.13.4														
		02325	SD-07 Certificates Equipment and Machinery Operator Authorization															

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01355

ENVIRONMENTAL PROTECTION

12/04

PART 1 GENERAL

1.1 REFERENCES
1.2 DEFINITIONS
1.2.1 Environmental Pollution and Damage
1.2.2 Environmental Protection
1.2.3 Contractor Generated Hazardous Waste
1.2.4 Waters of the United States
1.2.5 Wetlands
1.3 GENERAL REQUIREMENTS
1.4 SUBCONTRACTORS
1.5 PAYMENT
1.6 SUBMITTALS
1.7 ENVIRONMENTAL PROTECTION PLAN REQUIREMENTS
1.7.1 Contents of Environmental Protection Plan
1.8 ENVIRONMENTAL ASSESSMENT OF CONTRACT DEVIATIONS
1.9 NON-COMPLIANCE NOTIFICATION

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION

3.1 PROTECTION OF FEATURES
3.2 LAND RESOURCES
3.3 WATER RESOURCES
3.4 PROTECTION OF MARINE ANIMALS, WILDLIFE AND VEGETATION
3.5 U.S. DEPARTMENT OF AGRICULTURE (USDA) QUARANTINED CONSIDERATIONS
3.6 WETLANDS AND NATURAL HABITAT
3.7 POST CONSTRUCTION CLEANUP

-- End of Section Table of Contents --

SECTION 01355

ENVIRONMENTAL PROTECTION
12/04

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

33 CFR 328	Definitions
40 CFR 68	Chemical Accident Prevention Provisions
40 CFR 302	Designation, Reportable Quantities, and Notification
40 CFR 355	Emergency Planning and Notification

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2003) U.S. Army Corps on Engineers Safety and Health Requirements Manual
WETLAND MANUAL	Corps of Engineers Wetlands Delineation Manual Technical Report Y-87-1

1.2 DEFINITIONS

Environmental pollution and damage is defined as the presence of chemical, physical, or biological elements or agents that adversely affect human health or welfare; unfavorably alter ecological balances of plant or animal communities; or degrade the environment from an aesthetic, cultural or historic perspective.

1.2.1 Environmental Pollution and Damage

Environmental pollution and damage is the presence of chemical, physical, or biological elements or agents which adversely affect human health or welfare; unfavorably alter ecological balances of importance to human life; affect other species of importance to humankind; or degrade the environment aesthetically, culturally, or historically.

1.2.2 Environmental Protection

Environmental protection is the prevention and control of pollution and habitat disruption that may occur to the environment during construction. The control of environmental pollution and damage requires consideration of land, water, and air; biological and cultural resources; and includes management of visual aesthetics; noise; solid, chemical, gaseous, and liquid waste; radiant energy and radioactive material as well as other pollutants.

1.2.3 Contractor Generated Hazardous Waste

Contractor generated hazardous waste means materials that, if abandoned or disposed of, may meet the definition of a hazardous waste. These waste streams would typically consist of material brought on site by the Contractor to execute work, but are not fully consumed during the course of construction. Examples include, but are not limited to, excess paint thinners (i.e. methyl ethyl ketone, toluene), waste thinners, excess paints, excess solvents, waste solvents, excess pesticides, and contaminated pesticide equipment rinse water.

1.2.4 Waters of the United States

All waters which are under the jurisdiction of the Clean Water Act, as defined in 33 CFR 328.

1.2.5 Wetlands

Wetlands means those areas that are inundated or saturated by surface or ground water at a frequency and duration sufficient to support, and that under normal circumstances do support, a prevalence of vegetation typically adapted for life in saturated soil conditions. Wetlands generally include swamps, marshes, and bogs. Official determination of whether or not an area is classified as a wetland must be done in accordance with WETLAND MANUAL.

1.3 GENERAL REQUIREMENTS

The Contractor shall minimize environmental pollution and damage that may occur as the result of construction operations. The environmental resources within the project boundaries and those affected outside the limits of permanent work shall be protected during the entire duration of this contract. The Contractor shall comply with all applicable Federal, State, and local laws and regulations. The Contractor shall provide environmental protective measures and procedures to prevent and control pollution, limit habitat disruption, and correct environmental damage that occurs during construction. The Contractor shall be responsible for any delays resulting from failure to comply with environmental laws and regulations.

1.4 SUBCONTRACTORS

The Contractor shall ensure compliance with this SECTION by subcontractors.

1.5 PAYMENT

No separate payment will be made for work covered under this SECTION. The Contractor shall be responsible for payment of fees associated with environmental permits, application, and notices obtained by the Contractor. All costs associated with this SECTION shall be included in the contract price. The Contractor shall be responsible for payment of all fines and fees for violation or non-compliance with Federal, State, Regional and local laws and regulations.

1.6 SUBMITTALS

The Contractor shall make submittals for the following listed reports and certificates as required by the specifications. The Contracting Officer may request submittals in addition to those specified when deemed necessary to adequately describe the work. Units of weights and measures used on all submittals shall be the same as those used in the contract drawings. Each submittal shall be complete and in sufficient detail to allow ready determination of compliance with contract requirements. Prior to submittal, all items shall be checked and approved by the Contractor's Quality Control (CQC) representative and each item shall be stamped, signed, and dated by the CQC representative indicating action taken in accordance with SECTION 01451. Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Environmental Protection Plan; G

Prior to commencement of any work, including delivery of any plant, equipment or construction materials to the site, submit a plan for environmental protection as specified herein.

The paragraph "ENVIRONMENTAL PROTECTION PLAN REQUIREMENTS" below lists personnel requirements and plans to be submitted by the Contractor as a part of the Environmental Protection Plan. Although these requirements are listed as individual Plans and personnel requirements that are a part of the contents of the Environmental Protection Plan, all listed individual Plans and personnel requirements must be submitted with the entire Environmental Protection Plan for approval.

1.7 ENVIRONMENTAL PROTECTION PLAN REQUIREMENTS

The Contractor shall submit an Environmental Protection Plan for review and approval by the Contracting Officer. This Environmental Protection Plan shall consist of a written narrative, as well as any individual plans, supplemental drawings, documents, and photographs required to verify the Contractor's work will be in accordance with the environmental permits and all laws and regulations governing the work as indicated and specified. The Contractor shall submit this plan and all supplementary data for approval

at least 10 calendar days prior to the scheduled Preconstruction Conference. The Contractor will be informed in writing of any revisions as may be required by the Contracting Officer at the Preconstruction Conference and shall submit a final plan for final approval not later than 5 calendar days prior to start of scheduled construction activities. Acceptance is conditional and is predicated upon satisfactory performance during construction. The Government reserves the right to require the Contractor to make changes in the Environmental Protection Plan or operations if the Contracting Officer determines that environmental protection requirements are not being met. The plan shall detail the actions that the Contractor shall take to comply with all applicable Federal, State, and local laws and regulations concerning environmental protection and pollution control and abatement, as well as the additional specific requirements of this contract. No physical work at the site, including delivery of the Contractor's plant and equipment and construction materials, shall begin prior to acceptance by the Contracting Officer of the Contractor's Environmental Protection Plan covering the work to be performed. No requirement in this Section shall be construed as relieving the Contractor of any applicable Federal, State, and local environmental protection laws and regulations. During Construction, the Contractor shall be responsible for identifying, implementing, and submitting for approval any additional requirements to be included in the Environmental Protection Plan.

1.7.1 Contents of Environmental Protection Plan

The purpose of the Environmental Protection Plan is to present a comprehensive overview of known or potential environmental issues which the Contractor must address during construction. Issues of concern shall be defined within the Environmental Protection Plan as outlined in this section. The Contractor shall address each topic at a level of detail commensurate with the environmental issue and required construction task(s). Topics or issues which are not identified in this SECTION, but which the Contractor considers necessary, shall be identified and discussed after those items formally identified in this SECTION. The Environmental Protection Plan shall be current and maintained onsite by the Contractor. The Environmental Protection Plan shall comply with the requirements of EM 385-1-1 and include, but not be limited to, the following:

a. Name(s) of person(s) within the Contractor's organization who is(are) responsible for ensuring adherence to the Environmental Protection Plan and those who may be delegated with separate responsibilities subject to approval of the CO.

b. Name(s) and qualifications of person(s) responsible for manifesting hazardous waste to be removed from the site, if applicable.

c. Name(s) and qualifications of person(s) responsible for training the Contractor's environmental protection personnel.

d. Description of the Contractor's environmental protection personnel training program.

e. The Spill Control plan shall include the procedures, instructions,

and reports to be used in the event of an unforeseen spill of a substance regulated by 40 CFR 68, 40 CFR 302, 40 CFR 355, or regulated under State or Local laws and regulations. The Spill Control Plan supplements the requirements of EM 385-1-1. This plan shall include as a minimum:

1. The name of the individual who will report any spills or hazardous substance releases and who will follow up with complete documentation. This individual shall immediately notify the Contracting Officer in addition to the legally required Federal, State, and local reporting channels (including the National Response Center 1-800-424-8802) if a reportable quantity is released to the environment. The plan shall contain a list of the required reporting channels and telephone numbers.

2. The name and qualifications of the individual who will be responsible for implementing and supervising the containment and cleanup.

3. Training requirements for Contractor's personnel and methods of accomplishing the training.

4. A list of materials and equipment to be immediately available at the job site, tailored to cleanup work of the potential hazard(s) identified.

5. The names and locations of suppliers of containment materials and locations of additional fuel oil recovery, cleanup, restoration, and material-placement equipment available in case of an unforeseen spill emergency.

6. The methods and procedures to be used for expeditious contaminant cleanup.

f. A non-hazardous solid waste disposal plan identifying methods and locations for solid waste disposal including clearing debris. The plan shall include schedules for disposal. The Contractor shall identify any subcontractors responsible for the transportation and disposal of solid waste. Licenses or permits shall be submitted for solid waste disposal sites that are not a commercial operating facility. Evidence of the disposal facility's acceptance of the solid waste shall be attached to this plan during the construction.

g. A recycling and solid waste minimization plan with a list of measures to reduce consumption of energy and natural resources. The plan shall detail the Contractor's actions to comply with and to participate in Federal, State, Regional, and local government sponsored recycling programs to reduce the volume of solid waste at the source.

h. An air pollution control plan detailing provisions to assure that dust, debris, materials, trash, etc., do not become air borne and travel off the project site.

i. A contaminant prevention plan that: identifies potentially

hazardous substances to be used on the job site; identifies the intended actions to prevent introduction of such materials into the air, water, or ground; and details provisions for compliance with Federal, State, and local laws and regulations for storage and handling of these materials. In accordance with EM 385-1-1, a copy of the Material Safety Data Sheets (MSDS) and the maximum quantity of each hazardous material to be on site at any given time shall be included in the contaminant prevention plan. As new hazardous materials are brought on site or removed from the site, the plan shall be updated.

1.8 ENVIRONMENTAL ASSESSMENT OF CONTRACT DEVIATIONS

Any deviations, requested by the Contractor, from the drawings, plans and specifications which may have an environmental impact will be subject to approval by the Contracting Officer and may require an extended review, processing, and approval time. The Contracting Officer reserves the right to disapprove alternate methods, even if they are more cost effective, if the Contracting Officer determines that the proposed alternate method will have an adverse environmental impact.

1.9 NON-COMPLIANCE NOTIFICATION

The Contracting Officer will notify the Contractor in writing of any observed noncompliance with Federal, State or local environmental laws or regulations, permits, and other elements of the Contractor's Environmental Protection plan. The Contractor shall, after receipt of such notice, inform the Contracting Officer of the proposed corrective action and take such action when approved by the Contracting Officer. The Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No time extensions shall be granted or equitable adjustments allowed to the Contractor for any such suspensions. This is in addition to any other actions the Contracting Officer may take under the contract, or in accordance with the Federal Acquisition Regulation or Federal Law.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION

3.1 PROTECTION OF FEATURES

This SECTION supplements the CONTRACT CLAUSE "PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS". The Contractor shall prepare a list of features requiring protection under the provisions of the CONTRACT CLAUSE that are not specifically identified on the drawings or otherwise specified as environmental features requiring protection. The Contractor shall protect those environmental features as indicated and specified, in spite of interference that their preservation may cause to the Contractor's work under the contract.

3.2 LAND RESOURCES

The Contractor shall confine all activities to areas defined by the drawings and specifications. Prior to the beginning of any construction,

the Contractor shall identify any land resources to be preserved within the work area. Except in areas indicated on the drawings or specified to be dredged, the Contractor shall not remove, cut, deface, injure, or destroy land resources including trees, shrubs, vines, grasses, topsoil, and land forms without approval. No ropes, cables, or guys shall be fastened to or attached to any trees for anchorage unless specifically authorized. The Contractor shall provide effective protection for land and vegetation resources at all times as defined in the following subparagraphs. Stone, soil, or other materials displaced into uncleared areas shall be removed by the Contractor.

3.3 WATER RESOURCES

The Contractor shall monitor construction activities to prevent pollution of surface and ground waters. Toxic or hazardous chemicals shall not be applied to soil or vegetation. All water areas affected by construction activities shall be monitored by the Contractor. The Contractor shall perform monitoring, inspections, sampling and testing, reporting, and record keeping as indicated and specified.

3.4 PROTECTION OF MARINE ANIMALS, WILDLIFE AND VEGETATION

The Contractor is informed that the work areas are in a portion of Virginia frequented by migratory birds and is a native habitat for eagles, hawks, egrets, herons, pelicans, terns, and other wildlife that are identified as either endangered species protected by federal law or species of special concern for Commonwealth of Virginia agencies. If, in the performance of this contract, evidence of the possible disturbance to any such migratory bird or listed species may occur, the Contractor shall notify the Contracting Officer immediately, giving the location and nature of the findings. The Contractor shall advise all personnel associated with the operation of the vessels and plant of the civil and criminal provisions of the Endangered Species Act (ESA), the Migratory Bird Act, and the Marine Mammal Protection Act (MMPA). In the event that endangered or protected species are affected by this work, the work under this contract may be suspended or terminated as determined by the Contracting Officer. All crew members of the dredge, attendant plant operators, and those sub-contractors employed on the work shall be required to read and certify in writing they are aware of the contents of this specification and the Contractor's Environmental Protection Plan. Copies of this SECTION and the Environmental Protection Plan, including a posting warning of the civil and criminal liabilities that violators are subject to for non-compliance to the requirements of them, shall be clearly posted with other required postings on-site for employees.

3.5 U.S. DEPARTMENT OF AGRICULTURE (USDA) QUARANTINED CONSIDERATIONS

The Contractor shall thoroughly clean all construction equipment at the prior job site in a manner that ensures all residual soil is removed and that egg deposits from plant pests are not present. The Contractor shall consult with the USDA Plant Protection and Quarantine (USDA - PPQ) jurisdictional office for additional cleaning requirements that may be necessary.

3.6 WETLANDS AND NATURAL HABITAT

Use of the Contractor's plant to construct the scheduled work, including the associated use of ropes, cables, or guys over wetlands and in natural habitat areas, shall be scheduled in a manner to disturb the wetlands and natural habitat areas to the minimum necessary to accomplish the work. Any damage to wetlands or natural habitat areas shall be repaired to original condition at no additional expense to the government. The Contracting Officer will notify the Contractor in writing of any observed noncompliance with the previously mentioned Federal, State or local laws or regulations, permits, and other elements of the Contractor's environmental protection plan. The Contractor shall, after receipt of such notice, inform the Contracting Officer of proposed corrective action and take such action when approved. If the Contractor fails to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No time extensions shall be granted or costs or damages allowed to the Contractor for any such suspensions.

3.7 POST CONSTRUCTION CLEANUP

The Contractor shall clean up all areas used for construction in accordance with Contract Clause: "Cleaning Up". The Contractor shall, unless otherwise instructed in writing by the Contracting Officer, obliterate all signs of temporary construction facilities such as haul roads, work area, structures, foundations of temporary structures, stockpiles of excess or waste materials, and other vestiges of construction prior to final acceptance of the work. The disturbed land area shall be graded, filled and the entire area seeded unless otherwise indicated.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01420

SOURCES FOR REFERENCE PUBLICATIONS

12/04

PART 1 GENERAL

1.1 REFERENCES
1.2 ORDERING INFORMATION

-- End of Section Table of Contents --

SECTION 01420

SOURCES FOR REFERENCE PUBLICATIONS
12/04

PART 1 GENERAL

1.1 REFERENCES

Various publications are referenced in other sections of the specifications to establish requirements for the work. These references are identified in each section by document number, date and title. The document number used in the citation is the number assigned by the standards producing organization, (e.g. ASTM B 564 Nickel Alloy Forgings). However, when the standards producing organization has not assigned a number to a document, an identifying number has been assigned for reference purposes.

1.2 ORDERING INFORMATION

The addresses of the standards publishing organizations whose documents are referenced in other sections of these specifications are listed below, and if the source of the publications is different from the address of the sponsoring organization, that information is also provided. Documents listed in the specifications with numbers which were not assigned by the standards producing organization should be ordered from the source by title rather than by number.

ASME INTERNATIONAL (ASME)
Three Park Avenue
New York, NY 10016-5990
Ph: 212-591-7722
Fax: 212-591-7674
E-mail: infocentral@asme.org
Internet: http://www.asme.org

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)
1 Batterymarch Park
Quincy, MA 02169-7471
Ph: 617-770-3000
Fax: 617-770-0700
E-mail: webmaster@nfpa.org
Internet: http://www.nfpa.org

U.S. ARMY CORPS OF ENGINEERS (USACE)
Order CRD-C DOCUMENTS from:
U.S. Army Engineer Waterways Experiment Station
ATTN: Technical Report Distribution Section, Services Branch, TIC
3909 Halls Ferry Road
Vicksburg, MS 39180-6199

Ph: 601-634-2664
Fax: 601-634-2388
E-mail: mtc-info@erdc.usace.army.mil
Internet: http://www.wes.army.mil/SL/MTC/handbook.htm

Order Other Documents from:
USACE Publications Depot
Attn: CEIM-IM-PD
2803 52nd Avenue
Hyattsville, MD 20781-1102
Ph: 301-394-0081
Fax: 301-394-0084
E-mail: pubs-army@usace.army.mil
Internet: http://www.usace.army.mil/publications
or http://www.hnd.usace.army.mil/techinfo/engpubs.htm

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)
8601 Adelphi Road
College Park, MD 20740-6001
Ph: 866-272-6272
Fax: 301-837-0483
Internet: http://www.archives.gov

Order documents from:
Superintendent of Documents
U.S.Government Printing Office (GPO)
732 North Capitol Street, NW
Washington, DC 20401
Ph: 888-293-6498 or 202-512-1530
Fax: 202-512-1262
E-mail: gpoaccess.gov
Internet: http://www.gpoaccess.gov

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01451

CONTRACTOR QUALITY CONTROL

12/04

PART 1 GENERAL

1.1 PAYMENT
1.2 SUBMITTALS

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS
3.2 QUALITY CONTROL PLAN
3.2.1 General
3.2.2 Acceptance of Plan
3.2.3 Notification of Changes
3.3 COORDINATION MEETING
3.4 QUALITY CONTROL ORGANIZATION
3.4.1 Personnel Requirements
3.4.2 CQC System Manager
3.4.3 Additional Requirement
3.4.4 Organizational Changes
3.5 SUBMITTALS AND DELIVERABLES
3.6 CONTRACTOR QUALITY CONTROL (CQC)
3.6.1 Preparatory Phase
3.6.2 Initial Phase
3.6.3 Follow-up Phase
3.6.4 Additional Preparatory and Initial Phases
3.7 DOCUMENTATION
3.8 SAMPLE FORMS
3.9 NON-COMPLIANCE NOTIFICATION

-- End of Section Table of Contents --

SECTION 01451

CONTRACTOR QUALITY CONTROL
12/04

PART 1 GENERAL

1.1 PAYMENT

Separate payment will not be made for providing and maintaining an effective Quality Control program, and all costs associated therewith shall be included in the applicable unit prices or lump-sum prices contained in the Bidding Schedule.

1.2 SUBMITTALS

The Contractor shall make submittals for the following listed reports and certificates as required by the specifications. The Contracting Officer may request submittals in addition to those specified when deemed necessary to adequately describe the work. Units of weights and measures used on all submittals shall be the same as those used in the contract drawings. Each submittal shall be complete and in sufficient detail to allow ready determination of compliance with contract requirements. Prior to submittal, all items shall be checked and approved by the Contractor's Quality Control (CQC) representative and each item shall be stamped, signed, and dated by the CQC representative indicating action taken in accordance with SECTION 01451. Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-01 Preconstruction and Postconstruction Submittals

Quality Control Plan; G

Prior to commencement of dredging, submit a copy of Quality Control Plan to Contracting Officer indicating plans, procedures, and organization necessary to produce an end product that complies with the contract requirements.

SD-11 Closeout Submittals

Daily Quality Control Reports

Daily quality control reports including preparatory and initial phase minutes shall be submitted on a daily basis as specified in paragraph "DOCUMENTATION".

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

The Contractor is responsible for quality control and shall establish and maintain an effective quality control system in compliance with the Contract Clause titled "Inspection of Construction." The quality control system shall consist of plans, procedures, and organization necessary to produce an end product that complies with the contract requirements. The system shall cover all construction operations, both onsite and offsite, and shall be keyed to the proposed construction sequence.

3.2 QUALITY CONTROL PLAN

3.2.1 General

Prior to start of the scheduled work operations, the Contractor shall furnish his Quality Control Plan to the COR for acceptance. The CQC Plan the Contractor proposes to implement shall identify the personnel, procedures, instructions, records, and forms, and, as a minimum, shall include:

a. A description of the quality control organization, including a chart showing lines of authority by name with duties and responsibilities of their respective position, qualifications (in resume format), and acknowledgment that the CQC staff shall implement the three phase control system for all aspects of the work specified.

b. The number, classifications, qualifications, duties, responsibilities and authorities of personnel. A copy of the letter, signed by an authorized official of the firm, which describes the responsibilities and delegates the sufficient authorities to adequately perform the functions of the CQC System Manager, including authority to stop work which is not in compliance with the contract. The CQC System Manager shall issue letters of direction to all other various quality control representatives outlining duties, authorities and responsibilities, and shall furnish copies to the Government at the same time.

c. Control, verification and acceptance testing procedures for each specific test to include the test name, specification paragraph requiring test, feature of work to be tested, test frequency, and person or laboratory responsible for each test (laboratory facilities will be approved by the CO).

d. Procedures for scheduling, reviewing, certifying, and managing submittals, including those of subcontractors, offsite fabricators, suppliers, and purchasing agents. These procedures shall be in accordance with Section 01330 SUBMITTAL PROCEDURES.

e. Procedures for tracking preparatory, initial, and follow-up control phases and control, verification, and acceptance tests including documentation.

f. Procedures for tracking construction deficiencies from identification through acceptable corrective action. These procedures shall establish verification that identified deficiencies have been corrected.

g. Reporting procedures, including proposed reporting formats.

h. A list of the definable features of work. A definable feature of work is a task which is separate and distinct from other tasks, has separate control requirements, and may be identified by different trades or disciplines, or it may be work by the same trade in a different environment. Although each section of the specifications may generally be considered as a definable feature of work, there are frequently more than one definable feature under a particular section. This list will be agreed upon during the coordination meeting.

3.2.2 Acceptance of Plan

Acceptance of the Contractor's plan is required prior to the start of construction. Acceptance is conditional and will be predicated on satisfactory performance during the construction. The Government reserves the right to require the Contractor to make changes in his CQC Plan and operations including removal of personnel, as necessary, to obtain the quality specified.

3.2.3 Notification of Changes

After acceptance of the CQC Plan, the Contractor shall notify the Contracting Officer in writing of any proposed change. Proposed changes are subject to acceptance by the Contracting Officer.

3.3 COORDINATION MEETING

As soon as practicable after receipt of Notice to Proceed (NTP) and before start of the scheduled work, and prior to acceptance by the Government of the CQC Plan, the Contractor shall meet with the Contracting Officer or Authorized Representative and discuss the Contractor's quality control system. The Contractor's Project Manager, Submittals Clerk and Quality Control Manager, Dredge Captain and Plant Operators, and the Surveyor or Engineer to be employed by the Contractor to perform all surveys and layout of the work required of the Contractor shall attend this meeting. The Contractor is encouraged to have an officer of his company and representation from any major subcontractors at the conference. The CQC Plan shall be submitted for review a minimum of 14 calendar days prior to the Coordination Meeting. During the meeting, a mutual understanding of the system details shall be developed, including the forms for recording the CQC operations, control activities, testing, administration of the system for both onsite and offsite work, and the interrelationship of Contractor's Management and control with the Government's Quality Assurance. Minutes of

the meeting shall be prepared by the Government and signed by both the Contractor and the Contracting Officer. The minutes shall become a part of the contract file. There may be occasions when subsequent conferences will be called by either party to reconfirm mutual understandings, to address deficiencies in the CQC system, or clarify procedures which may require corrective action by the Contractor.

3.4 QUALITY CONTROL ORGANIZATION

3.4.1 Personnel Requirements

The requirements for the CQC organization are a CQC System Manager and sufficient number of additional qualified personnel to ensure contract compliance. The Contractor shall provide a CQC organization that shall be at the site at all times during progress of the work and with complete authority to take any action necessary to ensure compliance with the contract. All CQC staff members shall be subject to interview and acceptance by the Contracting Officer or his designated representative.

3.4.2 CQC System Manager

The Contractor shall identify as CQC System Manager an individual within the onsite work organization who shall be responsible for overall management of CQC and have the authority to act in all CQC matters for the Contractor. The CQC System Manager will be held responsible for the quality of work on the job and is subject to removal by the Contracting Officer for non-compliance with quality requirements specified in the contract. The CQC System Manager shall be:

a. A graduate engineer, graduate architect, graduate of construction management, or an experienced construction management person with a minimum of five years experience in dredging work similar in magnitude and duration to this contract. This experience shall include work in environments with similar dredging conditions and compliance with environmental requirements in the Commonwealth of Virginia.

This CQC System Manager shall be on the site at all times during construction and shall be employed by the prime Contractor. The CQC System Manager shall be assigned as System Manager but may have duties as project superintendent in addition to quality control. An alternate for the CQC System Manager shall be identified in the plan to serve in the event of the System Manager's absence. The requirements for the alternate shall be the same as for the designated CQC System Manager.

3.4.3 Additional Requirement

In addition, this experience shall include successful completion of Course entitled "Construction Quality Management for Contractors". The Contractor and his designated CQC staff shall have completed this training within 60 calendar days of receipt of his Notice To Proceed. This course is offered periodically by the Corps of Engineers. Specific times and locations are available from the Norfolk District, telephone (757) 441-7723.

3.4.4 Organizational Changes

The Contractor shall maintain the CQC staff at full strength at all times. When it is necessary to make changes to the CQC staff, the Contractor shall revise the CQC Plan to reflect the changes and submit the changes to the Contracting Officer for acceptance.

3.5 SUBMITTALS AND DELIVERABLES

Submittals, if needed, shall be made as specified in Section 01330 SUBMITTAL PROCEDURES. The CQC organization shall be responsible for certifying that all submittals and deliverables are in compliance with the contract requirements.

3.6 CONTRACTOR QUALITY CONTROL (CQC)

Contractor Quality Control is the means by which the Contractor ensures that the construction, to include that of subcontractors and suppliers, complies with the requirements of the contract. At least three phases of control shall be conducted by the CQC System Manager for each definable feature of work as follows:

3.6.1 Preparatory Phase

This phase shall be performed prior to beginning work on each definable feature of work, after all required plans/documents/materials are approved/accepted, and after copies are at the work site. This phase shall include:

a. A review of the paragraphs of applicable specifications, reference codes, and standards. A copy of those sections of referenced codes and standards applicable to that portion of the work to be accomplished in the field shall be made available by the Contractor at the preparatory inspection. These copies shall be maintained in the field and available for use by Government personnel until final acceptance of the work.

b. A review of the contract drawings.

c. A check to assure that all materials and equipment have been tested, submitted, and approved.

d. Review of provisions that have been made to provide required control inspection and testing.

e. Examination of the work area to assure that all required preliminary work has been completed and is in compliance with the contract.

f. A physical examination of required materials, equipment, and sample work to assure that they are on hand, conform to approved shop drawings or submitted data, and are properly stored.

g. A review of the appropriate activity hazard analysis to assure

safety requirements are met.

h. Discussion of procedures for controlling quality of the work including repetitive deficiencies. Document construction tolerances and workmanship standards for that feature of work.

i. A check to ensure that the portion of the plan for the work to be performed has been accepted by the Contracting Officer.

j. Discussion of the initial control phase.

k. The Government shall be notified at least 48 hours, excluding non-workdays, in advance of beginning the preparatory control phase. This phase shall include a meeting conducted by the CQC System Manager and attended by the superintendent, other CQC personnel (as applicable), and the foreman responsible for the definable feature. The results of the preparatory phase actions shall be documented by separate minutes prepared by the CQC System Manager and attached to the daily CQC report. The time and date of the preparatory phase meeting shall be coordinated with the Progress Schedule. The Contractor shall instruct applicable workers as to the acceptable level of workmanship required in order to meet contract specifications.

3.6.2 Initial Phase

This phase shall be accomplished at the beginning of each definable feature of work. The following shall be accomplished:

a. A check of work to ensure that it is in full compliance with contract requirements. Review minutes of the preparatory meeting.

b. Verify adequacy of controls to ensure full contract compliance. Verify required control inspection and testing.

c. Establish level of workmanship and verify that it meets minimum acceptable workmanship standards. Compare with required sample panels as appropriate.

d. Resolve all differences.

e. Check safety to include compliance with and upgrading of the safety plan and activity hazard analysis. Review the activity analysis with each worker.

f. The Government shall be notified at least 24 hours, excluding non-workdays, in advance of beginning the initial phase. Separate minutes of this phase shall be prepared by the CQC System Manager and attached to the daily CQC report. Exact location of initial phase shall be indicated for future reference and comparison with follow-up phases.

g. The initial phase should be repeated for each new crew to work onsite, or any time acceptable specified quality standards are not

being met.

3.6.3 Follow-up Phase

Daily checks shall be performed to assure control activities, including control testing, are providing continued compliance with contract requirements, until completion of the particular feature of work. The checks shall be made a matter of record in the CQC documentation. Final follow-up checks shall be conducted and all deficiencies corrected prior to the start of additional features of work which may be affected by the deficient work. The Contractor shall not build upon nor conceal non-conforming work.

3.6.4 Additional Preparatory and Initial Phases

Additional preparatory and initial phases shall be conducted on the same definable features of work if: the quality of on-going work is unacceptable; if there are changes in the applicable CQC staff, onsite production supervision or work crew; if work on a definable feature is resumed after a substantial period of inactivity; or if other problems develop.

3.7 DOCUMENTATION

The Contractor shall maintain a Daily Quality Control Reports recording a current record providing factual evidence that required quality control activities and tests have been performed. These records shall include the work of subcontractors and suppliers and shall be on an acceptable form that includes, as a minimum, the following information:

a. Contractor/subcontractor and their area of responsibility.

b. Operating plant/equipment with hours worked, idle, or down for repair.

c. Work performed each day, giving location, description, and by whom. When Network Analysis (NAS) is used, identify each phase of work performed each day by NAS activity number.

d. Test and control activities performed with results and references to specifications/drawings requirements. The control phase shall be identified (Preparatory, Initial, Follow-up). List of deficiencies noted, along with corrective action.

e. Quantity of materials received at the site with statement as to acceptability, storage, and reference to specifications/drawings requirements.

f. Offsite surveillance activities, including actions taken.

g. Job safety evaluations stating what was checked, results, and instructions or corrective actions.

h. Instructions given/received and conflicts in plans and/or

specifications.

i. Contractor's verification statement.

These records shall indicate a description of trades working on the project; the number of personnel working; weather conditions encountered; and any delays encountered. These records shall cover both conforming and deficient features and shall include a statement that equipment and materials incorporated in the work and workmanship comply with the contract. The original and one copy of these records in report form shall be furnished to the Government daily within 24 hours after the date covered by the report. All calendar days shall be accounted for throughout the life of the contract. The first report following a day of no work shall be for that day only. Reports shall be signed and dated by the CQC System Manager. The report from the CQC System Manager shall include copies of test reports and copies of reports prepared by all subordinate quality control personnel.

3.8 SAMPLE FORMS

Sample forms for recording of Preparatory and Initial Phase Inspections, Quality Control Reports and Daily Report of Operations - Dredges are included at the end of this SECTION. The Contractor shall utilize these forms as a guide only in the planning and scheduling of his work; however, the actual CQC requirements as specified in this SECTION will be fully implemented by the Government at the Pre-Construction Conference.

3.9 NON-COMPLIANCE NOTIFICATION

The Contracting Officer will notify the Contractor of any detected noncompliance with the foregoing requirements. The Contractor shall take immediate corrective action after receipt of such notice. Such notice, when delivered to the Contractor at the work site, shall be deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders shall be made the subject of claim for extension of time or for excess costs or damages by the Contractor.

-- End of Section --

SAMPLE FORM

PREPARATORY PHASE CHECKLIST

PREPARATORY PHASE CHECKLIST

Date Preparatory Held:_____

Contract No.:_____ Spec. Section & Paragraph_____

Title:_____ Drawing Sheet Numbers_____

MAJOR DEFINABLE FEATURE OF WORK:_____

A. PERSONNEL PRESENT:

NAME	POSITION	COMPANY
1)_____	_____	_____
2)_____	_____	_____
3)_____	_____	_____
4)_____	_____	_____
5)_____	_____	_____
6)_____	_____	_____
7)_____	_____	_____
8)_____	_____	_____
9)_____	_____	_____
10)_____	_____	_____

(List additional personnel on reverse side)

B. Has each specification paragraph, drawing, and permit requirement been studied: YES___ NO___

C. TRANSMITTALS INVOLVED:

NUMBER & ITEM	CODE	CONTRACTOR OR GOVERNMENT APPROVAL
1)_____	_____	_____
2)_____	_____	_____
3)_____	_____	_____
4)_____	_____	_____
5)_____	_____	_____
6)_____	_____	_____

C(1). Have all items involved been approved? YES____ NO____

If NO, list items: _____

_____

D. ARE ALL MATERIALS ON HAND? YES___ NO____

Have all materials been checked for contract compliance against approved shop drawings? YES___ NO____

D(1). Items not on hand or not in accordance with transmittals:

1)_____

2)_____

3)_____

4)_____

E. TESTS REQUIRED IN ACCORDANCE WITH CONTRACT REQUIREMENTS:

TEST	PARAGRAPH
1)_____	_____
2)_____	_____
3)_____	_____
4)_____	_____

F. ACCIDENT PREVENTION PREPLANNING – HAZARD CONTROL MEASURES:

F(1). Applicable Outlines (Attach complete copies):

1)_____

2)_____

3)_____

4)_____

5)_____

6)_____

7)_____

8)_____

F(2). Operational Equipment and Operator Checklists:

FOR EQUIPMENT:

1)_____

2)_____

3)_____

FOR OPERATOR:

1)_____

2)_____

3)_____

G. HAVE PROCEDURES FOR ACCOMPLISHING WORK BEEN REVIEWED WITH APPROPRIATE PEOPLE: YES____ NO___

H. HAS ALL PRELIMINARY WORK BEEN ACCOMPLISHED IN ACCORDANCE WITH CONTRACT REQUIREMENTS AND IS THIS FEATURE OF WORK READY TO START: YES____ NO____

H(1). Explain any problems:_____

_____

_____

_____

_____

_____

_____

_____

_____
QUALITY CONTROL REPRESENTATIVE

SAMPLE FORM

INITIAL PHASE CHECKLIST

INITIAL PHASE CHECKLIST

Contract No.:_____ Date:_____

Spec. Section & Paragraph_____

Description and Location of Work Inspected:_____

_____

REFERENCE CONTRACT DRAWINGS:_____

A. PERSONNEL PRESENT:

NAME	POSITION	COMPANY
1)_____	_____	_____
2)_____	_____	_____
3)_____	_____	_____
4)_____	_____	_____
5)_____	_____	_____
6)_____	_____	_____

B. MATERIALS AND EQUIPMENT BEING USED ARE IN STRICT COMPLIANCE WITH THE CONTRACT: YES____ NO___

If NO, Explain: _____

_____

_____

C. WORKMANSHIP IS ACCEPTABLE: YES____ NO___ STATE AREAS WHERE IMPROVEMENT IS NEEDED: _____

_____

_____

D. SAFETY VIOLATIONS AND CORRECTION ACTION TAKEN:_____

_____

_____

_____

QUALITY CONTROL REPRESENTATIVE

SAMPLE FORM

CONTRACTOR QUALITY CONTROL REPORT

CONTRACTOR QUALITY CONTROL REPORT	REPORT NO.
	DATE
PROJECT/CONTRACT NUMBER	SUPERINTENDENT
CONTRACTOR	WEATHER

PRECIPITATION PAST 24 HOURS(inches) : TEMPERATURE (F): MINIMUM MAXIMUM

WERE THER ANY DELAYS IN WORK PROGRESS TODAY? NO___ YES___
If YES, Explain:

VERBAL INSTRUCTIONS GIVEN BY THE GOVERNMENT:

HAS ANYTHING DEVELOPED WHICH MIGHT LEAD TO A CHANGE ORDER OR CLAIM? NO___ YES___
If YES, Explain:

NOTE: Official notification of claim must be made to the Contracting Officer by separate correspondence.

SAFETY INSPECTION/MEETINGS: Indicate inspections made, items inspected, deficiencies noted and corrective action taken.

WERE THERE ANY LOST TIME ACCIDENTS THIS DATE? NO___ YES ___ If YES, attach accident report.

PRIME CONTRACTOR/SUBCONTRACTOR WORKFORCE
(If space provided below is inadequate, use additional sheets)

No.	TRADE	HOURS	EMPLOYER	No.	TRADE	HOURS	EMPLOYER

CUMULATIVE TOTAL HOURS OF WORK	TOTAL WORK HOURS ON JOB SITE THIS DATE
HOURS FROM PREVIOUS REPORT	TOTAL WORK HOURS FROM START OF CONSTRUCTION

MAJOR ITEMS OF EQUIPMENT

TYPE/CAPACITY	No.	STANDBY HOURS	OPERATING HOURS

THREE PHASE INSPECTION

ADVANCE NOTICE OF PREPARATORY, INITIAL OR FINAL FOLLOW-UP INSPECTION:
(Minimum five working days notice required)

PREPARATORY INSPECTION HELD TODAY:
Indicate Definable Features of Work. Attach Preparatory Checklist.

INITIAL INSPECTION HELD TODAY:
Indicate Definable Features of Work. Attach Initial Checklist.

FINAL FOLLOW-UP INSPECTION HELD TODAY:
Indicate NAS Activity Number. Attach Final Follow-up Checklist.

ACTIVITIES IN PROGRESS: Attach daily CQC follow-up inspection deficiencies/corrections noted.

ACTIVITY NUMBER	S=START C=CONTINUING F=FINISH	DESCRIPTION OF WORK ACTUALLY PERFORMED/MAJOR MATERIAL DELIVERIES TODAY

CQC TESTING

ACTIVITY NUMBER	DESCRIPTION OF TESTS PERFORMED	PASSED/FAILED

USER SCHOOLING CONDUCTED

ACTIVITY NUMBER	DESCRIPTION OF SCHOOLING

INSTALLED PROPERTY PRICING DATA ATTACHED: YES ____ NO ____

TRANSFERRED PROPERTY, DD-1149 ATTACHED: YES____ NO ____

QA COMMENTS CORRECTED TODAY: YES____ NO ____

EQUIPMENT SAFETY CHECKLIST ATTACHED: YES____ NO ____

GENERAL COMMENTS:

CONTRACTOR CERTIFICATION: On behalf of the contractor, I certify that this report is complete and correct and all equipment and material used and work performed during this reporting period are in compliance with the contract plans and specifications, to the best of my knowledge, except as noted above.

Authorized Contractor Representative: _____

Report Date: _____ Date submitted to Government Representative: _____

SAMPLE FORM

REPORT OF OPERATIONS
DREDGES
(ENG FORM 4267)

DAILY REPORT OF OPERATIONS - DREDGES

THRU:	TO:	FROM:	REPORT NO.

CHARACTER	☐ MAINTE-NANCE ☐ NEW WORK ☐ DAILY ☐ STATUS ☐ COMPLETION ☐ ANNUAL					DATE OR PERIOD	
DREDGE	NAME AND TYPE		SIZE →	PIPELINE *in. dia.*		DIPPER OR BUCKET *cu. yds.*	
	HORSEPOWER OF →	DREDGE PUMP	SUCTION PIPE JET	CUTTER OR BUCKET		PROPULSION	
	NUMBER OF CREWMEMBERS →	DREDGE / SHORE	OTHER PLANT	TOTAL	**WORK SCHEDULE** →	SHIFTS PER DAY	DAYS PER WEEK
PROJECT AND BAR	NAME		**AUTH DIMENSIONS** →	WIDTH	DEPTH	OVERDEPTH	
	LOCATION *(include station numbers)*						
CHARACTER OF MATERIAL	ABSOULTE DENSITY	IN PLACE DENSITY *GMS/Liter*		VOIDS RATIO			
	GRAIN SIZE			GEOLOGICAL CLASSIFICATION			
CONTRACT OR DREDGING ORDER	NUMBER		☐ CONTRACTO ☐ HIRED LABOR	TOTAL NO. OF DAYS IN WHICH WORK WAS DONE			
CHANNEL CONDITION	AVERAGE DEPTH →	BEFORE DREDGING	AFTER DREDGING	MINIMUM SOUNDING →	BEFORE DREDGING	AFTER DREDGING	
RIVER STAGE	MINIMUM	TIME	MAXIMUM	TIME	GAGE LOCATION		
WEATHER CONDITION	*(clear, cloudy, rain, snow, and fog)*		VISIBILITY *miles*	WIND *(maximum velocity & direction)*			

WORK PERFORMED

ITEM	UNIT	QUANTITY
AVERAGE WIDTH OF CUT	FEET	
TOTAL ADVANCE THIS PERIOD	FEET	
TOTAL ADV. PREVIOUS TO THIS	FEET	
TOTAL ADVANCE TO DATE	FEET	
FLOATING PIPE: SHORE PIPE:		
TOTAL LENGTH OF DISHARGE PIPE	FEET	
AVERAGE LIFT	FEET	
AVERAGE PUMP SPEED	R.P.M.	
AVG. DREDGED PER PUMP. HR,	CU.YDS.	
SCOWS LOADED	NUMBER	
AVERAGE LOAD PER SCOW	CU. YDS.	

CUBIC YARDS REMOVED

AMOUNT DREDGED THIS PERIOD:	
(1) GROSS *(computed amount)*	
(2) CREDITED *(pay place)*	
AMOUNT PREVIOUSLY REPORTED:	
(1) GROSS *(computed amount)*	
(2) CREDITED *(pay place)*	
TOTAL AMOUNT DREDGED TO DATE:	
(1) GROSS *(computed amount)*	
(2) CREDITED *(pay place)*	

ATTENDANT PLANT

ITEM	NAME OR NUMBER	HOURS

NUMBER OF INSPECTIONS	BY DISTRICT PERSONNEL	BY OTHER PERSONNEL
CONTRACT USE ONLY	HAS ANYTHING DEVELOPED WHICH MIGHT LEAD TO A CHANGE ORDER OR CLAIM? *(If "YES", explain under remarks on back)* ☐ NO ☐ YES	

DISTRIBUTION OF TIME

EFFECTIVE WORKING TIME *(chargeable to cost of work)*		**HOURS**	**MIN.**
PUMPING OR DREDGING			
PCT. OF EFFECTIVE RENTAL TIME			
BOOSTER *(in line)* *Hrs.*			
NON-EFFECTIVE WORKING TIME *(chargeable to cost of work)*			
HANDLING PIPE LINES			
HANDLING ANCHOR LINES			
CLEARING PUMP AND PIPE LINE			
CLEARING CUTTER OR SUCTION HEAD			
WAITING FOR SCOWS			
TO AND FROM WHARF OR ANCHORAGE			
CHANGING LOCATION OF PLANT ON JOB			
LOSS DUE TO OPPOSING NATURAL ELEMENTS			
LOSS DUE TO PASSING VESSELS			
SHORE LINE AND SHORE WORK			
WAITING FOR BOOSTER			
MINOR OPER. REPAIRS *(explain in remarks)*			
WAITING FOR ATTENDANT PLANT			
PREPERATION AND MAKING UP TOW			
TRANSFERRING PLANT BETWEEN WORKS			
LAY TIME OFF SHIFT AND SATURDAYS			
SUNDAYS AND HOLIDAYS			
FIRE DRILL			
MISCELLANEOUS *(explain in remarks)*			
TOTAL NON-EFFECTIVE WORKING TIME			
PCT. OF NON-EFFECTIVE RENTAL TIME			
TOTAL EFFECTIVE AND NON-EFFECTIVE TIME *(chargeable to cost of work)*			
PCT. OF TOTAL TIME IN PERIOD			
LOST TIME *(not chargeable to cost of work)*			
MAJOR REPAIRS AND ALTERATIONS			
CESSATION			
COLLISIONS			
MISCELLANEOUS *(explain in remarks)*			
TOTAL LOST TIME			
PERCENTAGE OF TOTAL TIME			
TOTAL TIME IN PERIOD			

ENG FORM 4267
JAN 70

REPLACES ENG FORM 28 *(Costs)*, 1 MAR 53, AND ENG FORM 29 *(Costs)*, 1 JAN 62, WHICH ARE OBSOLETE. *(ER 1125-2-304)*

(Signature and Renarks required on reverse side.)

SUMMARY OF COSTS

ITEMS	COST
DIRECT PLANT OPERATING COSTS	
UNIFORM DAILY RATE BASIS *(To be completed when submitting Status and Completion reports.)*	
CHARGES: _____ DAYS AT _____ PER DAY *(Item 19, ENG Form 22 (Costs)- adjusted to exclude plant increment cost.)* ▶ **OR** ◀	
ACTUAL PLANT COSTS *(To be completed when submiting Annual report.)*	
PAYROLLS *(gross)*.....	
SUBS~~ISTENCE &~~ QUARTERS OR ~~PER DIEM &~~ MILEAGE.....	
FUEL BARRELS AT PER BARREL.....	
WATER.....	
LUBRICANTS.....	
PLANT OWNERSHIP COSTS *(as computed below)*.....	
INSURANCE.....	
ATTENDANT PLANT.....	
MISCELLANEOUS.....	
SUBTOTAL - UNIFORM DAILY RATE OR ACTUAL	
SHORE WORK	
SUBTOTAL- SHORE WORK COSTS.....	
OTHER COSTS	
SURVEYS.....	
INSPECTION AND SUPERVISION.....	
OVERHEAD.....	
OTHER INDIRECT COSTS.....	
SUBTOTAL - OTHER COSTS.....	
~~SUBTOTAL - OTHER UNIT COST PER CUBIC YARD.~~	
GRAND TOTAL - ALL COSTS.....	

OPERATING SUPPLIES

COMMODITIES	CONSUMED		INVENTORY	
	UNIT	QUANTITY	QUANTITY	VALUE
FUEL *(oil)*	**BBLS**			
LUBRICANT *(oil)*	**GAL**			
LUBRICANT *(grease)*	**LBS**			
WATER	**GAL**			

SUBSISTENCE SUPPLIES.....	
MISCELLANEOUS SUPPLIES.....	
TOTAL.....	

ANNUAL REPORT DATA

(complete when submitting Annual report.)

	per min.
COST PER RENTAL MINUTE *(Based on total operating cost)*.....	
TOTAL COST OF PLANT *(End of F.Y. reporting period)*.....	
BOOK VAULE *(End of F.Y. reporting period)*.....	
BALANCE IN PLANT ACCOUNT *(End of F.Y. reporting period)*.....	
PLANT OWNERSHIP COSTS *(Actual for F.Y. reporting period)*:	
DEPRECIATION.....	
REPAIRS *(Adjusted)*.....	
CESSATION OF WORK.....	
SMALL TOOLS, ETC.	
TOTAL.....	

REMARKS

SUBMITTED BY *(Name, title, and signature)*	RECOMMENDED BY *(Name, title, and signature)*	APPROVED BY *(Name, title, and signature)*

(REVERSE OF ENG FORM 4267)

U.S. GOVERNMENT PRINTING OFFICE: 1970 OF-376-067

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01500

TEMPORARY CONSTRUCTION FACILITIES

12/04

PART 1 GENERAL

1.1 GENERAL REQUIREMENTS
1.1.1 Site Plan
1.1.2 Identification of Employees
1.2 AVAILABILITY AND USE OF UTILITY SERVICES
1.2.1 Utility Services
1.2.2 Telephone
1.3 CLEANUP

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION (NOT APPLICABLE)

-- End of Section Table of Contents --

SECTION 01500
TEMPORARY CONSTRUCTION FACILITIES
12/04

PART 1 GENERAL

1.1 GENERAL REQUIREMENTS

1.1.1 Site Plan

The Contractor may use the intertidal areas outside of the navigation channel for storage of materials and equipment; however, the location of such areas the Contractor may wish to utilize are subject to the approval of the Contracting Officer. Additionally, local laws and regulations may restrict the Contractor's usage of these areas within their jurisdiction and coordination is the responsibility of the Contractor. The Contractor shall prepare a site plan indicating the proposed location and dimensions of any areas to be used by the Contractor, the type of facilities to be used, avenues of ingress/egress to the areas, and details of installation. Any toilet facilities used shall be fully self-contained.

1.1.2 Identification of Employees

The Contractor shall be responsible for furnishing to each employee and for requiring each employee engaged on the work to display identification as approved and directed by the Contracting Officer. Prescribed identification shall immediately be delivered to the Contracting Officer for cancellation upon release of any employee. When required, the Contractor shall obtain and provide fingerprints of persons employed on the project. Contractor and subcontractor personnel shall wear identifying markings on hard hats clearly identifying the company for whom the employee works.

1.2 AVAILABILITY AND USE OF UTILITY SERVICES

1.2.1 Utility Services

The Contractor is informed that utility services are not available in the work area and any such use or need by the Contractor shall be at his expense.

1.2.2 Telephone

The Contractor shall make arrangements and pay all costs for telephone facilities desired.

1.3 CLEANUP

Construction debris, waste materials, packaging material and the like shall be removed from the work site daily. Any dirt or mud which is tracked onto paved or surfaced roadways shall be cleaned away. Stored material shall be neatly stacked when stored.

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION (NOT APPLICABLE)

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01525

SAFETY AND OCCUPATIONAL HEALTH REQUIREMENTS

12/04

PART 1 GENERAL

1.1 REFERENCES
1.2 SUBMITTALS
1.3 DEFINITIONS
1.4 REGULATORY REQUIREMENTS
1.5 DRUG PREVENTION PROGRAM
1.6 SITE QUALIFICATIONS, DUTIES AND MEETINGS
1.6.1 Personnel Qualifications
1.6.1.1 Site Safety and Health Officer (SSHO)
1.6.1.2 Competent Person for Confined Space Entry
1.6.2 Personnel Duties
1.6.2.1 Designated Site Safety and Health Officer (SSHO)
1.6.3 Post Award Meetings
1.6.3.1 Preconstruction Conference
1.6.3.2 Weekly Safety Meetings
1.6.3.3 Work Phase Meetings
1.7 TRAINING
1.7.1 New Employee Indoctrination
1.7.2 Periodic Training
1.7.3 Training on Activity Hazard Analysis (AHA)
1.8 ACCIDENT PREVENTION PLAN (APP)
1.8.1 EM 385-1-1 Contents
1.9 ACTIVITY HAZARD ANALYSIS (AHA)
1.10 DISPLAY OF SAFETY INFORMATION
1.11 SITE SAFETY REFERENCE MATERIALS
1.12 EMERGENCY MEDICAL TREATMENT
1.13 REPORTS
1.13.1 Accident Reports
1.13.2 Accident Notification
1.13.3 Bi-Weekly Exposure Reports
1.13.4 Regulatory Citations and Violations

PART 2 PRODUCTS (This Division Not Used.)

PART 3 EXECUTION

3.1 CONSTRUCTION WORK
3.1.1 Hazardous Material Use
3.1.2 Hazardous Material Exclusions

3.2 EQUIPMENT
3.2.1 Material Handling Equipment
3.2.2 Weight Handling Equipment
3.2.3 Equipment and Mechanized Equipment
3.3 WORK IN CONFINED SPACES
3.4 CRYSTALLINE SILICA
3.5 HOUSEKEEPING
3.5.1 Clean-Up

-- End of Section Table of Contents --

SECTION 01525

SAFETY AND OCCUPATIONAL HEALTH REQUIREMENTS
12/04

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASME INTERNATIONAL (ASME)

ASME B30.3	(1996) Construction Tower Cranes
ASME B30.5	(2000) Mobile and Locomotive Cranes
ASME B30.8	(2000) Floating Cranes and Floating Derricks
ASME B30.22	(2000) Articulating Boom Cranes

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.94	Ventilation
29 CFR 1910.146	Permit-required Confined Spaces
29 CFR 1915	Confined and Enclosed Spaces and Other Dangerous Atmospheres in Shipyard Employment

U. S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2003) Safety and Health Requirements Manual

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 10	(2002) Portable Fire Extinguishers
NFPA 241	(2000) Safeguarding Construction, Alteration, and Demolition Operations

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only or as otherwise designated. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Accident Prevention Plan (APP)

Activity Hazard Analysis (AHA)

SD-06 Test Reports

Reports

Submit reports as their incidence occurs, in accordance with the requirements of the paragraph entitled, "Reports."

Accident Reports

Monthly Exposure Reports

Regulatory Citations and Violations

1.3 DEFINITIONS

a. Competent Person for Fall Protection. A person who is capable of identifying hazardous or dangerous conditions in the personal fall arrest system or any component thereof, as well as their application and use with related equipment, and has the authority to take prompt corrective measures to eliminate the hazards of falling.

b. High Visibility Accident. Any mishap which may generate publicity or high visibility.

c. Medical Treatment. Treatment administered by a physician or by registered professional personnel under the standing orders of a physician. Medical treatment does not include first aid treatment even through provided by a physician or registered personnel.

d. Multi-Employer Work Site (MEWS). A multi-employer work site, as defined by OSHA, is one in which many employers occupy the same site. The Government considers the Prime Contractor to be the "controlling authority" for all work site safety and health of the subcontractors.

e. Recordable Injuries or Illnesses. Any work-related injury or illness that results in:

(1) Death, regardless of the time between the injury and death, or the length of the illness;

(2) Days away from work;

(3) Restricted work;

(4) Transfer to another job;

(5) Medical treatment beyond first aid;

(6) Loss of consciousness; or

(7) A significant injury or illness diagnosed by a physician or other licensed health care professional, even if it did not result in (1) through (6) above.

g. Site Safety and Health Officer (SSHO). The superintendent or other qualified or competent person who is responsible for the on-site safety and health required for the project. The Contractor quality control (QC) person can be the SSHO on this project.

1.4 REGULATORY REQUIREMENTS

In addition to the detailed requirements included in the provisions of this contract, work performed shall comply with USACE EM 385-1-1, and the applicable federal, state, and local laws, ordinances, criteria, rules and regulations governing the work. Submit matters of interpretation of standards to the appropriate administrative agency for resolution before starting work. Where the requirements of this specification, applicable laws, criteria, ordinances, regulations, and referenced documents vary, the most stringent requirements shall apply.

1.5 DRUG PREVENTION PROGRAM

Conduct a proactive drug and alcohol use prevention program for all workers, prime and subcontractor, on the site. Ensure that no employee uses illegal drugs or consumes alcohol during work hours. Ensure there are no employees under the influence of drugs or alcohol during work hours. After accidents, collect blood, urine, or saliva specimens and test the injured and involved employees for the influence of drugs and alcohol. A copy of the test shall be made available to the Contracting Officer upon request.

1.6 SITE QUALIFICATIONS, DUTIES AND MEETINGS

1.6.1 Personnel Qualifications

1.6.1.1 Site Safety and Health Officer (SSHO)

Site Safety and Health Officer (SSHO) shall be provided at the work site at all times to perform safety and occupational health management, surveillance, inspections, and safety enforcement for the Contractor. The SSHO shall meet the following requirements:

a. A minimum of 5 years safety work on similar projects.

b. 30-hour OSHA construction safety class or equivalent within the last 5 years.
c. An average of at least 24 hours of formal safety training each year for the past 5 years.
d. Competent person training as needed.

1.6.1.2 Competent Person for Confined Space Entry

Provide a competent person meeting the requirements of EM 385-1-1 who is assigned in writing by the Designated Authority to assess confined spaces and who possesses demonstrated knowledge, skill and ability to:

a. Identify the structure, location, and designation of confined and permit-required confined spaces where work is done;

b. Calibrate and use testing equipment including but not limited to, oxygen indicators, combustible gas indicators, carbon monoxide indicators, and carbon dioxide indicators, and to interpret accurately the test results of that equipment;

c. Perform all required tests and inspections specified in 29 CFR 1910.146 and 29 CFR 1915 Subpart B;

d. Assess hazardous conditions including atmospheric hazards in confined space and adjacent spaces and specify the necessary protection and precautions to be taken;

e. Determine ventilation requirements for confined space entries and operations;

f. Assess hazards associated with hot work in confined and adjacent space and determine fire watch requirements; and,

g. Maintain records required.

1.6.2 Personnel Duties

1.6.2.1 Designated Site Safety and Health Officer (SSHO)

a. Conduct daily safety and health inspections and maintain a written log which includes area/operation inspected, date of inspection, identified hazards, recommended corrective actions, estimated and actual dates of corrections. Safety inspection logs shall be attached to the Contractors' daily quality control report.

b. Conduct mishap investigations and complete required reports. Maintain the OSHA Form 300 and Daily Production reports for prime and sub-contractors.

c. Maintain applicable safety reference material on the job site.

d. Attend the pre-construction conference, pre-work meetings including preparatory inspection meeting, and periodic in-progress meetings.

e. Implement and enforce accepted APPS and AHAs.

f. Maintain a safety and health deficiency tracking system that monitors outstanding deficiencies until resolution. A list of unresolved safety and health deficiencies shall be posted at an area frequented by all wokers as acceptable by the COR.

g. Ensure sub-contractor compliance with safety and health requirements.

Failure to perform the above duties will result in dismissal of the designated SSHO, and a project work stoppage. The project work stoppage will remain in effect pending approval of a suitable replacement.

1.6.3 Post Award Meetings

1.6.3.1 Preconstruction Conference

a. The Contractor will be informed, in writing, of the date of the preconstruction conference. The purpose of the preconstruction conference is for the Contractor and the Contracting Officer's representatives to become acquainted and explain the functions and operating procedures of their respective organizations and to reach mutual understanding relative to the administration of the overall project's Accident Prevention Plan (APP) before the initiation of work.

b. Contractor representatives who have a responsibility or significant role in accident prevention on the project shall attend the preconstruction conference. This includes the project superintendent, site safety and health officer, quality control supervisor, or any other assigned safety and health professionals who participated in the development of the APP (including the Activity Hazard Analyses (AHAs) and special plans, program and procedures associated with it).

c. The Contractor shall discuss the details of the submitted APP to include incorporated plans, programs, procedures and a listing of anticipated AHAs that will be developed and implemented during the performance of the contract. This list of proposed AHAs will be reviewed at the conference and an agreement will be reached between the Contractor and the Contracting Officer's representative as to which phases will require an analysis. In addition, a schedule for the preparation, submittal, review, and acceptance of AHAs shall be established to preclude project delays.

d. Deficiencies in the submitted APP will be brought to the attention of the Contractor at the preconstruction conference, and the Contractor shall revise the plan to correct deficiencies and re-submit it for acceptance. Work shall not begin until there is an accepted APP.

1.6.3.2 Weekly Safety Meetings

Conduct weekly safety meetings at the project site for all employees. The Contracting Officer will be informed of the meeting in advance and be allowed attendance. Minutes showing contract title, signatures of

attendees and a list of topics discussed shall be attached to the Contractors' daily quality control report.

1.6.3.3 Work Phase Meetings

The appropriate AHA shall be reviewed and attendance documented by the Contractor at the preparatory, initial, and follow-up phases of quality control inspection. The analysis should be used during daily inspections to ensure the implementation and effectiveness of safety and health controls.

1.7 TRAINING

1.7.1 New Employee Indoctrination

New employees (prime and sub-contractor) shall be informed of specific site hazards before they begin work. Documentation of this orientation shall be kept on file at the project site.

1.7.2 Periodic Training

Provide Safety and Health Training in accordance with USACE EM 385-1-1 and the accepted APP. Ensure all required training has been accomplished for all onsite employees.

1.7.3 Training on Activity Hazard Analysis (AHA)

Prior to beginning a new phase, training will be provided to all affected employees to include a review of the AHA to be implemented.

1.8 ACCIDENT PREVENTION PLAN (APP)

The Contractor shall use a qualified person to prepare the written site-specific APP. Prepare the APP in accordance with the format and requirements of USACE EM 385-1-1 and as supplemented herein. Cover all paragraph and subparagraph elements in USACE EM 385-1-1, Appendix A, "Minimum Basic Outline for Preparation of Accident Prevention Plan". Where a paragraph or subparagraph element is not applicable to the work to be performed indicate "Not Applicable" next to the heading. Specific requirements for some of the APP elements are described below. The APP shall be job-specific and shall address any unusual or unique aspects of the project or activity for which it is written. The APP shall interface with the Contractor's overall safety and health program. Any portions of the Contractor's overall safety and health program referenced in the APP shall be included in the applicable APP element and made site-specific. The Government considers the Prime Contractor to be the "controlling authority" for all work site safety and health of the subcontractors. Contractors are responsible for informing their subcontractors of the safety provisions under the terms of the contract and the penalties for noncompliance, coordinating the work to prevent one craft from interfering with or creating hazardous working conditions for other crafts, and inspecting subcontractor operations to ensure that accident prevention responsibilities are being carried out. The APP shall be signed by the person and firm (senior person) preparing the APP, the Contractor, the on-site superintendent, and the designated site safety and health officer.

Submit the APP to the Contracting Officer 15 calendar days prior to the date of the preconstruction conference for acceptance. Work cannot proceed without an accepted APP. The Contracting Officer reviews and comments on the Contractor's submitted APP and accepts it when it meets the requirements of the contract provisions.

Once accepted by the Contracting Officer, the APP and attachments will be enforced as part of the contract. Disregarding the provisions of this contract or the accepted APP will be cause for stopping of work, at the discretion of the Contracting Officer, until the matter has been rectified.

Once work begins, changes to the accepted APP shall be made with the knowledge and concurrence of the Contracting Officer, project superintendent, SSHO and quality control manager. Should any unforeseen hazard become evident during the performance of work, the project superintendent shall inform the Contracting Officer, both verbally and in writing, for resolution as soon as possible. In the interim, all necessary action shall be taken by the Contractor to restore and maintain safe working conditions in order to safeguard onsite personnel, visitors, the public, and the environment.

Copies of the accepted plan will be maintained by the Contracting Officer and at the job site. The APP shall be continuously reviewed and amended, as necessary, throughout the life of the contract. Unusual or high-hazard activities not identified in the original APP shall be incorporated in the plan as they are discovered.

1.8.1 EM 385-1-1 Contents

In addition to the requirements outlines in Appendix A of USACE EM 385-1-1, the following is required:

a. Names and qualifications (resumes including education, training, experience and certifications) of all site safety and health personnel designated to perform work on this project to include the designated site safety and health officer and other competent and qualified personnel to be used such as CSPs. The duties of each position shall be specified.

b. Qualifications of competent and of qualified persons. As a minimum, competent persons shall be designated and qualifications submitted for each of the following major areas: confined space; health hazard recognition, personal protective equipment and clothing to include selection, use and maintenance.

c. Health Hazard Control Program. The Contractor shall designate a competent and qualified person to establish and oversee a Health Hazard Control Program in accordance with USACE EM 385-1-1, Section 6. The program shall ensure that employees, on-site Government representatives, and others, are not adversely exposed to chemical, physical and biological agents and that necessary controls and protective actions are instituted to ensure health.

d. Alcohol and Drug Abuse Plan

(1) Describe plan for random checks and testing with pre-employment screening in accordance with the DFAR Clause subpart 252.223-7004, "Drug Free Work Force."

(2) Description of the on-site prevention program

e. Training Records and Requirements. List of mandatory training and certifications which are applicable to this project (e.g. explosive actuated tools, confined space entry, fall protection, dredge and boat operation, vehicle operator, forklift operators, personal protective equipment); list of requirements for periodic retraining/certification; outline requirements for supervisory and employee safety meetings.

1.9 ACTIVITY HAZARD ANALYSIS (AHA)

The Activity Hazard Analysis (AHA) format shall be in accordance with USACE EM 385-1-1. Submit the AHA for review at least 15 calendar days prior to the start of each phase. Format subsequent AHA as amendments to the APP. An AHA will be developed by the Contractor for every operation involving a type of work presenting hazards not experienced in previous project operations or where a new work crew or subcontractor is to perform work. The analysis must identify and evaluate hazards and outline the proposed methods and techniques for the safe completion of each phase of work. At a minimum, define activity being performed, sequence of work, specific safety and health hazards anticipated, control measures (to include personal protective equipment) to eliminate or reduce each hazard to acceptable levels, equipment to be used, inspection requirements, training requirements for all involved, and the competent person in charge of that phase of work. For work with fall hazards, including fall hazards associated with safety railings and lifelines, identify the appropriate fall protection methods used. For work with pipelines and other floating plant/equipment, address safeguarding measures related to each item of plant/equipment. An activity requiring an AHA shall not proceed until the AHA has been accepted by the Contracting Officer's representative and a meeting has been conducted by the Contractor to discuss its contents with everyone engaged in the activity, including on-site Government representatives. The Contractor shall document meeting attendance at the preparatory, initial, and follow-up phases of quality control inspection. The AHA shall be continuously reviewed and, when appropriate, modified to address changing site conditions or operations. The analysis should be used during daily inspections to ensure the implementation and effectiveness of the activity's safety and health controls.

The AHA list will be reviewed periodically (at least bi-weekly) at the Contractor supervisory safety meeting and updated as necessary when procedures, scheduling, or hazards change.

Activity hazard analyses shall be updated as necessary to provide an effective response to changing work conditions and activities. The on-site superintendent, site safety and health officer and competent persons used to develop the AHAs, including updates, shall sign and date the AHAs before they are implemented.

1.10 DISPLAY OF SAFETY INFORMATION

Prior to commencement of any work, the Contractor shall designate for approval a location frequented by all emplyees in clear view to display safety information. The following information shall be displayed at this location, maintained current, and protected against the elements and unauthorized removal for the duration of the contract:

a. Map denoting the route to the nearest emergency care facility.

b. Emergency phone numbers.

c. Copy of the most up-to-date APP.

d. Current AHA(s).

e. OSHA 300A Form.

f. OSHA Safety and Health Protection-On-The-Job Poster.

1.11 SITE SAFETY REFERENCE MATERIALS

Maintain safety-related references applicable to the project, including those listed in the article "References." Maintain applicable equipment manufacturer's manuals.

1.12 EMERGENCY MEDICAL TREATMENT

Contractors will arrange for their own emergency medical treatment. Government has no responsibility to provide emergency medical treatment.

1.13 REPORTS

1.13.1 Accident Reports

a. For recordable injuries and illnesses, and property damage accidents resulting in at least $2,000 in damages, the Prime Contractor shall conduct an accident investigation to establish the root cause(s) of the accident, complete the USACE Accident Report Form 3394] and provide the report to the Contracting Officer within 1 calendar day of the accident. The Contracting Officer will provide copies of any required or special forms.

1.13.2 Accident Notification

Notify the Contracting Officer as soon as practical, but not later than four hours, after any accident meeting the definition of Recordable Injuries or Illnesses or High Visibility Accidents, property damage equal to or greater than $2,000. Information shall include contractor name; contract title; type of contract; name of activity, installation or location where accident occurred; date and time of accident; names of personnel injured; extent of property damage, if any; extent of injury, if known, and brief description of accident (to include type of construction

equipment used, PPE used, etc.). Preserve the conditions and evidence on the accident site until the Government investigation team arrives on-site and Government investigation is conducted.

1.13.3 Bi-Weekly Exposure Reports

Bi-weekly exposure reporting to the Contracting Officer is required to be attached to the daily report of operations. This report is a compilation of employee-hours worked each month for all site workers, both prime and subcontractor. The Contracting Officer will provide copies of any special forms.

1.13.4 Regulatory Citations and Violations

Contact the Contracting Officer immediately of any OSHA or other regulatory agency inspection or visit, and provide the Contracting Officer with a copy of each citation, report, and contractor response. Correct violations and citations promptly and provide written corrective actions to the Contracting Officer.

PART 2 PRODUCTS (This Division Not Used.)

PART 3 EXECUTION

3.1 CONSTRUCTION WORK

The Contractor shall comply with USACE EM 385-1-1, NFPA 241, the APP, the AHA, Federal and State OSHA regulations, and other related submittals and activity fire and safety regulations. The most stringent standard shall prevail.

3.1.1 Hazardous Material Use

Any work or storage involving hazardous chemicals or materials must be done in a manner that will not expose Government or Contractor employees to any unsafe or unhealthful conditions. Adequate protective measures must be taken to prevent Government or Contractor employees from being exposed to any hazardous condition that could result from the work or storage. The Prime Contractor shall keep a complete inventory of hazardous materials brought onto the work-site. Approval by the Contracting Officer of protective measures and storage area is required prior to the start of the work.

3.1.2 Hazardous Material Exclusions

Notwithstanding any other hazardous material used in this contract, radioactive materials or instruments capable of producing ionizing/non-ionizing radiation (with the exception of radioactive material and devices used in accordance with USACE EM 385-1-1 such as nuclear density meters for compaction testing and laboratory equipment with radioactive sources) as well as materials which contain asbestos, mercury or polychlorinated biphenyls, di-isocynates, lead-based paint are prohibited. The Contracting Officer, upon written request by the Contractor, may consider exceptions to the use of any of the above excluded

materials.

3.2 EQUIPMENT

3.2.1 Material Handling Equipment

a. Material handling equipment such as forklifts shall not be modified with work platform attachments for supporting employees unless specifically delineated in the manufacturer's printed operating instructions.

b. The use of hooks on equipment for lifting of material must be in accordance with manufacturer's printed instructions.

c. Operators of forklifts or power industrial trucks shall be licensed in accordance with OSHA.

3.2.2 Weight Handling Equipment

b. The Contractor shall notify the Contracting Officer 15 days in advance of any cranes entering the activity so that necessary quality assurance spot checks can be coordinated. Contractor's operator shall remain with the crane during the spot check.

c. The Contractor shall comply with the crane manufacturer's specifications and limitations for erection and operation of cranes and hoists used in support of the work. Erection shall be performed under the supervision of a designated person (as defined in ASME B30.5). All testing shall be performed in accordance with the manufacturer's recommended procedures.

d. The Contractor shall comply with ASME B30.5 for mobile and locomotive cranes, ASME B30.22 for articulating boom cranes, ASME B30.3 for construction tower cranes, and ASME B30.8 for floating cranes and floating derricks.

e. The presence of Government personnel does not relieve the Contractor of an obligation to comply with all applicable safety regulations. The Government will investigate all complaints of unsafe or unhealthful working conditions received in writing from contractor employees, federal civilian employees, or military personnel.

f. Each load shall be rigged/attached independently to the hook/master-link in such a fashion that the load cannot slide or otherwise become detached. Christmas-tree lifting (multiple rigged materials) is not allowed.

h. When operating in the vicinity of overhead transmission lines, operators and riggers shall be alert to this special hazard and shall follow the requirements of USACE EM 385-1-1 section 11 and ASME B30.5 or ASME B30.22 as applicable.

i. Crane suspended personnel work platforms (baskets) shall not be used unless the Contractor proves that using any other access to the

work location would provide a greater hazard to the workers or is impossible. Personnel shall not be lifted with a line hoist or friction crane.

j. A fire extinguisher having a minimum rating of 10BC and a minimum nominal capacity of 5lb of extinguishing agent shall be available at all operator stations or crane cabs. Portable fire extinguishers shall be inspected, maintained, and recharged as specified in NFPA 10, Standard for Portable Fire Extinguishers.

k. All employees shall be kept clear of loads about to be lifted and of suspended loads.

l. A weight handling equipment operator shall not leave his position at the controls while a load is suspended.

m. The Contractor shall use cribbing when performing lifts on outriggers.

n. The crane hook/block must be positioned directly over the load. Side loading of the crane is prohibited.

o. A physical barricade must be positioned to prevent personnel from entering the counterweight swing (tail swing) area of the crane.

p. A substantial and durable rating chart containing legible letters and figures shall be provided with each crane and securely mounted onto the crane cab in a location allowing easy reading by the operator while seated in the control station.

q. Certification records which include the date of inspection, signature of the person performing the inspection, and the serial number or other identifier of the crane that was inspected shall always be available for review by Contracting Officer personnel.

r. Written reports listing the load test procedures used along with any repairs or alterations performed on the crane shall be available for review by Contracting Officer personnel.

s. The Contractor shall certify that all crane operators have been trained in proper use of all safety devices (e.g. anti-two block devices).

3.2.3 Equipment and Mechanized Equipment

a. Equipment shall be operated by designated qualified operators. Proof of qualifications shall be kept on the project site for review.

b. Manufacturer's specifications or owner's manual for the equipment shall be on-site and reviewed for additional safety precautions or requirements that are sometimes not identified by OSHA or USACE EM 385-1-1. Such additional safety precautions or requirements shall be incorporated into the AHAs.

c. Equipment and mechanized equipment shall be inspected in accordance with manufacturer's recommendations for safe operation by a competent person prior to being placed into use.

d. Daily checks or tests shall be conducted and documented on equipment and mechanized equipment by designated competent persons.

3.3 WORK IN CONFINED SPACES

The Contractor shall comply with the requirements in Section 06.I of USACE EM 385-1-1 and OSHA 29 CFR 1910.146. Any potential for a hazard in the confined space requires a permit system to be used.

a. Entry Procedures. Prohibit entry into a confined space by personnel for any purpose, until the qualified person has conducted appropriate tests to ensure the confined or enclosed space is safe for the work intended and that all potential hazards are controlled or eliminated and documented. (See Section 06.I.05 of USACE EM 385-1-1 for entry procedures.) All hazards pertaining to the space shall be reviewed with each employee during review of the AHA.

b. Forced air ventilation is required for all confined space entry operations and the minimum air exchange requirements must be maintained to ensure exposure to any hazardous atmosphere is kept below its' action level.

c. Ensure the use of rescue and retrieval devices in confined spaces greater than 1.5 m (5 feet) in depth. Conform to Sections 06.I.09, 06.I.10 and 06.I.11 of USACE EM 385-1-1.

d. Sewer wet wells require continuous atmosphere monitoring with audible alarm for toxic gas detection.

e. Include training information for employees who will be involved as entrants and attendants for the work. Conform to Section 06.I.06 of USACE EM 385-1-1.

f. Daily Entry Permit. Post the permit in a conspicuous place close to the confined space entrance.

3.4 CRYSTALLINE SILICA

Grinding, abrasive blasting, and foundry operations of construction materials containing crystalline silica, shall comply with OSHA regulations, such as 29 CFR 1910.94, and USACE EM 385-1-1, Appendix C. The Contractor shall develop and implement effective exposure control and elimination procedures to include dust control systems, engineering controls, and establishment of work area boundaries, as well as medical surveillance, training, air monitoring, and personal protective equipment.

3.5 HOUSEKEEPING

3.5.1 Clean-Up

All debris in work areas shall be cleaned up daily or more frequently if necessary. Construction debris may be temporarily located in an approved location, however garbage accumulation must be removed each day.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01850

DRAWING INDEX

12/04

PART 1 GENERAL

1.1 INDEX OF CONTRACT DRAWINGS

PART 2 PRODUCTS (This Division not used)

PART 3 EXECUTION (This Division not used)

-- End of Section Table of Contents --

SECTION 01850

DRAWING INDEX
12/04

PART 1 GENERAL

1.1 INDEX OF CONTRACT DRAWINGS

The list of drawings below are included as a part to this Solicitation.

Norfolk District File No.	Title
H-23-14-130(1)	TITLE SHEET
H-23-14-130(2)	MAPPING SHEET
H-23-14-130(3)	MAPPING SHEET
H-23-14-130(4)	MAPPING SHEET
H-23-14-130(5)	MAPPING SHEET
H-23-14-130(6)	MAPPING SHEET
H-23-14-130(7)	MAPPING SHEET
H-23-14-130(8)	MAPPING SHEET
H-23-14-130(9)	MAPPING SHEET
H-23-14-130(10)	MAPPING SHEET
H-23-14-130(11)	MAPPING SHEET
H-23-14-130(12)	MAPPING SHEET
H-23-14-130(13)	MAPPING SHEET
H-23-14-130(14)	MAPPING SHEET
H-23-14-130(15)	DETAIL SHEET

PART 2 PRODUCTS (This Division not used)

PART 3 EXECUTION (This Division not used)

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 02 - SITE CONSTRUCTION

SECTION 02325

DREDGING

12/04

PART 1 GENERAL

1.1 SUBMITTALS
1.2 References
1.3 PLANT
1.4 CHARACTER OF MATERIALS
1.5 OBSTRUCTION IDENTIFICATION

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION

3.1 REMOVAL AND PLACEMENT OF EXCAVATED MATERIAL AND REQUIREMENTS FOR USE OF GOVERNMENT FURNISHED PLACEMENT AREAS
3.1.1 General Information
3.1.2 Government Furnished Upland Placement Area
3.1.3 Placement Area Use and Maintenance During Placement Operations
3.1.4 Government Furnished Beach Placement Areas
3.1.5 Watches at Beach Placement Areas
3.1.6 Warning Signs
3.1.7 Examination of Pipeline
3.1.8 Misplaced Material
3.2 REQUIRED DREDGING PRISM, OVERDEPTH, AND SIDE SLOPES
3.2.1 Required Dredging Prism
3.2.2 Overdepth
3.2.3 Side Slopes
3.3 QUALITY CONTROL FOR HYDROGRAPHIC SURVEYS AND SURVEY EQUIPMENT
3.3.1 Basis of Surveys

-- End of Section Table of Contents --

SECTION 02325

DREDGING
12/04

PART 1 GENERAL

1.1 SUBMITTALS

The Contractor shall make submittals for the following listed reports and certificates as required by the specifications. The Contracting Officer may request submittals in addition to those specified when deemed necessary to adequately describe the work. Units of weights and measures used on all submittals shall be the same as those used in the contract drawings. Each submittal shall be complete and in sufficient detail to allow ready determination of compliance with contract requirements. Prior to submittal, all items shall be checked and approved by the Contractor's Quality Control (CQC) representative and each item shall be stamped, signed, and dated by the CQC representative indicating action taken in accordance with SECTION 01451. Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-07 Certificates

Equipment and Machinery Operator Authorization

The Contractor shall submit a list of designated personnel qualified and authorized to operate machinery and equipment. The list shall be maintained at the job site in a current status at all times.

1.2 References

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

ENGINEERING MANUALS

EM 385-1-1	(2003) Safety and Health Requirements Manual
EM 1110-2-1003	(2002) Hydrographic Surveying Manual

1.3 PLANT

Plant and equipment employed on the dredging work shall be in satisfactory operating condition, capable of safely and efficiently performing the work as indicated or specified, and shall be subject to inspection and approval

by the Government at all times. A complete listing of all dredging plant and machinery to be used in the work, including booster pumps, skiffs, barges, and other related equipment, shall be submitted. The listing shall include year and manufacturer, operational capacities, safety features, operating and licensing requirements for operators, and a description where and how the item of equipment or plant will be employed in the work. All floating plant and pipelines used as access ways or working platforms shall be equipped with walkways and guardrails conforming to Corps of Engineers Manual EM 385-1-1 and meet OSHA requirements for worker safety. All buoyant (plastic) dredge pipelines that are used on this contract shall be weighted or anchored securely to the bottom so that the pipeline will stay on the bottom, and marked with floats or buoys during daylight and amber lights during darkness to mark distinctly the entire length and course of the line.

1.4 CHARACTER OF MATERIALS

The material to be removed is the shoaling that has occurred since the Entrance Channel, Turning Basin, Narrows Channel to Broad Bay, and Long Creek Side Channel were last dredged. Bidders are expected to examine the site of work and decide for themselves the character of the materials. The records of previous dredging are available in the Operations Branch at the Norfolk District. The Government does not warrant the accuracy of the records of previous dredging. Local minor variations in the subsurface materials are to be expected and, if encountered, will not be considered as being materially different within the purview of Contract Clause "DIFFERING SITE CONDITIONS".

1.5 OBSTRUCTION IDENTIFICATION

The Contractor may encounter obstructions or other debris that is not identified and may pose a hazard to navigation. The Contractor shall advise the Contracting Officer immediately of any obstructions or other debris of this nature that is encountered.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION

3.1 REMOVAL AND PLACEMENT OF EXCAVATED MATERIAL AND REQUIREMENTS FOR USE OF GOVERNMENT FURNISHED PLACEMENT AREAS

3.1.1 General Information

The Contractor shall dredge and transport material by hydraulic dredge and pipeline to the designated placement area for each respective dredging area as indicated and specified. The Contractor shall protect all existing wetlands, marsh grasses, and adjacent structures in the vicinity of his activities for the duration of the contract. The dredge pipeline shall be placed and advanced in a manner to traverse and disturb native vegetation, dunes, marsh and wetlands to the minimum amount practicable. Ingress and egress of personnel and equipment across marsh and wetlands areas shall be scheduled to coincide with high tide to the maximum extent practicable. The condition of the dredging and placement areas, at the time of the latest survey, are depicted on the contract drawings; however, due to

natural changes in topography, the actual elevations at the time of the work may vary from the elevations indicated. The Contractor shall immediately suspend dredging and placement operations in the event of any dike or containment failure, gullying or eroding of existing soil materials, or any other such failure. The Contractor may resume work only when such failures have been corrected. The Contractor may be required to recover at no additional cost to the Government any material improperly placed in the beach placement areas or as a result of dike or containment failures. Damages and claims due to any failure of the dike due to construction error or negligence in operations is the responsibility of the Contractor. The required placement area for each respective dredging area is as follows

(a) Entrance Channel - Ocean Park Beach Placement Area
(b) Mooring and Turning Basin - Ocean Park Beach Placement Area
(c) Long Creek Side Channel - Ocean Park Beach Placement Area
(d) Narrows Channel - 64th Street Beach Placement Area
(d) Channel to Broad Bay - Maple Street Upland Placement Area.

3.1.2 Government Furnished Upland Placement Area

The interior and exterior of the placement area, dikes, spillboxes and associated piping are expected to be adequate for the placement of dredged material proposed in this contract; however, the Contractor is responsible to insure all portions of the placement area, dikes, drainage piping and spillboxes are adequate and in proper working order before commencement of placement operations. Any required clearing or grading of the interior or exterior of the placement area, repairs to dikes or spillboxes and associated drainage piping, clearing of debris from spillboxes or piping, and replacement of weir boards is the Contractor's responsibility and shall be provided at no additional cost to the Government with all associated costs for these items included as part of the Contractor's mobilization expenses. All materials repaired or replaced shall be in sizes and type to match existing as approved by the Contracting Officer. All trash and debris shall be removed and disposed in approved landfills at the Contractor's expense. Prior to commencing dredging operations, the weir boards shall be set at a height to assure a minimum ponding depth within the placement area of two feet measured at the spill box. Additionally, for the duration of the contract the Contractor shall be responsible to maintain the placement area dikes and operate the spillbox by keeping spillway weirs at the correct level and free of trash and debris at all times to maintain:

(1) the minimum required ponding level;
(2) specified freeboard; and
(3) specified effluent and other water-quality standards.

3.1.3 Placement Area Use and Maintenance During Placement Operations

The Contractor shall install a baffle plate, spreader pipes, pocket pipes, or other approved apparatus to the discharge end of the dredge pipeline to prevent scour and washouts within the dike and at the dredge pipe outfall. The Contractor shall employ proper dredging and placement methods to ensure that adequate ponding depth is maintained and that a minimum of two feet of freeboard, measured at the minimum containment dike elevation, is

maintained at all times. The contractor shall immediately notify the COR if the freeboard drops below four-feet. The Contractor shall immediately suspend dredging and placement operations in the event of any containment dike failure, if dikes are being scoured by dredging, or if dike failure appears to be imminent. The Contractor may resume work only after suitable permanent repairs to the containment dike have been made. The Contractor shall provide at least one qualified employee during daylight and at least two qualified employees at night to monitor the Contractor's dredged material placement operations, including but not limited to the discharge of material, level of ponding, freeboard, condition of the dikes, and release of effluent from the Placement Area. The number of employees is expressed as a minimum; accordingly, the Contractor is responsible to provide at his expense the number of employees required to accomplish all work as indicated and specified. If during observance of his work the Contracting Officer determines the Contractor’s staff on site to be insufficient, additional employees in a number as directed by the Contracting Officer will be provided by the Contractor at his expense. Any damages that result from the negligence of the Contractor to properly manage the dredged material placement and properly maintain the containment dikes shall be fully repaired by the Contractor at his own expense. The Contractor shall leave the placement site in a well maintained condition. The spillbox shall be well maintained with the boards at the correct level and free of trash and debris at all times. During the progress of the work the Contractor shall perform grading and ditching as necessary to eliminate undrained areas within the containment area. At the completion of the scheduled work, the Contractor shall leave the spillbox in a well-maintained and operable condition to assure adequate site drainage.

3.1.4 Government Furnished Beach Placement Areas

The Contractor shall place the excavated material to the lines and grades indicated on the drawings for each respective dredging area, subject to such minor modifications as deemed necessary by the Contracting Officer to accommodate natural changes and variations in the beach that may have occurred since the drawings were prepared. The beach is subject to natural changes and the actual elevations at the time of the work may vary from the elevations shown on the contract drawings. The Contractor shall protect from damage all existing sand dunes and maintain in place any existing beach material that is above the required placement elevation for this contract. The Contractor shall not borrow material or grade material from these areas or disturb vegetation on dunes. The operation and movement of vehicles, equipment and personnel on, over, or across sand dunes is specifically prohibited except at crossing points that have been approved by the Contracting Officer. The Contractor shall install a baffle plate, spreader pipes, pocket pipes, or other approved apparatus to the discharge end of the pipeline that precisely controls the placement of the beach fill material and increases the settlement rate of the material to the maximum extent practicable. Temporary longitudinal control dikes shall be constructed in a manner that requires the effluent water to travel a minimum distance of 200 feet, measured horizontally, prior to returning to the nearby waters. Such longitudinal dikes and outfall devices shall be used to prevent transverse gullying and erosion at the point of deposit and the subsequent loss of material directly into the nearby waters. Once the material has been deposited, the Contractor shall distribute and grade the

material to the lines and elevations as indicated and specified for the respective Placement Area. The final graded beach fill segments shall be constructed to an acceptable tolerance of 0.5 foot above or 0.5 foot below the required elevation and specified grade. The Contractor shall not place material in such a manner as to encroach landward of the existing sand dunes or manmade structures or lines indicated or as may be identified by the Contracting Officer.

3.1.5 Watches at Beach Placement Areas

During dredging operations, the Contractor shall provide qualified personnel 24-hours per day at the discharge area. Monitoring personnel shall be qualified to monitor the Contractor's operations at the Placement Area, including but not limited to the discharge of material, level of ponding, freeboard, condition of the dikes, and release of effluent from the Placement Area. The monitoring personnel shall have fully functional two-way radio communications with the dredge operator at all times when dredging is in progress. At all times during discharge of material on the beach and from sunset to sunrise at the upland placement area, at least 2 watch persons shall be assigned on watch duty with whistles, flashlights, and two-way radio communication with the dredge and equipment operators on the beach, as applicable. During material palcement operations at the beach placement area, watch men shall be stationed at each side of the discharge pipeline in close proximity to the immediate placement area. In addition to the monitoring responsibilites indicated above, the watch men shall be responsible to keep the public out of the work area around the discharge pipeline. In the event that an unauthorized person(s) enters the work area, all work shall immediately stop until the person(s) has been removed from the work area. Work shall not be performed unless the designated watch persons are on site. Frequent communication checks shall be made to assure proper material placement during dredging operations. In the event of any communications failure or improper material placement is determined, all dredging and placement operations shall be immediately suspended until communications are restored as approved by the Contracting Officer, or in the event of improper material placement, until proper material placement procedures are reestablished by the Contractor as approved by the Contracting Officer. All costs resulting from suspensions of work as specified above shall be the responsibility of the Contractor and at no additional expense to the Government.

3.1.6 Warning Signs

The Contractor shall erect and maintain at his own expense suitable navigation warning signs at each end of a submerged pipeline and at any other points necessary to prevent hazards to navigation.

3.1.7 Examination of Pipeline

The pipeline, including connections used for a submerged line, shall be examined and determined to be in good condition to reasonably expect it to last throughout the job without wearing to the extent of allowing leaks. In the event that leaks occur anywhere in the pipeline, the Contractor will be required to immediately discontinue using the respective equipment until the leaks are stopped. The Contractor shall also be required to recover at

no cost to the Government any material improperly placed because of a leak or leaks in the equipment.

3.1.8 Misplaced Material

The requirements and methods of dredged material placement for this contract has been planned in accordance with Environmental Permits obtained by the Government for the scheduled work. Any material that is deposited elsewhere than in places designated or in a manner than approved by the Contracting Officer is in violation of the Environmental Permits and will not be paid for. Additionally, the Contractor may be required to remove such misplaced material and deposit it where directed by the Contracting Officer at the Contractor's expense and be subject to an unsatisfactory performance rating by the Contracting Officer.

3.2 REQUIRED DREDGING PRISM, OVERDEPTH, AND SIDE SLOPES

3.2.1 Required Dredging Prism

Within the specific areas indicated to be dredged or areas approved by the Contracting Officer, the required dredging prism is defined by the required depths and applicable side slopes as indicated and specified. The actual quantity within the required dredging prism will be computed from the last surveys made before dredging.

3.2.2 Overdepth

To cover inaccuracies of the dredging process, material actually removed from within the specific areas to be dredged to a depth of not more than one foot below the required depth will be estimated and paid for at the contract price.

3.2.3 Side Slopes

Material actually removed, within limits approved by the Contracting Officer, to provide for final side slopes not flatter than 1 vertical on 3 horizontal, but not in excess of the amount originally lying above this limiting side slope, will be estimated and paid for, whether dredged in original position or by dredging space below the pay slope plane at the bottom of the slope for upslope material capable of falling into the cut. In computing the limiting amount of side-slope dredging an overdepth of one foot measured vertically will be used.

3.3 QUALITY CONTROL FOR HYDROGRAPHIC SURVEYS AND SURVEY EQUIPMENT

Hydrographic surveys will be conducted to meet USACE Performance Standards as defined in the Hydrographic Surveying Manual EM 1110-2-1003. Surveys will be performed by single transducer sounding techniques, multi-beam sweep type surveys, or a combination of both at the discretion of the Government. Bottom soundings will be obtained by the single beam survey fathometer operating at a frequency ranging from 190 to 210 Khz. When utilizing multi-beam technology, the operating frequency will range from 180 to 250 khz. All fathometers will be calibrated following procedures outlined in the Hydrographic Surveying Manual EM 1110-2-1003.

3.3.1 Basis of Surveys

The Government hydrographic surveys shall be the sole basis for determining payment for dredging and final acceptance.

-- End of Section --